# NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

NORTH TERMINAL EXPANSION / IMPROVEMENTS



RENDERING IS A GRAPHIC DEPICTION FOR GENERAL REFERENCE ONLY AND NOT TO BE USED TO DETERMINE MATERIALS, QUANTITIES, OR DIMENSIONS.

**PERMIT DOCUMENTS**

1

## BOARD OF DIRECTORS

GLEN MCDONALD, CHAIR
HOLLY K. MELZER, ESQ., VICE CHAIR
WILL CRAMER, MEMBER
BRIAN KELLENBERGER, MEMBER
JAMES JOHNSON, MEMBER
LES MCFATTER, MEMBER
MAYOR MARK SHELDON, MEMBER

## DRAWING INDEX


GENERAL
G-0.0.0 COVER SHEET
G-0.0.1 NOTES, SYMBOLS, & ABBREVIATIONS
G-0.0.2 BUILDING CODE INFORMATION
G-0.0.3 ADA CLEARANCES
G-0.0.4 PARTITION TYPES
G-0.0.5 UL ASSEMBLY DETAILS
G-0.0.6 UL ASSEMBLY DETAILS
G-0.0.7 UL ASSEMBLY DETAILS
G-0.0.8 UL ASSEMBLY DETAILS
1 G-0.0.9 UL ASSEMBLY DETAILS
G-1.0.0 LIFE SAFETY PLAN - LEVEL 01
G-2.0.0 LIFE SAFETY PLAN - LEVEL 02

ARCHITECTURE
A-1.0.1 DEMOLITION FLOOR PLAN - LEVEL 01
A-1.0.2 DEMOLITION FLOOR PLAN - LEVEL 02
1 A-1.1.1 DEMOLITION CEILING PLAN - LEVEL 01
A-1.1.2 DEMOLITION CEILING PLAN - LEVEL 02
A-2.0.1 SITE PLAN
A-2.0.2 REFERENCE PLAN - LEVEL 01
A-2.0.3 REFERENCE PLAN - LEVEL 02
A-2.1.0 ENLARGED FLOOR PLAN - LEVEL 01
A-2.1.1 ENLARGED FLOOR PLAN - LEVEL 02
1 A-2.1.2 ENLARGED FLOOR PLANS
1 A-4.0.1 BUILDING SECTIONS
A-5.0.1 INTERIOR ELEVATIONS
1 A-5.0.2 INTERIOR ELEVATIONS
A-6.0.1 REFLECTED CEILING PLAN - LEVEL 01
A-6.0.2 REFLECTED CEILING PLAN - LEVEL 02
A-6.0.3 FINISH FLOOR PLAN
A-6.0.4 SIGNAGE PLAN
A-7.0.1 DETAILS & SCHEDULES
A-7.0.2 STOREFRONT ELEVATIONS AND DETAILS
A-7.0.3 DETAILS
1 A-7.0.4 DETAILS
1 A-7.0.5 SIGNAGE DETAILS

STRUCTURAL
S-0.0.1 STRUCTURAL SPECIFICATIONS
S-0.0.2 SCHEDULES
S-1.0.1 NORTH TERMINAL RENOVATION FOUNDATION PLAN
S-2.0.1 NORTH TERMINAL RENOVATION FLOOR FRAMING PLAN
S-3.0.1 NORTH TERMINAL RENOVATION DETAILS
S-3.0.2 COMPOSITE DECK DETAILS

MECHANICAL
M0.0.1 HVAC LEGEND, SCHEDULES, AND NOTES
M1.0.1 HVAC DEMOLITION PLAN - LEVEL 2
M2.0.1 HVAC NEW WORK PLAN - LEVEL 2
M3.0.1 HVAC DETAILS
M4.0.1 HVAC CONTROLS

PLUMBING
P0.0.1 PLUMBING LEGEND, SCHEDULE, DETAILS, AND NOTES
P1.0.1 PLUMBING DEMOLITION PLAN - LEVEL 2
P2.0.1 PLUMBING NEW WORK PLAN - LEVEL 1
P2.0.2 PLUMBING NEW WORK PLAN - LEVEL 2
P3.0.1 PLUMBING RISER DIAGRAMS

ELECTRICAL
E-001 LEGEND AND NOTES
E-101 DEMOLITION ELECTRICAL PLAN - FIRST FLOOR
E-102 DEMOLITION ELECTRICAL PLAN - SECOND FLOOR
E-201 NEW LIGHTING PLAN - FIRST FLOOR
E-202 NEW POWER PLAN - SECOND FLOOR
E-203 NEW LIGHTING PLAN - SECOND FLOOR
E-204 NEW HVAC POWER PLAN - SECOND FLOOR
E-205 NEW FIRE ALARM PLAN - SECOND FLOOR
E-301 LIGHTING FIXTURE SCHEDULE AND CONTROLS
E-401 ELECTRICAL DETAILS
E-501 PANEL SCHEDULES

FIRE PROTECTION
FP0.0.1 FIRE PROTECTION LEGEND AND NOTES
FP1.0.1 FIRE PROTECTION DEMOLITION PLAN
FP2.0.1 FIRE PROTECTION NEW WORK PLAN

TELE/COMM
T-0.0.1 SYSTEMS LEGEND AND NOTES
T-0.0.2 SYSTEMS NOTES
T-1.0.1 ENLARGED SYSTEMS FLOOR PLAN
T-2.0.1 TELECOM DETAILS
T-2.0.2 SECURITY DETAILS
T-2.0.3 AUDIO / VISUAL DETAILS
T-2.0.4 GROUNDING DETAILS
T-3.0.1 SYSTEMS SINGLE LINE DIAGRAMS
T-4.0.1 ENLARGED TELECOM ROOM FLOOR PLAN
T-5.0.1 RACK ELEVATION


1

© 2018 All reproduction & intellectual property rights reserved.


FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

1 PERMIT DOCUMENTS

CLIENT
**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE
**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER
NO. 210211

ISSUE DATE
05.10.2022

DRAWING TITLE
**COVER SHEET**

SHEET NUMBER
**G-0.0.0**

5/11/2022 11:44:26 AM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/21021 - Panama City Airport NWFB_TASK 2_R21.rvt

# ABBREVIATIONS

| | |
|---|---|
| A/C | AIR CONDITION |
| AB | ANCHOR BOLT |
| ACT | ACOUSTICAL CEILING TILE |
| ACTV | VINYL FACED ACT |
| ADA | AMERICANS WITH DISABILITIES ACT |
| ADJ | ADJUSTABLE |
| AEDC | DEFIBRILLATOR & CABINET |
| AFF | ABOVE FINISHED FLOOR |
| AHU | AIR HANDLING UNIT |
| ALUM | ALUMINUM |
| ARCH | ARCHITECT |
| AWT | ACOUSTICAL WALL TREATMENT |
| BALC | BALCONY |
| BD | BOARD |
| BITUM | BITUMINOUS |
| BLDG | BUILDING |
| BM | BENCHMARK |
| BN | BARN DOOR |
| B.O. | BOTTOM OF |
| BR | BEDROOM |
| BRKT | BRACKET |
| C/C | CENTER TO CENTER |
| CAB | CABINET |
| CBB | CEMENTITIOUS BACKER BOARD |
| CFMF | COLD FORMED METAL FRAMING |
| CH | COAT HOOK |
| CIP | CAST IN PLACE |
| CJ | CONTROL JOINT |
| CL | CENTER LINE |
| CLL | COLUMN CENTER LINE |
| CMU | CONCRETE MASONRY UNIT |
| COL | COLUMN |
| CONT | CONTINUOUS |
| CPT | CARPET |
| CR | CLOSET ROD |
| CSB | CONCRETE SPLASH BLOCK |
| CT | CERAMIC TILE |
| CTB | CERAMIC TILE BASE |
| CTR | CENTER |
| CW | CURTAINWALL |
| DBL | DOUBLE |
| DEMO | DEMOLITION |
| DET | DETAIL |
| DHW | DOUBLE HUNG WINDOWS |
| DIA | DIAMETER |
| DIM | DIMENSION |
| DMPF | DAMP PROOFING |
| DS | DOWNSPOUT |
| DWG | DRAWING |
| E | EAST |
| EA | EACH |
| EB | EXPANSION BOLT |
| EIFS | EXTERIOR INSULATION AND FINISH SYSTEM |
| EJ | EXPANSION JOINT |
| EL | ELEVATION |
| EL PNL | ELECTRICAL PANEL |
| EOS | EDGE OF SLAB |
| EP | EPOXY PAINT |
| EQ | EQUAL |
| EQUIP | EQUIPMENT |
| EWC | ELECTRIC WATER COOLER |
| EXH | EXHAUST |
| EXIST | EXISTING |
| EXP | EXPANSION |
| EXTR | EXTERIOR |
| F | FLUSH |
| FA | FIRE ALARM |
| FB | FIBERGLASS |
| FD | FLOOR DRAIN |
| FE | FIRE EXTINGUISHER |
| FEC | FIRE EXTINGUISHER & CABINET |
| FFE | FINISH FLOOR ELEVATION |
| FF&E | FIXTURES, FURNITURE & EQUIPMENT |
| FHC | FIRE HOSE CABINET |
| FIN | FINISH |
| FIN FLR | FINISH FLOOR |
| FLR FIN | FLOOR FINISH |
| FLUOR | FLUORESCENT |
| FO | FINISHED OPENING |
| FOG | FACE OF GLASS |
| FOM | FACE OF MASONRY |
| FOS | FACE OF STUD |
| FT | FEET |
| FV | FIELD VERIFY |
| GALV | GALVANIZED |
| GB | GRAB BAR |
| GC | GENERAL CONTRACTOR |
| GD | GARBAGE DISPOSAL |
| GDR | GUARD RAIL |
| GFRC | GLASS FIBER REINFORCED CONCRETE |
| GFRG | GLASS FIBER REINFORCED GYPSUM |
| GHM | GALVANIZED HOLLOW METAL |
| GL | GLASS |
| GL BLK | GLASS BLOCK |
| GR FL | GROUND FLOOR |
| GYM | GYMNASIUM |
| GYP BD | GYPSUM BOARD |
| GWB | GYPSUM WALLBOARD |
| H&CW | HOT & COLD WATER |
| HB | HOSE BIBB |
| HC | HANDICAP |
| HM | HOLLOW METAL |
| HT | HEIGHT |
| HMD | HOLLOW METAL DOOR |
| HMDF | HOLLOW METAL DOOR & FRAME |
| HMF | HOLLOW METAL FRAME |
| HORIZ | HORIZONTAL |
| HW | HOT WATER |
| ID | INSIDE DIAMETER |
| INCL | INCLUDED |
| INFO | INFORMATION |
| INSUL | INSULATION |
| JC | JANITOR CLOSET |
| JST | JOIST |
| LAM | LAMINATE |
| LAM GL | LAMINATED GLASS |
| LAV | LAVATORY |
| LD BRG | LOAD BEARING |
| LT GA | LIGHT GAUGE |
| LVR | LOUVER |
| LVT | LUXURY VINYL TILE |
| LWC | LIGHT WEIGHT CONCRETE |
| MAX | MAXIMUM |
| MBR | MASTER BEDROOM |
| MECH | MECHANICAL |
| MEMB | MEMBRANE |
| MEZZ | MEZZANINE |
| MFR | MANUFACTURER |
| MFR REC | MFR RECOMMENDATION |
| MID | MIDDLE |
| MIN | MINIMUM |
| MISC | MISCELLANEOUS |
| MLDG | MOLDING / MOULDING |
| MO | MASONRY OPENING |
| MRT | MARBLE THRESHOLD |
| MS | MOP SINK |
| MTL | METAL |
| MW | MICROWAVE |
| MWP | MEMBRANE WATERPROOFING |
| N | NORTH |
| NA | NOT APPLICABLE / NOT AVAILABLE |
| NL | NATURAL LIGHT |
| NTE | NOT TO EXCEED |
| NTS | NOT TO SCALE |
| OFCI | OWNER FURNISHED, GC INSTALLED |
| OFOI | OWNER FURNISHED & INSTALLED |
| O.H. | OPPOSITE HAND |
| OH DR | OVERHEAD DOOR |
| OITC | OUTSIDE / INSIDE TRANSMISSION CLASS |
| ORD | OVERFLOW ROOF DRAIN |
| PCC | PRECAST CONCRETE |
| PEMB | PRE-ENGINEERED METAL BUILDING |
| PERIM | PERIMETER |
| PLAM | PLASTIC LAMINATE |
| PNL | PANEL |
| PR | PAIR |
| PT | PAINT |
| P.T. | PRESSURE TREATED |
| PWR | POWER |
| QTR | QUARTER |
| QTY | QUANTITY |
| R | RADIUS |
| RB | RUBBER BASE |
| RCP | REFLECTED CEILING PLAN |
| RD | ROOF DRAIN |
| RDL | ROOF DRAIN LEADER |
| REBAR | REINFORCING STEEL BARS |
| REC | RECESSED |
| REF | REFERENCE OR REFRIGERATOR |
| REINF | REINFORCE |
| REQD | REQUIRED |
| REV | REVISION |
| RH | ROOF HATCH |
| RO | ROUGH OPENING |
| RWL | RAINWATER LEADER |
| S | SOUTH |
| SAN | SANITARY |
| SCHED | SCHEDULE |
| SCWD | SOLID CORE WOOD DOOR |
| SGD | SLIDING GLASS DOOR |
| SF | SQUARE FOOT / FEET |
| SH | SHINGLES |
| SHT | SHEET |
| SHV | SHELVING |
| SHWR | SHOWER |
| SIM | SIMILAR |
| SM | SHEET METAL |
| SQ | SQUARE |
| SS | STAINLESS STEEL |
| STC | SOUND TRANSMISSION CLASS |
| SY | SQUARE YARD |
| TEMP | TEMPORARY |
| THK | THICKNESS |
| THRU | THROUGH |
| TN | TRUE NORTH |
| T.O. | TOP OF |
| TOB | TOP OF BEAM |
| TOS | TOP OF STEEL |
| TLT | TOILET |
| TYP | TYPICAL |
| UCD | UNDERCUT DOOR |
| UNO | UNLESS NOTED OTHERWISE |
| UR | URINAL |
| VB | VINYL BASE |
| VCT | VINYL COMPOSITION TILE |
| VERT | VERTICAL |
| VIF | VERIFY IN FIELD |
| VR | VAPOR RETARDER |
| VTR | VENT THROUGH ROOF |
| W/ | WITH |
| WC | WATER CLOSET |
| WD | WOOD |
| WDF | WOOD DOOR & FRAME |
| WH | WATER HEATER |
| WPM | WATERPROOF MEMBRANE |
| WWF | WELDED WIRE FABRIC |
| WGL | WIRED GLASS |

# GENERAL NOTES:

1. CONTRACTOR SHALL NOT SCALE DRAWINGS.
2. THESE WORKING DRAWINGS INDICATE MATERIALS AND METHODS OF CONSTRUCTION TO SET STANDARDS OF QUALITY AND/OR PERFORMANCE. OTHER MATERIALS AND/OR METHODS MAY BE CONSIDERED BY THE ARCHITECT FOR ACCEPTANCE PROVIDED THEY DO NOT ALTER THE ORIGINAL DESIGN INTENT. SUBMIT ALL PROPOSED ALTERNATES TO ARCHITECT IN WRITING FOR CONSIDERATION PRIOR TO IMPLEMENTATION. INCLUDE REASON/PURPOSE FOR SUBSTITUTION, COST DIFFERENCE TO ORIGINALLY SPECIFIED ITEM AND LEADTIME. ANY SUGGESTED SUBSTITUTIONS SHALL BE FORWARDED TO THE ARCHITECT A MINIMUM OF THREE WEEKS IN ADVANCE OF BIDDING OR IMPLEMENTING WORK. PROJECT COMPLETION SCHEDULE SHALL NOT BE JEOPARDIZED BY CONTRACTOR BY LATE SUBMITTAL OF SUBSTITUTIONS.
3. THE ARCHITECT IS NOT RESPONSIBLE FOR DISCREPANCIES OR OMISSIONS THAT ARISE DUE TO CHANGES BY THE CONTRACTOR, OR OWNER AFTER THE DATE OF ISSUANCE OF THE DRAWINGS.
4. ALL CONSTRUCTION EITHER OUTLINED OR IMPLIED IN THESE DOCUMENTS SHALL COMPLY WITH ALL APPLICABLE CODE REQUIREMENTS.
5. ALL SUBCONTRACTORS INCLUDING MECHANICAL, PLUMBING AND ELECTRICAL SHALL BE RESPONSIBLE FOR SECURING PERMITS FOR THEIR WORK AND TRADES, UTILITY HOOK-UPS, AND FOR PROVIDING ANY ADDITIONAL DRAWINGS THE BUILDING DEPARTMENT MAY REQUIRE.
6. THIS DESIGN TEAM (ARCHITECTS/INTERIOR DESIGNERS, AND ENGINEERS) WILL NOT BE RESPONSIBLE FOR AND WILL NOT HAVE CONTROL OR CHARGE OF CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, OR FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THIS PROJECT AND WILL NOT BE RESPONSIBLE FOR CONTRACTOR'S FAILURE TO CARRY OUT THE WORK ON THIS PROJECT IN ACCORDANCE WITH THESE CONSTRUCTION DOCUMENTS OR INDUSTRY STANDARDS. THE DESIGN TEAM WILL NOT BE RESPONSIBLE FOR OR HAVE CONTROL OR CHARGE OVER THE ACTS OR OMISSIONS OF THE CONTRACTOR, SUBCONTRACTORS, OR ANY OF THEIR AGENTS OR EMPLOYEES OR ANY OTHER PERSON PERFORMING ANY OF THE WORK OF THIS PROJECT.
7. ALL WORK OF OUTLINED TRADES SHALL BE PERFORMED BY SKILLED CRAFTSMEN IN THE TRADE, AND THE WORK SHALL BE OF A QUALITY THAT IS ACCEPTABLE BY INDUSTRY STANDARDS AND SATISFACTORY TO THE DESIGNER, ARCHITECT, BUILDING MANAGEMENT AND CLIENT.
8. DEBRIS RESULTING FROM CONSTRUCTION SHALL BE REMOVED ENTIRELY FROM THE SITE ON A REGULAR BASIS TO A WASTE AND/OR RECYCLING AREA PROVIDED BY THE CONTRACTOR.
9. CONTRACTOR SHALL COORDINATE INSTALLATION OF MILLWORK, FIXTURES, WALL HUNG UNITS, AND APPLIANCES AND EQUIPMENT AS IMPLIED AND INDICATED ON CONSTRUCTION DOCUMENTS. PROVIDE APPROPRIATE ELECTRICAL, MECHANICAL AND PLUMBING SUPPORT FOR ALL APPLIANCES AS PER MANUFACTURER'S RECOMMENDATIONS.
10. UPON AWARDING CONTRACTS TO SUBCONTRACTORS, THE GENERAL CONTRACTOR SHALL SUBMIT TO THE ARCHITECT AND OWNER A SCHEDULE FOR ALL LONG LEAD TIME ITEMS ON THE PROJECT (I.E. MATERIALS, EQUIPMENT, HARDWARE, FABRICS) AND SHALL BE RESPONSIBLE FOR NOTIFYING THE ARCHITECT AND OWNER AS TO ANY ITEM WHICH MAY CAUSE THE PROJECT COMPLETION TO BE DELAYED, PRIOR TO ORDERING THAT ITEM.
11. PATCH AND FIRE STOP ALL PENETRATIONS IN FLOOR AND WALL ASSEMBLIES TO COMPLY WITH APPLICABLE BUILDING CODE.
12. CONSIDERATION SHALL BE GIVEN WHEN LAYING OUT AND DETAILING THE WORK TO BE DONE TO VARIATIONS IN FLOOR PLANES RESULTING FROM CONSTRUCTION QUALITY AND LIVE DEAD LOADS IMPOSED ON THE STRUCTURE. ALIGNMENT OF DOOR AND WINDOW HEADS, AND ANY OTHER HORIZONTAL ELEMENT SHALL BE MAINTAINED AT A CONSTANT AND SHALL NOT FOLLOW VARIATIONS IN FLOOR PLANE.
13. CONTRACTOR SHALL DISPOSE OF ALL CHEMICALS AND HAZARDOUS MATERIALS IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND ORDINANCES.
14. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND CONDITIONS AT SITE AND NOTIFY ARCHITECT OF ANY DISCREPANCIES BEFORE ORDERING MATERIALS, BEGINNING FABRICATION, OR STARTING CONSTRUCTION.
15. CONTRACTOR SHALL CLEAN THE JOB SITE ON A WEEKLY BASIS (MINIMUM) AS THE PROJECT PROGRESSES AND AT THE END OF THE PROJECT. REMOVE DUST, DEBRIS, OILS, STAINS, FINGERPRINTS AND LABELS FORM EXPOSED FINISHED SURFACES, INCLUDING GLASS SURFACES AND PERIMETER WINDOW SILLS, GLAZING AND WINDOW TREATMENTS.
16. CONTRACTOR SHALL TURN OVER CLOSE-OUT PACKAGE TO ARCHITECT AT SUBSTANTIAL COMPLETION. CLOSE-OUT DOCUMENTS TO INCLUDE: CERTIFICATE OF OCCUPANCY, AS-BUILT DRAWINGS, TEST AND BALANCE REPORTS, WARRANTY INFORMATION AND OPERATIONS AND MAINTENANCE MANUAL.
17. CONTRACTOR TO ENSURE THAT ALL COMPOSITE WOOD AND AGRIFIBER PRODUCTS, INCLUDING CORE MATERIALS, MUST CONTAIN NO ADDED UREA-FORMALDEHYDE RESINS.
18. CONTRACTOR TO ENSURE THAT ALL ADHESIVES, SEALANTS AND SEALANT PRIMERS USED MUST NOT EXCEED THE VOC CONTENT LIMITS OF THE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD) RULE #1168 REQUIREMENTS IN EFFECT ON JANUARY 1, 2003 AND RULE AMENDMENT DATED OCTOBER 3, 2003.
19. SAFETY PLAN REQUIRED TO BE PREPARED AND REVIEWED IN THE PRECONSTRUCTION MEETING PRIOR TO START OF WORK. 1

# GENERAL NOTES:

PROPOSED SCOPE OF WORK INCLUDES THE DEMOLITION AND RENOVATION OF ROUGHLY 12,500 SF OF EXISTING SHELL AND FINISHED SPACE. NEWLY RENOVATED SPACES INCLUDE RESTROOMS, WAITING, TICKETING, LOUNGE AND CONCESSIONS AREA.

# PROJECT TEAM

## FITZGERALD COLLABORATIVE GROUP, LLC

**Architecture, Planning & Interiors**
850 S. Gadsden St, Suite 140
Tallahassee, FL 32301
850.350.3500

Contact: Donald Gray, Jr.
donald@fc-grouplc.com

## DAG ARCHITECTS

**Architecture, Planning & Interiors**
455 Harrison Avenue
Panama City, FL 32401
850.387.1671

Contact: Jim Tatum
jtatum@dagarchitects.com

## HG ENGINEERING

**Electrical / Telecom Engineers**
621 N Tyndall Pkwy,
Panama City, FL 32404

Contact: Dan White, P.E., LEED AP (BD+C)
dwhite@hgengineers.com

## JSM & ASSOCIATES

**Airport Consultants**
470 County Rd 448
Tavares, FL 32778
352.508.4760

Contact: Jon Oakes
jon.oakes@jsmairports.com

## PENNONI

**Structural Engineers**
1705 S. Gadsden Street, Suite 100
Tallahassee, FL 23201
352.504.6873

Contact: Justin Duncan, PE
jduncan@pennoni.com


## WATFORD ENGINEERING

**Mechanical, Plumbing, and Fire Engineers**
4452 Clinton Street
Marianna, FL 32446
850.526.3447


Contact: David N Watford, P.E., LEED AP
david@watford-engineering.com

# ANNOTATION SYMBOLS

DRAWING TITLEBAR:





DRAWING REFERENCE SYMBOL:





SPACE NAME / NUMBER SYMBOL:





DETAIL REFERENCE:





GRAPHIC ARROWS:






GRAPHIC SYMBOLS:








BUILDING / WALL SECTION REFERENCE:






PARTITION/ DOOR TYPE SYMBOLS:




REVISION SYMBOLS:




# LOCATION MAP




SITE --
**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**NOTES, SYMBOLS, & ABBREVIATIONS**

SHEET NUMBER

**G-0.0.1**

5/10/2022 6:01:05 PM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK-2_R21.rvt

## 1. GENERAL INFORMATION:

OWNER: PANAMA CITY-BAY COUNTY AIRPORT AND INDUSTRIAL DISTRICT
PROJECT NAME: PANAMA CITY AIRPORT - NWFBIA NORTH TERMINAL RENOVATION
PROJECT ADDRESS: 6300 WEST BAY PKWY, PANAMA CITY, FL 32409
COUNTY: BAY COUNTY

## 2. ADMINISTRATION - APPLICABLE CODES

A. FLORIDA BUILDING CODE: (FBC-B) 2020 - SEVENTH EDITION
B. FLORIDA BUILDING CODE: ACCESSIBILITY (FBC-A) 2020 - SEVENTH EDITION
C. FLORIDA BUILDING CODE: ENERGY CONSERVATION (FBC-EG) 2020 - SEVENTH EDITION
D. FLORIDA BUILDING CODE: MECHANICAL (FBC-M) 2020 - SEVENTH EDITION
E. FLORIDA BUILDING CODE: PLUMBING (FBC-P) 2020 - SEVENTH EDITION
F. FLORIDA BUILDING CODE: FUEL GAS (FBC-FG) 2020 - SEVENTH EDITION
G. NATIONAL ELECTRICAL CODE: (NEC) 2020 EDITION
H. FLORIDA FIRE PREVENTION CODE (FFPC) 2020 - SEVENTH EDITION
I. FLORIDA BUILDING CODE (FBC-EB), 2020 - SEVENTH EDITION

## 3. USE AND OCCUPANCY CLASSIFICATION

PRIMARY OCCUPANCY

- Assembly A-2 / Restaurant(FBC Section 303.3)
- Assembly A-3 / Waiting Areas in Transportation Terminals (FBC Section 303.4)
- Business B / Office (FBC Section 304.1)
- Storage S-2 / Low-Hazard Storage (FBC Section 311.3)
- Mixed Non Separated Use with A-3 as the most restrictive classification

SPECIAL DETAILED REQUIREMENTS BASED ON OCCUPANCY

- Public Food Service Establishments (FBC Section 456)

| | |
|---|---|
| ASSEMBLY, WAITING AREA | 15 GROSS SF / OCCUPANT |
| CONCOURSE | 100 GROSS SF / OCCUPANT |
| BUSINESS | 150 GROSS SF/ OCCUPANT |
| STORAGE | 300 GROSS SF / OCCUPANT |

## 4. BUILDING HEIGHT

EXISTING BUILDING - EXISTING CONSTRUCTION **TYPE IB, FULLY SPRINKLERED**

| ACTUAL BUILDING HEIGHTS | | ALLOWABLE BUILDING HEIGHTS | |
|---|---|---|---|
| HEIGHT | NUMBER OF STORIES | ALLOWABLE HEIGHT (FBC TABLE 504.3) | ALLOWABLE NUMBER OF STORIES (FBC TABLE 504.4) |
| +/- 43 FEET | 2 STORIES | 180 FEET | 12 STORIES |

## 5. EGRESS RELATED REQUIREMENTS

| | |
|---|---|
| MINIMUM CORRIDOR WIDTH (FBC TABLE 1020.2) | MINIMUM CORRIDOR WIDTH = 0.2 INCH PER OCCUPANT LOAD (FBC 1005.3.2, BUT NOT LESS THAN **44 INCHES**) |
| DEAD END CORRIDORS NOT TO EXCEED (FBC SECTION 1020.4) | ASSEMBLY 20'-0"<br>BUSINESS 50'-0" (W/ AUTOMATIC SPRINKLER SYSTEM)<br>STORAGE NOT REQUIRED (LOW HAZARD) |
| MAXIMUM TRAVEL DISTANCES (FBC TABLE 1017.2) | ASSEMBLY* 250'-0" (W/ SPRINKLER SYSTEM)<br>*PER SECTION 1029.7, WHERE AISLES ARE PROVIDED FOR SEATING, THE DISTANCE SHALL BE MEASURE ALONG THE AISLES AND AISLE ACCESSWAYS.<br>BUSINESS 300'-0" (W/ SPRINKLER SYSTEM)<br>STORAGE NOT REQUIRED (LOW HAZARD) |
| COMMON PATH LIMIT | ASSEMBLY* 30'-0" (FBC 1029.8)<br>*EXCEPTION: NOT EXCEED 75 FEET FOR AREAS SERVING LESS THAN 50 OCCUPANTS<br>BUSINESS 100'-0" (PER FFPC 38.2.5.3.1 W/ SPRINKLER SYSTEM)<br>STORAGE NOT REQUIRED (LOW HAZARD) |
| NUMBER OF EXITS (FBC 1006.3.2) | ALL ROOMS, AREAS, OR SPACES INCLUDING MEZZANINES SHALL HAVE TWO EXITS OR EXIT ACCESS DOORWAYS (FBC 1006.2.1), EXCEPT AS NOTED:<br>OCCUPANT LOAD — NUMBER OF EXITS<br>1 - 500* — 2<br>501 - 1,000 — 3<br>MORE THAN 1,000 — 4<br>*ONE EXIT ALLOWED, IF BOTH MAXIMUM OCCUPANT LOAD AND MAXIMUM PATH OF TRAVEL WITH SPRINKLER SYSTEM ARE MET AS LISTED BELOW (FBC TABLE 1006.2.1):<br>OCCUPANCY — MAX OCCUPANT LOAD — MAX. COMMON PATH OF TRAVEL<br>ASSEMBLY — 49 — 75'-0"<br>BUSINESS — 49 — 100'-0"<br>STORAGE — 29 — 100'-0" |
| MINIMUM DOOR WIDTH (FBC 1005.3.2) | MINIMUM DOOR WIDTH = 0.2 INCHES PER OCCUPANT, BUT NOT LESS THAN 32 INCHES.<br>PER FBC 1010.1.1,<br>MINIMUM CLEAR OPENING = 32 INCHES<br>MAXIMUM DOOR LEAF WIDTH = 48 INCHES |
| MINIMUM STAIRWAY WIDTH (FBC 1005.3.1) | 0.3 INCHES PER OCCUPANT |
| MINIMUM EXIT PASSAGEWAYS WIDTH (FBC 1024.2) | NOT LESS THAN 44 INCHES,<br>NOT LESS THAN 36 INCHES WHEN OCCUPANT LOAD IS LESS THAN 50 |

## 6. FIRE RESISTANCE RATINGS

EXISTING CONSTRUCTION **TYPE IB**

**BUILDING ELEMENTS (FBC TABLE 601)**

| | RATING (HOURS) | COMMENTS |
|---|---|---|
| STRUCTURAL FRAME | 2 | |
| BEARING WALLS:<br>EXTERIOR<br>INTERIOR | <br>1<br>1 | |
| NON-BEARING WALLS:<br>EXTERIOR<br>X< 5 FEET<br>5≤ X ≤10<br>10≤ X < 30<br>INTERIOR | <br><br>1<br>1<br>1<br><br>0 | |
| FLOOR CONSTRUCTION | 2 | |
| ROOF CONSTRUCTION | 1 | 0 HR, IF ANY PART OF ROOF IS ABOVE 20 FEET FROM ANY FLOOR BELOW |
| CORRIDOR (FBC TABLE 1020.1) | 0 | WITH AUTOMATIC SPRINKLERT SYSTEM FOR OCCUPANT LOAD >30 |
| **FIRE SEPARATION** | | |
| SHAFT ENCLOSURE (FBC SECTION 707.3.1 & 713.4) | 1<br>2 | WHERE CONNECTING LESS THAN (4) STORIES<br>WHERE CONNECTING (4) OR MORE STORIES |
| | OPENINGS IN A SHAFT ENCLOSURE SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 716. DOORS SHALL BE SELF- OR AUTOMATIC-CLOSING BY SMOKE DETECTION | |
| EXIT PASSAGEWAYS (FBC 1024.3) | 1 | |
| OPENING PROTECTIVES (FBC TABLE 716.5) | 1 1/2<br>1<br>1/3 | DOOR IN (2) HOUR FIRE BARRIER<br>DOOR IN (1) HOUR FIRE BARRIER<br>DOOR IN CORRIDOR WALLS OR SMOKE BARRIER WALLS |

## 7. PORTABLE FIRE EXTINGUISHERS

PORTABLE EXTINGUISHERS ARE REQUIRED PER FBC 906

| | |
|---|---|
| MAXIMUM FLOOR AREA PER EXTINGUISHER | 11,250 SF |
| MAXIMUM DISTANCE OF TRAVEL TO EXTINGUISHER | 75 FEET |

## 8. INTERIOR FINISH REQUIREMENTS

INTERIOR WALL AND CEILING FINISHES SHALL BE CLASSIFIED AS FOLLOWS AND SHALL BE RESTRICTED FOR USE BY THE FOLLOWING TABLE AS DEFINED PER FBC SECTION 803.1.1

| CLASS | FLAME SPREAD INDEX | SMOKE DEVELOPMENT INDEX |
|---|---|---|
| A | 0 - 25 | 0 - 450 |
| B | 26 - 75 | 0 - 450 |
| C | 76 - 200 | 0 - 450 |

**WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY (FBC TABLE 803.11)**

| | SPRINKLERED | | |
|---|---|---|---|
| OCCUPANCY | EXIT ENCLOSURE | CORRIDORS | ROOMS |
| A-2, A-3 | B | B | C |
| B | B | C | C |
| S | C | C | C |
| | | | |

## 9. PLUMBING FIXTURES

FBC TABLE 2902.1 MINIMUM NUMBER OF REQUIRED PLUMBING FIXTURES

| | FEMALE | | MALE | | FAMILY / SINGLE USER | |
|---|---|---|---|---|---|---|
| FIXTURE | # REQUIRED | # PROVIDED | # REQUIRED | # PROVIDED | # REQUIRED | # PROVIDED |
| WATER CLOSETS (1 PER 500) | 4 | 7 | 2 | 3 | 0 | 1 |
| URINALS (< 67% OF REQ WC) | | | 2 | 4 | 0 | 0 |
| LAVATORIES (1 PER 750) | 3 | 6 | 3 | 6 | 0 | 1 |
| | SERVICE | | FBC-P TABLE 403.1 | | | |
| | # REQUIRED | # PROVIDED | | | | |
| SERVICE SINKS (1 SERVICE SINK) | 1 | 1 | | | | |
| DRINKING FOUNTAINS (1 PER 1000) | 1 | 1 | | | | |

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**BUILDING CODE INFORMATION**

SHEET NUMBER


# G-0.0.2


5/10/2022 6:01:08 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK 2_R21.rvt

# MOUNTING HEIGHTS- PLUMBING AND ACCESSORIES


NOTE: INSTALL ALL ITEMS IN ACCORDANCE WITH THIS DRAWING
NOTE: DIMENSIONS ARE TO TOP OF FINISH FLOOR

NOTE: PROVIDE BLOCKING FOR ALL ACCESSORIES MOUNTED ON GWB PARTITIONS
NOTE: MAINTAIN INTEGRITY OF FIRE RATING WHERE ACCESSORIES ARE MOUNTED IN OR ON RATED WALLS






## 13 ADA TOE CLEARANCES
3/8" = 1'-0"





## 12 ADA PROTRUDING OBJECT
3/8" = 1'-0"





## 11 TYP RESTROOM MOUNTING HEIGHTS
1/4" = 1'-0"





## 10 ADA ROOM SIGN
3/8" = 1'-0"





## 09 ADA REACH RANGES
3/8" = 1'-0"





## 08 ADA WATER CLOSET CLEARANCES
3/8" = 1'-0"





## 07 ADA DOOR OPENINGS
3/8" = 1'-0"





## 06 ADA DOORS RECESSED CLEARANCES
3/8" = 1'-0"





## 05 ADA DOORS IN SERIES
3/8" = 1'-0"





## 04 ADA ACCESSIBLE ROUTE
3/8" = 1'-0"




## 03 ADA VERTICAL CHANGES
1/4" = 1'-0"




## 02 ADA WHEEL CHAIR CLEARANCES
3/8" = 1'-0"




## 01 ADA DOORS MANEUVERING CLEARANCES
3/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

# ADA CLEARANCES


SHEET NUMBER

# G-0.0.3


5/10/2022 6:01:13 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK-2_R21.rvt

# PARTITION NOTES

*NOTE: PARTITIONS TO EXTEND 6" ABOVE ADJACENT CEILING UNLESS NOTED OTHERWISE.
SEE REFLECTED CEILING PLANS & INTERIOR ELEVATIONS FOR DELINEATION OF FULL HEIGHT WALLS.





TYPICAL PARTITION BRACING




I1 — 2-HR RATED FULL-HEIGHT PARTITION (UL U415)
20 GUAGE 2-1/2" CH METAL STUDS, 24" O.C.
WITH (2) LAYERS 5/8" TYPE X GYPSUM BOARD ON ONE SIDE. (1) LAYER OF 1" LINER PANEL ON SHAFT SIDE. SOUND ATTENUATION BLANKETS AS INDICATED ON PLAN.

H1 — (1) LAYER 5/8" GYPSUM BOARD ON ONE SIDE OF 7/8" GALVANIZED FURRING CHANNELS AT 16" O.C. ON CMU OR CONCRETE. CARRY TO 6" ABOVE CEILING




NOT USED

G1 — 1-HR RATED FULL-HEIGHT PARTITION (UL U419)
6" METAL STUDS. 16" O.C. WITH (1) LAYER 5/8" TYPE X GWB ON EACH SIDE. SOUND ATTENUATION BLANKETS AS INDICATED ON PLAN.

F1 — NOT USED

E1 — 2-HR RATED FULL-HEIGHT PARTITION (UL U419)
6" METAL STUDS. 16" O.C.
WITH (2) LAYERS 5/8" TYPE X GWB EACH SIDE. SOUND ATTENUATION BLANKETS AS INDICATED ON PLAN.

D1 — NON-RATED PARTIAL-HEIGHT PARTITION
6" METAL STUDS. 16" O.C.
WITH (1) LAYER 5/8" GWB SOUND ATTENUATION BLANKETS AS INDICATED ON PLAN.

C1 — NON-RATED FULL-HEIGHT PARTITION
4" METAL STUDS. 16" O.C.
WITH (1) LAYER 5/8" GWB EACH SIDE

C2 — NON-RATED FULL-HEIGHT PARTITION
6" METAL STUDS. 16" O.C.
WITH (1) LAYER 5/8" GWB EACH SIDE

B1 — NON-RATED PARTIAL-HEIGHT PARTITION
4" METAL STUDS. 16" O.C.
WITH (1) LAYER 5/8" GWB

B2 — NON-RATED PARTIAL-HEIGHT PARTITION
4" METAL STUDS. 16" O.C.
WITH (1) LAYER 5/8" GWB WITH SOUND ATTENUATION BLANKETS

A1 — NON-RATED PARTIAL-HEIGHT PARTITION 4"
METAL STUDS 16" O.C.
WITH (1) LAYER 5/8" GWB EACH SIDE

## 01 PARTITION TYPES

1" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,
PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**PARTITION TYPES**

SHEET NUMBER

**G-0.0.4**

5/10/2022 6:01:16 PM BIM 360://21211 - NFBIA North Terminal Renovations - Task #2 (2021)\21211 - Panama City Airport NWFB_TASK 2_R21.rvt

**CGC INC** — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Types C and SCX

**UNITED STATES GYPSUM CO** — Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SGX, SHX, ULIX, ULX, USGX, WRC, WRX.

**USG BORAL DRYWALL SFZ LLC** — Types C, SCX, SGX, USGX

**USG MEXICO S A DE C V** — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**System E — 2 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 1/2 in. or 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally, attached to studs with 1 in. long Type S steel screws spaced 12 in. OC when installed vertically or 8 in. when installed horizontally. Horizontal joints need not be backed by steel framing.

**CGC INC** — 1/2 in. Types C, IP-X2, IPC-AR; 5/8 in. Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Types C and SCX

**UNITED STATES GYPSUM CO** — 1/2 in. Types C, IP-X2, IPC-AR; 5/8 in. Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SGX, SHX, ULIX, ULX, USGX, WRC, WRX.

**USG BORAL DRYWALL SFZ LLC** — 1/2 in. Type C; 5/8 in. Types C, SCX, SGX, USGX

**USG MEXICO S A DE C V** — 1/2 in. Types C, IP-X2, IPC-AR; 5/8 in. Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**System F — 2 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 1/2 in. or 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically in two layers. Inner or base layer attached to resilient furring channels (Item 2B) with 1 in. long Type S steel screws spaced 24 in. Outer or face layer attached to resilient furring channels (Item 2B) with 1-5/8 in. long Type S steel screws spaced 12 in. OC and staggered 12 in. from base layer screws. Joints between inner and outer layers staggered 24 in.

**CGC INC** — 1/2 in. Type C, IP-X2, IPC-AR or WRC; 5/8 in. Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Types C and SCX

**UNITED STATES GYPSUM CO** — 1/2 in. Type C, IP-X2, IPC-AR or WRC; 5/8 in. Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SGX, SHX, ULIX, ULX, USGX, WRC, WRX.

**USG BORAL DRYWALL SFZ LLC** — 1/2 in. Type C; 5/8 in. Types C, SCX

**USG MEXICO S A DE C V** — 1/2 in. Types C, IP-X2, IPC-AR or WRC; 5/8 in. Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULIX, USGX, WRC, WRX

**System G — 3 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally in three layers. Inner or base layer attached to studs with 1 in. long Type S steel screws spaced 24 in. OC when installed vertically or 16 in OC when installed horizontally. Middle layer attached to studs with 1-5/8 in. long Type S steel screws spaced 24 in. when installed vertically or 16 in. OC when installed horizontally. Outer or face layer attached to studs with 2-1/4 in. long Type S steel screws spaced 16 in. when installed vertically or 12 in. OC when installed horizontally. Screws offset 6 in. from layer below. Horizontal joints on adjacent layers staggered a min of 12 in. . Horizontal joints need not be backed by steel framing. Vertical joints centered over studs and staggered 24 in. on adjacent layers.

**CGC INC** — Types C, IP-X2, IPC-AR, ULIX, WRC

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Type C

**UNITED STATES GYPSUM CO** — Types C, IP-X2, IPC-AR, ULIX, WRC

**USG BORAL DRYWALL SFZ LLC** — Type C

**USG MEXICO S A DE C V** — Types C, IP-X2, IPC-AR, WRC

**System H — 3 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally, two layers over the flange of the "C" section of the studs, one layer over the flange of the "H" section of the studs. Inner or base layer attached to studs with 1 in. long Type S steel screws spaced 24 in. OC when installed vertically or 16 in. OC when installed horizontally. Face layer attached to studs with 1-5/8 in. long Type S steel screws spaced 16 in. when installed vertically or 12 in. OC when installed horizontally. Screws offset 6 in. from layer below. Horizontal joints on adjacent layers staggered a min of 12 in. Horizontal joints need not be backed by steel framing. Vertical joints centered over studs and staggered 24 in. on adjacent layers.

**CGC INC** — Types C, IP-X2, IPC-AR, ULIX, WRC

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Type C

**UNITED STATES GYPSUM CO** — Types C, IP-X2, IPC-AR, ULIX, WRC

**USG BORAL DRYWALL SFZ LLC** — Type C

**USG MEXICO S A DE C V** — Types C, IP-X2, IPC-AR, WRC

**System I — 4 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 3/4 in. thick, 4 ft wide (or 1200 mm for metric spacing) wallboard with square or tapered edges. Total of four layers to be used. First and second (inner) layers applied vertically or horizontally over the steel studs. Horizontal joints need not be backed by steel framing. When applied vertically, joints centered over studs and staggered min 24 in., otherwise all joints staggered min 12 in. First layer secured to studs with 1-1/4 in. long Type S self-drilling, self-tapping bugle-head steel screws spaced 24 in. OC. Second layer secured to studs with 2-1/4 in. long Type S self-drilling, self-tapping bugle-head steel screws spaced 12 in. OC. Third layer applied vertically over the furring channels (Item 2C) with a 1-1/4 in. long Type S self-drilling, self-tapping bugle-head steel screws spaced 12 in. OC. Fourth layer applied vertically or horizontally with 2-1/4 in. long Type S self-drilling, self-tapping bugle-head steel screws spaced 12 in. OC. When applied vertically, joints to be staggered min 24 in. from third layer, otherwise all joints staggered min 12 in.

**CGC INC** — Types IP-X3 or ULTRACODE

**UNITED STATES GYPSUM CO** — Types IP-X3 or ULTRACODE

**USG BORAL DRYWALL SFZ LLC** — Type ULTRACODE

**USG MEXICO S A DE C V** — Types IP-X3 or ULTRACODE

4A. **Gypsum Board* —** (As an alternate to Item 4 Systems A, B, C, D, E, G, H, and I when used as the base layer, For direct attachment only) — Nom 5/8 in. or 3/4 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over 20 MSG steel studs and staggered min 1 stud cavity on opposite sides of studs. See Items 1, 2, 2A, 2B and 2D. Wallboard secured to studs with 1-1/4 in. long Type S-12 steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. For Joint Compound see Item 5. To be used with Lead Batten Strips (see Item 9) or Lead Discs or Tabs (see Item 10).
**RAY-BAR ENGINEERING CORP** — Type RB-LBG

channels are friction fitted into clips.
**PLITEQ INC** — Type GENIECLIP

2G. **Steel Framing Members* —** (Optional, Not Shown) — Furring channels and Steel Framing Members as described below. Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).
a. **Furring Channels —** Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item 2Gb. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. Gypsum board attached to furring channels as described in Item 4.

b. **Steel Framing Members* —** Used to attach furring channels (Item 2Ga) to studs. Clips spaced 24 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips.
**REGUPOL AMERICA** — Type SonusClip

2H. **Steel Framing Members* —** (Optional, Not Shown) — Resilient channels and Steel Framing Members as described below. Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).
a. **Resilient Channels —** Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and secured in place with two No. 8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 in. from the center of the overlap. Gypsum board attached to resilient channels as described in Item 4.

b. **Steel Framing Members* —** Used to attach resilient channels (Item 2Ha) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Resilient channels are secured to clips with one No. 10 x 1/2 in. pan-head self-drilling screw.
**KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip

2I. **Steel Framing Members* —** (Optional, Not Shown) — For use with single or double layer systems. Furring channels and Steel Framing Members as described below. Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).
a. **Furring Channels —** Formed of No. 25 MSG galv steel. 2-23/32 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board installed vertically only and attached to furring channels as described in Item 4.

b. **Steel Framing Members* —** Used to attach furring channels (Item 2Ia) to studs (Item 2 or 2A). Clips spaced max. 24 in. OC., and secured to studs with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center grommet. Furring channels are friction fitted into clips.
**CLARKDIETRICH BUILDING SYSTEMS** — Type ClarkDietrich Sound Clip

3. **Gypsum Board* —** Gypsum liner panels, nom 1 in. thick, 24 in. or 600 mm (for metric spacing) wide. Panels cut 1 in. less in length than floor to ceiling height. Vertical edges inserted in "H" portion of "C-H" studs or the gap between the two 3/4 in. legs of the "E" studs. Free edge of end panels attached to long leg of vertical "J" - runners with 1-5/8 in. long Type S steel screws spaced not greater than 12 in. OC. When wall height exceeds liner panel length, liner panel may be butted to extend to the full height of the wall. Horizontal joints need not be backed by steel framing. In System I, butt joints in liner panels are staggered min 36 in. Butt joints backed with 6 in. by 22 in. strips of 3/4 in. thick gypsum wallboard (Item 4). Wallboard strips centered over butt joints and secured to liner panels with six 1-1/2 in. long Type G steel screws, three screws along the 22 in. dimension at the top and bottom of the strips.
**CGC INC** — Type SLX

**UNITED STATES GYPSUM CO** — Type SLX

**USG BORAL DRYWALL SFZ LLC** — Type SLX

**USG MEXICO S A DE C V** — Type SLX

4. **Gypsum Board* —**

**System A — 1 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally, attached to studs with 1 in. long Type S steel screws spaced 12 in. when installed vertically or 8 in OC when installed horizontally. Horizontal joints need not be backed by steel framing.

**CGC INC** — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULIX, USGX, WRC, WRX

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Types C and SCX

**UNITED STATES GYPSUM CO** — Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SGX, SHX, ULIX, ULX, WRC, WRX, USGX.

**USG BORAL DRYWALL SFZ LLC** — Types C, SCX, SGX, USGX

**USG MEXICO S A DE C V** — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**System B — 2 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 1/2 in. or 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally in two layers. Inner or base layer attached to studs with 1 in. long Type S steel screws spaced 24 in. OC when installed vertically or 16 in. OC when installed horizontally. Outer or face layer attached to studs with 1-5/8 in. long Type S steel screws spaced 12 in. OC when installed vertically and staggered 12 in. from base layer screws or 8 in. OC when installed horizontally and staggered 8 in. from base layer screws. Horizontal joints between inner and outer layers staggered a min of 12 in. Horizontal joints need not be backed by steel framing. Vertical joints centered over studs and staggered 24 in.

**CGC INC** — 1/2 in. Type C, IP-X2, IPC-AR or WRC; 5/8 in. Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Types C and SCX

**UNITED STATES GYPSUM CO** — 1/2 in. Types C, IP-X2, IPC-AR, or WRC; 5/8 in. Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SGX, SHX, ULIX, ULX, USGX, WRC, WRX.

**USG BORAL DRYWALL SFZ LLC** — 1/2 in. Type C; 5/8 in. Types C, SCX, SGX, USGX

**USG MEXICO S A DE C V** — 1/2 in. Types C, IP-X2, IPC-AR or WRC; 5/8 in. Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

**System C — 2 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 3/4 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally, secured with 1-1/4 in. long Type S steel screws spaced 8 in. OC along vertical edges and 12 in. OC in the field when installed vertically or 8 in. OC along the vertical edges and in the field when installed horizontally. Horizontal joints need not be backed by steel framing. Screws along side joints offset 4 in. Requires min 4 in. deep framing per Items 1, 2 and 3. Requires min 3 in. thick mineral wool batts per Item 6.

**CGC INC** — Types IP-X3 or ULTRACODE


**UNITED STATES GYPSUM CO** — Types IP-X3 or ULTRACODE

**USG BORAL DRYWALL SFZ LLC** — Type ULTRACODE

**USG MEXICO S A DE C V** — Types IP-X3 or ULTRACODE

**System D — 2 Hr**

Gypsum panels, with beveled, square or tapered edges, nom 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally, attached directly to studs with 1 in. long Type S steel screws spaced 24 in. when installed vertically or 16 in. OC when installed horizontally. Horizontal joints need not be backed by steel framing. Requires face layer of 1/2 or 5/8 in. thick cementitious backer units per Item 7 and min 1-1/2 in. thick mineral wool batts per Item 6.




1. **Floor, Side and Ceiling Runners —** "J" - shaped runner, min 2-1/2 in. deep (min 4 in. deep when System C is used), with unequal legs of 1 in. and 2 in., fabricated from min 24 MSG (min 20 MSG when Item 4A, 4B, 4C, 4D or 7 are used) galv steel. Runners positioned with short leg toward finished side of wall. Runners attached to structural supports with steel fasteners located not greater than 2 in. from ends and not greater than 24 in. OC. "E" - shaped studs (Item 2A) may be used as side runners in place of "J" - shaped runners.

2. **Steel Studs —** "C-H" - shaped studs, min 2-1/2 in. deep (min 4 in. deep when System C is used), fabricated from min 25 MSG (min 20 MSG when Items 2D, 4A, 4B, 4C, 4D or 7 is used) galv steel. Cut to lengths 3/8 to 1/2 in. less than floor-to-ceiling height and spaced 24 in. or 600 mm OC (max 16 in. OC when Items 4A, 4B, 4C, or 4D are used).

2A. **Steel Studs —** (Not Shown) — "E" - shaped studs installed back to back in place of "C-H" - shaped studs (Item 2) "E" - shaped studs secured together with steel screws spaced a maximum 12 in. OC. Fabricated from min 25 MSG (min 20 MSG when Item 2D, 4A, 4B or 7 is used) galv steel, min 2-1/2 in. deep (min 4 in. deep when System C is used), with one leg 1 in. long and two legs 3/4 in. long. Shorter legs 1 in. apart to engage gypsum liner panels. Cut to lengths 3/8 to 1/2 in. less than floor to ceiling heights.

2B. **Furring Channels —** (Optional, Not Shown) — For use with single or double layer systems. Resilient furring channels fabricated from min 25MSG corrosion protected steel, installed horizontally, and spaced vertically a max 24 in. OC. Flange portion of channel attached to each intersecting "C-H" or "E" stud on side of stud opposite the 1 in. liner panels with 1/2 in. long Type S or S-12 pan-head steel screws. When furring channels are used, wallboard to be installed vertically only. . Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).

2C. **Furring Channels —** For use with System I - "Hat" - shaped, 25 MSG galv steel furring channels attached directly over the inner layers of wallboard to each stud with 2 in. long Type S pan head steel screws. Screws alternate from top flange to bottom flange at each stud intersection. Furring channels spaced vertically max 24 in. OC.

2D. **Steel Framing Members* —** (Optional, Not Shown) — For use with single or double layer systems. Furring channels and Steel Framing Members as described below. Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).
a. **Furring Channels —** Formed of No. 25 MSG galv steel. 2-9/16 in. or 2-23/32 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board installed vertically only and attached to furring channels as described in Item 4.

b. **Steel Framing Members* —** Used to attach furring channels (Item 2Da) to studs (Item 2 or 2A). Clips spaced max. 24 in. OC., and secured to studs with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center grommet. Furring channels are friction fitted into clips. RSIC-1 clip for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) clip for use with 2-23/32 in. wide furring channels.
**PAC INTERNATIONAL L L C** — Types RSIC-1, RSIC-1 (2.75)

2E. **Steel Framing Members* —** (Optional, Not Shown) — Furring channels and Steel Framing Members as described below. . Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).
a. **Furring Channels —** Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire.Gypsum board attached to furring channels as described in Item 4.

b. **Steel Framing Members* —** Used to attach furring channels (Item 2Ea) to studs. Clips spaced 24 in. OC., and secured to studs with 2 in. coarse drywall screw with 1 in. diam washer through the center hole. Furring channels are friction fitted into clips.
**STUDCO BUILDING SYSTEMS** — RESILMOUNT Sound Isolation Clips - Type A237R

2F. **Steel Framing Members* —** (Optional, Not Shown) — For use with single or double layer systems. Furring channels and Steel Framing Members as described below. Not to be used with Type FRX-G gypsum board, lead backed gypsum boards (Items 4A-4D), or cementitious backer units (Item 7).
a. **Furring Channels —** Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board installed vertically only and attached to furring channels as described in Item 3.

b. **Steel Framing Members* —** Used to attach furring channels (Item 2Da) to studs (Item 2 or 2A ). Clips spaced max. 24 in. OC. GENIECLIPS secured to studs with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center grommet. Furring

UL Product iQ™

# BXUV.U415 - Fire-resistance Ratings - ANSI/UL 263

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

## Fire-resistance Ratings - ANSI/UL 263

BXUV - Fire Resistance Ratings - ANSI/UL 263 Certified for United States
BXUV7 - Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada


See General Information for Fire-resistance Ratings - ANSI/UL 263 Certified for United States
Design Criteria and Allowable Variances


See General Information for Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada
Design Criteria and Allowable Variances

## Design No. U415

February 14, 2022

**Nonbearing Wall Ratings — 1, 2, 3 or 4 Hr**
*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

**NORTH TERMINAL EXPANSION / IMPROVEMENTS**

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**UL ASSEMBLY DETAILS**

SHEET NUMBER

**G-0.0.5**

5/10/2022 6:01:18 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK-2_R21.rvt

4B. **Gypsum Board* —** (As an alternate to Item 4 Systems A, B, C, D, E, G, H, and I when used as the base layer, For direct attachment only) — Nominal 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-1/4 in. long Type S-12 (or #6 by 1-1/4 in. long bugle head fine driller) steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field.
**NEW ENGLAND LEAD BURNING CO INC, DBA NELCO** — Type Nelco

4C. **Gypsum Board* —** (As an alternate to Item 4 Systems A, B, C, D, E, G, H, and I when used as the base layer, For direct attachment only) — Nom 5/8 or 3/4 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over 20 MSG steel studs and staggered min 1 stud cavity on opposite sides of studs. See Items 1, 2, 2A, 2B and 2D. Wallboard secured to studs with 1-1/4 in. long Type S-12 steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. For Joint Compound see Item 5. To be used with Lead Batten Strips (see Item 9A) or Lead Discs (see Item 10A). Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 10 ft long with a max thickness of 0.140 in. placed on the face of studs and attached to the stud with two 1 in. long Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip.
**MAYCO INDUSTRIES INC** — Type X-Ray Shielded Gypsum

4D. **Gypsum Board* —** (As an alternate to Item 4 Systems A, B, C, D, E, G, H, and I when used as the base layer, For direct attachment only) — Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-1/4 in. long Type S-12 steel screws gypsum panel steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 8 ft long with a max thickness of 0.14 in. placed on the face of studs and attached to the stud with construction adhesive and two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs, nominal 3/8 in. diam by max 0.085 in. thick. Compression fitted or adhered over the screw heads. Lead batten strips and discs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C".
**RADIATION PROTECTION PRODUCTS INC** — Type RPP - Lead Lined Drywall

5. **Joint Tape and Compound —** (Not Shown)

**Systems A, B, C, E, F, G, H, I**

Joints on outer layers of gypsum boards (Item 4 and 4A) covered with paper tape and joint compound. Paper tape and joint compound may be omitted when gypsum boards are supplied with square edges. Exposed screw heads covered with joint compound.

6. **Batts and Blankets* —**

**Systems A, B, E, F, G, H, I**

(Optional) — Mineral wool or glass fiber batts partially or completely filling stud cavity. Any mineral wool or glass fiber batt mineral bearing the UL Classification Marking as to Fire Resistance.

**Systems C & D**

Min 3 in. (System C) and min 1-1/2 in. (System D) thick mineral wool batts, friction fitted between the studs and floor and ceiling runners.

**ROCKWOOL** — Type AFB, min. density 1.8 pcf / 28.8 kg/m$^3$

**THERMAFIBER INC** — Type SAFB, SAFB FF

7. **Cementitious Backer Units* —** (System D) — Nom 1/2 or 5/8 in. thick panels, square edge, attached to studs over gypsum wallboard with 1-5/8 in. long, Type S-12, corrosion resistant steel screws spaced 8 in. OC and staggered 8 in. from gypsum wall board screws. Joints covered with glass fiber mesh tape. Vertical joints staggered one stud cavity from gypsum wallboard joints. Horizontal joints staggered a min of 12 in. from the gypsum wallboard joints.
**UNITED STATES GYPSUM CO** — Type DCB

8. **Laminating Adhesive* —** (Optional, Not Shown) — Used to bond outer layer of Cementitious Backer Units (Item 7) to inner layers of Gypsum Board (Item 4) in System D. ANSI A136.1 Type 1 organic adhesive applied with 1/4 in. square notched trowel. See Adhesives (BYWR) in the Fire Resistance Directory or Adhesives (BJLZ) in the Building Materials Directory for names of Classified companies.

9. **Lead Batten Strips —** (Not Shown, For Use With Item 4A) — Lead batten strips, min 1-1/2 in. wide, max 10 ft long with a max thickness of 0.125 in. Strips placed on the interior face of studs and attached from the exterior face of the stud with two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead batten strips to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Lead batten strips required behind vertical joints of lead backed gypsum wallboard (Item 4A) and optional at remaining stud locations. Required behind vertical joints.

9A. **Lead Batten Strips —** (Not Shown, for use with Item 4C) — Lead batten strips, 2 in. wide, max 10 ft long with a max thickness of 0.140 in. Strips placed on the face of studs and attached to the stud with two min. 1 in. long min. Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip or with one min. 1 in. long min. Type S-8 pan head steel screw at the top of the strip. Lead batten strips to have a purity of 99.5% meeting the Federal specification QQ-L-201f, Grades "B, C or D". Lead batten strips required behind vertical joints of lead backed gypsum wallboard (Item 6) and optional at remaining stud locations.

10. **Lead Discs or Tabs —** (Not Shown, For Use With Item 4A) — Used in lieu of or in addition to the lead batten strips (Item 9) or optional at other locations - Max 3/4 in. diam by max 0.125 in. thick lead discs compression fitted or adhered over steel screw heads or max 1/2 in. by 1-1/4 in. by max 0.125 in. thick lead tabs placed on gypsum boards (Item 4A) underneath screw locations prior to the installation of the screws. Lead discs or tabs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C".

10A. **Lead Discs —** (Not Shown, for use with Item 4C) — Max 5/16 in. diam by max 0.140 in. thick lead discs compression fitted or adhered over steel screw heads. Lead discs to have a purity of 99.5% meeting the Federal Specification QQ-L-201f, Grades "B, C or D".

11. **Lead Batten Strips —** (Not Shown, For Use With Item 4B) — Lead batten strips, 2 in. wide, max 10 ft long with a max thickness of 0.142 in. Strips placed on the face of studs and attached to the stud with two min. 1 in. long min. Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip or with one min. 1 in. long min. Type S-8 pan head steel screw at the top of the strip. Lead batten strips to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Lead batten strips required behind vertical joints of lead backed gypsum wallboard (Item 4B) and optional at remaining stud locations.

12. **Lead Tabs —** (Not Shown, For Use With Item 4B) — 2 in. wide, 5 in. long with a max thickness of 0.142 in. Tabs friction-fit around front face of stud, the stud folded back flange, and the back face of the stud. Tabs required at each location where a screw (that secures the gypsum boards, Item 4B) will penetrate the steel stud. Lead tabs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Lead tabs may be held in place with standard adhesive tape if necessary.

*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**

Last Updated on 2022-02-14

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,
PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

# UL ASSEMBLY DETAILS

SHEET NUMBER

# G-0.0.6

5/10/2022 6:01:20 PM BIM 360://210211 - NFBIA North Terminal Renovations – Task #2 (2021)/210211 - Panama City Airport NWFB_TASK-2_R21.rvt

at maximum 6 in. OC. in the perimeter and 12 in. OC. in the field. When used, gypsum panels attached over OSB or plywood panels and fastener lengths for gypsum panels increased by min. 1/2 in.

4. **Batts and Blankets* —** (Required as indicated under Item 5) — Mineral wool batts, friction fitted between studs and runners. Min nom thickness as indicated under Item 5.
See **Batts and Blankets** (BKNV or BZJZ) Categories for names of Classified companies.

4A. **Batts and Blankets* —** (Optional) — Placed in stud cavities, any glass fiber or mineral wool insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance.
See **Batts and Blankets** (BKNV or BZJZ) Categories for names of Classified companies.

4B. **Fiber, Sprayed* —** (Optional, for use with Type ULIX) Where insulation is required - Spray applied granulated mineral fiber material. The fiber is applied with adhesive at a minimum density of 4.0 pcf to completely fill the wall cavity in accordance with the application instructions supplied with the product. See **Fiber, Sprayed** (CCAZ).
**AMERICAN ROCKWOOL MANUFACTURING, LLC** — Type Rockwool Premium Plus

4C. **Foamed Plastic* —** (Where Batts and Blankets*, Item 4, are optional, for use with Item 5K) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity, for 2 hour rated assemblies only. When foamed plastic is used, minimum stud depth shall be 3-1/2 in.

**CARLISLE SPRAY FOAM INSULATION —** Types SealTite Pro Closed Cell (CC), SealTite Pro Open Cell (OC), SealTite Pro OCX, SealTite Pro No Trim 21, SealTite Pro One Zero, Foamsulate Closed Cell, Foamsulate OCX, Foamsulate 70, and Foamsulate HFO.

5. **Gypsum Board* —** Gypsum panels with beveled, square or tapered edges, applied vertically or horizontally. Vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Vertical joints in adjacent layers (multilayer systems) staggered one stud cavity. Horizontal joints need not be backed by steel framing. Horizontal edge joints and horizontal butt joints on opposite sides of studs need not be staggered. Horizontal edge joints and horizontal butt joints in adjacent layers (multilayer systems) staggered a min of 12 in. Horizontal edge joints and horizontal butt joints in adjacent layers (multilayer systems) with Type ULIX need not be staggered. The thickness and number of layers for the 1 hr, 2 hr, 3 hr and 4 hr ratings are as follows:

**Gypsum Board Protection on Each Side of Wall**

| Rating, Hr | Min Stud Depth, in. Items 2, 2C, 2D, 2F, 2G, 2O | No. of Layers & Thkns of Panel | Min Thkns of Insulation (Item 4) |
|---|---|---|---|
| 1 | 3-1/2 | 1 layer, 5/8 in. thick | Optional |
| 1 | 2-1/2 | 1 layer, 1/2 in. thick | 1-1/2 in. |
| 1 | 1-5/8 | 1 layer, 3/4 in. thick | Optional |
| 2 | 1-5/8 | 2 layers, 1/2 in. thick | Optional |
| 2 | 1-5/8 | 2 layers, 5/8 in. thick | Optional |
| 2 | 3-1/2 | 1 layer, 3/4 in. thick | 3 in. |
| 3 | 1-5/8 | 3 layers, 1/2 in. thick | Optional |
| 3 | 1-5/8 | 2 layers, 3/4 in. thick | Optional |
| 3 | 1-5/8 | 3 layers, 5/8 in. thick | Optional |
| 4 | 1-5/8 | 4 layers, 5/8 in. thick | Optional |
| 4 | 1-5/8 | 4 layers, 1/2 in. thick | Optional |
| 4 | 2-1/2 | 2 layers, 3/4 in. thick | 2 in. |

**CGC INC** — 1/2 in. thick Type C, IP-X2 or IPC-AR; WRC, 5/8 in. thick Type AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULIX, WRX or WRC; 3/4 in. thick Types IP-X3 or ULTRACODE

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — 1/2 in. thick Type C and 5/8 in. thick Type SCX

**UNITED STATES GYPSUM CO** — 1/2 in. thick Type C, IP-X2, IPC-AR or WRC; 5/8 in. thick Type SCX, SGX, SHX, ULIX, WRX, IP-X1, AR, C, WRC, FRX-G, IP-AR, IP-X2, IPC-AR; 3/4 in. thick Types IP-X3 or ULTRACODE

**USG BORAL DRYWALL SFZ LLC** — 1/2 in. Type C; 5/8 in. Types C, SCX, SGX, ULTRACODE

**USG MEXICO S A DE C V** — 1/2 in. thick Type C, IP-X2, IPC-AR or WRC; 5/8 in. thick Type AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, WRX, WRC or, 3/4 in. thick Types IP-X3 or ULTRACODE

When Item 7B, **Steel Framing Members***, is used, Nonbearing Wall Rating is limited to 1 Hr. Min. stud depth is 3-1/2 in., min. thickness of insulation (Item 4) is 3 in., and two layers of gypsum board panels (1/2 in. or 5/8 in. thick) shall be attached to furring channels as described in Item 6. One layer of gypsum board panels (1/2 in. or 5/8 in. thick) attached to opposite side of stud without furring channels as described in Item 6.

5A. **Gypsum Board* —** (As an alternate to Item 5) — 5/8 in. thick, 24 to 54 in. wide, applied horizontally as the outer layer to one side of the assembly. Secured as described in Item 6.
**CGC INC** — Type SHX.

**UNITED STATES GYPSUM CO** — Type FRX-G, SHX.

**USG MEXICO S A DE C V** — Type SHX.

5B. **Gypsum Board* —** (Not Shown) — As an alternate to Item 5 when used as the base layer on one or both sides of wall when 5/8 in or 3/4 in. thick products are specified. For direct attachment only to steel studs Item 2A, (not to be used with Item 3) — Nom 5/8 in. or 3/4 in. may be used as alternate to all 5/8 in. or 3/4 in. shown in Item 5, Wallboard Protection on Each Side of Wall table. Nom 5/8 in. or 3/4 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Gypsum board secured to 20 MSG steel studs Item 2A with 1-1/4 in. long Type S-12 steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. To be used with Lead Batten Strips (see Item 11) or Lead Discs or Tabs (see Item 12).
**RAY-BAR ENGINEERING CORP** — Type R8-LBG

5C. **Gypsum Board* —** (For Use With Item 2B) — Rating Limited to 1 Hour. 5/8 in. thick, 48 in. wide, Gypsum panels with beveled, square or tapered edges, applied vertically or horizontally. (Vertical Application) - The gypsum board is to be installed on each side of the studs with 1 in. long Type S coated steel screws spaced 8 in. OC starting 4 in. from the edge of the board at the vertical edges and 12 in. OC starting 6 in. from the edge of the board at the center of each board. Gypsum boards are to be secured to the top and bottom track with screws spaced 8 in. OC starting 4 in. from the board edge. Fasteners shall not penetrate through both the stud and the track at the same time. Vertical joints are to be centered over studs and staggered one stud cavity on opposite sides of studs. (Horizontal Application) - The gypsum board is to be installed on each side of the studs with 1 in. long Type S coated steel screws spaced 8 in. OC starting 4 in. from the edge of the board at the vertical edges and 12 in. OC starting 6 in. from the edge of the board at the center of each board. Gypsum boards are to be secured to the top and bottom track with screws spaced 8 in. OC starting 4 in. from the board edge. Fasteners shall not penetrate through both the stud and the track at the same time. All horizontal joints are to be backed as outlined under section VI of Volume 1 in the Fire Resistive Directory.
**CGC INC** — Type SCX, ULIX.

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Type SCX

**UNITED STATES GYPSUM CO** — Type SCX, SGX, ULIX.

**USG BORAL DRYWALL SFZ LLC** — Type SCX

**USG MEXICO S A DE C V** — Type SCX

**MARINO/WARE, DIV OF WARE INDUSTRIES INC** — Viper25™

**IMPERIAL MANUFACTURING GROUP INC** — Viper25™

2C. **Framing Members* — Steel Studs —** Not Shown — In lieu of Item 2 — proprietary channel shaped steel studs, min depth as indicated under Item 5, spaced a max if 24 in. OC, fabricated from min 0.018 in. thick galv steel. Studs cut 3/8 in. to 3/4 in. less in lengths than assembly heights.
**CALIFORNIA EXPANDED METAL PRODUCTS CO** — Viper20™

**MARINO/WARE, DIV OF WARE INDUSTRIES INC** — Viper20™

**IMPERIAL MANUFACTURING GROUP INC** — Viper20™

2D. **Framing Members* — Steel Studs —** In lieu of Item 2 — Channel shaped studs, min depth as indicated under Item 5, spaced a max of 24 in. OC. Studs to be cut 3/4 in. less than assembly height.
**ALLSTEEL & GYPSUM PRODUCTS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

**CONSOLIDATED FABRICATORS CORP, BUILDING PRODUCTS DIV** — Type SUPREME D24/30EQD and Type SUPREME D20

**QUAIL RUN BUILDING MATERIALS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

**SCAFCO STEEL STUD MANUFACTURING CO** — Type SUPREME D24/30EQD and Type SUPREME D20

**STEEL CONSTRUCTION SYSTEMS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

**TELLING INDUSTRIES L L C** — Type SUPREME D24/30EQD and Type SUPREME D20

**UNITED METAL PRODUCTS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

2E. **Framing Members* — Steel Studs —** (Not Shown, As an alternate to Item 2) — For use with Items 5F or 5G or 5I or Type ULIX only, channel shaped studs, min depth as indicated under Item 5F, 5G or 5I, fabricated from min. 0.015 in. (min bare metal thickness) galvanized steel, spaced a max of 24 in. OC. Studs to be cut 3/4 in. less than assembly height.
**CLARKDIETRICH BUILDING SYSTEMS** — CD ProSTUD

**DMFCWBS L L C** — ProSTUD

**MBA METAL FRAMING** — ProSTUD

**RAM SALES L L C** — Ram ProSTUD

**STEEL STRUCTURAL PRODUCTS L L C** — Tri-S ProSTUD

2F. **Framing Members* — Steel Studs —** Not Shown — In lieu of Item 2 — proprietary channel shaped steel studs, minimum width indicated under Item 5, 1-1/4 in. deep fabricated from min 0.015 in. (min bare metal thickness) galvanized steel. Studs 3/8 in. to 3/4 in. less in lengths than assembly heights.
**SUPER STUD BUILDING PRODUCTS** — The Edge

2G. **Framing Members* — Steel Studs —** Not Shown — In lieu of Item 2 — proprietary channel shaped studs, minimum width indicated under Item 5, Studs to be cut 3/8 to 3/4 in less than the assembly height.
**STUDCO BUILDING SYSTEMS** — CROCSTUD

2H. **Framing Members* — Steel Studs —** (Not Shown, As an alternate to Item 2) — Fabricated from min. 0.015 in. (min bare metal thickness) galvanized steel, spaced a max of 24 in. OC. Studs to be cut 3/4 in. less than assembly height.
**TELLING INDUSTRIES L L C** — TRUE-STUD™

2I. **Framing Members* — Steel Studs —**

2J. **Framing Members* — Metal Studs —** Not Shown — In lieu of Item 2 — proprietary channel shaped steel studs, min depth as indicated under Item 5, spaced a max if 24 in. OC, fabricated from min 0.018 in. thick galv steel. Studs cut 3/8 in. to 3/4 in. less in lengths than assembly heights

2K. **Framing Members* — Steel Studs —** As an alternate to Item 2 — For use with Item 1, channel shaped studs, fabricated from min 25 MSG corrosion-protected steel, min depth as indicated under Item 5, spaced a max of 24 in. OC. Studs to be cut 3/8 to 3/4 in. less than assembly height.
**EB METAL INC** — NITROSTUD

2L. **Framing Members* — Steel Studs —** As an alternate to Item 2 — For use with Item 1, channel shaped studs, fabricated from min 25 MSG corrosion-protected steel, min depth as indicated under Item 5, spaced a max of 24 in. OC. Studs to be cut 3/8 to 3/4 in. less than assembly height.
**OLMAR SUPPLY INC** — PRIMESTUD

2M. **Framing Members* — Steel Studs —** As an alternate to Item 2 — For use with Item 1, channel shaped studs, fabricated from min 25 MSG corrosion-protected steel, min depth as indicated under Item 5, spaced a max of 24 in. OC. Studs to be cut 3/8 to 3/4 in. less than assembly height.
**MARINO/WARE, DIV OF WARE INDUSTRIES INC** — StudRite™

2N. **Framing Members*— Steel Studs —** As an alternate to Item 2 — proprietary channel shaped steel studs, min depth 3-1/2 in. and as indicated under Item 5, spaced a max of 24 in. OC, fabricated from min 0.018 in. thick galv steel. Studs cut 3/8 in. to 3/4 in. less in length than assembly height.
**RESCUE METAL FRAMING, L L C** — AlphaSTUD

2O. **Framing Members* — Steel Studs —** As an alternate to Item 2 — proprietary channel shaped steel studs, min width as indicated under Item 5, galv steel. Studs to be cut 3/8 to 3/4 in. less in lengths than assembly height. Spaced 24 in. OC max.
**RONDO BUILDING SERVICES PTY LTD** — Rondo Lipped Wall Stud

2P. **Framing Members* — Steel Studs —** As an alternate to Item 2 — proprietary channel shaped steel studs, min width as indicated under Item 5, min 25 MSG galv steel. Studs to be cut 3/8 to 3/4 in. less in lengths than assembly height. Spaced 24 in. OC max.
**OEG BUILDING MATERIALS** — OEG Stud

2Q. **Framing Members* — Steel Studs —** Not Shown — In lieu of Item 2 — For use with Item 1Q, proprietary channel shaped steel studs, min depth as indicated under Item 5, spaced a max of 24 in. OC, fabricated from min 25 MSG (0.018 in. min. bare metal thickness). Studs cut 3/8 in. to 3/4 in. less in lengths than assembly heights.
**CALIFORNIA EXPANDED METAL PRODUCTS CO** — Viper X

3. **Wood Structural Panel Sheathing —** (Optional, For use with Item 5 Only) — (Not Shown) — 4 ft wide, 7/16 in. thick oriented strand board (OSB) or 15/32 in. thick structural 1 sheathing (plywood) complying with DOC PS1 or PS2, or APA Standard PRP-108, manufactured with exterior glue, applied horizontally or vertically to the steel studs. Vertical joints centered on studs, and staggered one stud space from wallboard joints. Attached to studs with flat-head self-drilling tapping screws with a min. head diam. of 0.292 in.

1B. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2C, proprietary channel shaped runners, 1-1/4 in. wide by 3-5/8 in. deep fabricated from min 0.018 in. thick galv steel, attached to floor and ceiling with fasteners spaced 24 in. OC max.
**CALIFORNIA EXPANDED METAL PRODUCTS CO** — Viper20™ Track

**MARINO/WARE, DIV OF WARE INDUSTRIES INC** — Viper20™ Track

**IMPERIAL MANUFACTURING GROUP INC** — Viper20™ Track

1C. **Framing Members* — Floor and Ceiling Runners —** (Not Shown) — In lieu of Item 1 — Channel shaped, attached to floor and ceiling with fasteners 24 in. OC. max.
**ALLSTEEL & GYPSUM PRODUCTS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

**CONSOLIDATED FABRICATORS CORP, BUILDING PRODUCTS DIV** — Type SUPREME D24/30EQD and Type SUPREME D20

**QUAIL RUN BUILDING MATERIALS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

**SCAFCO STEEL STUD MANUFACTURING CO** — Type SUPREME D24/30EQD and Type SUPREME D20

**STEEL CONSTRUCTION SYSTEMS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

**TELLING INDUSTRIES L L C** — Type SUPREME D24/30EQD and Type SUPREME D20

**UNITED METAL PRODUCTS INC** — Type SUPREME D24/30EQD and Type SUPREME D20

1D. **Floor and Ceiling Runners —** (Not Shown) — For use with Item 2A — Channel shaped, fabricated from min 20 MSG corrosion-protected or galv steel, min depth to accommodate stud size, with min 1 in. long legs, attached to floor and ceiling with fasteners spaced max 24 in. OC.

1E. **Framing Members* — Floor and Ceiling Runners —** (Not Shown, As an alternate to Item 1) — For use with Items 2E, 5F or 5G or 5I only, channel shaped, fabricated from min. 0.015 in. (min bare metal thickness) galvanized steel, attached to floor and ceiling with fasteners 24 in. OC. max.
**CLARKDIETRICH BUILDING SYSTEMS** — CD ProTRAK

**DMFCWBS L L C** — ProTRAK

**MBA METAL FRAMING** — ProTRAK

**RAM SALES L L C** — Ram ProTRAK

**STEEL STRUCTURAL PRODUCTS L L C** — Tri-S ProTRAK

1F. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2F, proprietary channel shaped runners, minimum width to accommodate stud size, with 1- 1/8 in. long legs fabricated from min 0.015 in. (min bare metal thickness) galv steel, attached to floor and ceiling with fasteners spaced 24 in. OC max.
**SUPER STUD BUILDING PRODUCTS** — The Edge

1G. **Framing Members* — Floor and Ceiling Runner —** For use with Item 2G, proprietary channel shaped runners, minimum width to accommodate stud size attached to floor and ceiling with fasteners 24 in. OC max.
**STUDCO BUILDING SYSTEMS** — CROCSTUD Track

1H. **Floor and Ceiling Runners —** (Not Shown) — Channel shaped, fabricated from min 0.02 in. galv steel, min width to accommodate stud size, with min 1 in. long legs, for use with studs specified below and fabricated from min 0.018 in. galv steel or thicker, attached to floor and ceiling with fasteners spaced max 24 in. OC.
**MARINO/WARE, DIV OF WARE INDUSTRIES INC** — Viper20™ Track VT100

**IMPERIAL MANUFACTURING GROUP INC** — Viper20™ Track VT100

1I. **Framing Members* — Floor and Ceiling Runners —** (Not Shown, As an alternate to Item 1) — For use with Items 2H, channel shaped, fabricated from min. 0.015 in. (min bare metal thickness) galvanized steel, attached to floor and ceiling with fasteners 24 in. OC. max.
**TELLING INDUSTRIES L L C** — TRUE-TRACK™

1J. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2I, proprietary channel shaped runners, 3-5/8 in. deep attached to floor and ceiling with fasteners 24 in. OC max.

1K. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2J, proprietary channel shaped runners, 1-1/4 in. wide by 3-5/8 in. deep fabricated from min 0.018 in. thick galv steel, attached to floor and ceiling with fasteners spaced 24 in. OC max.

1L. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2N, proprietary channel shaped runners, 1-1/4 in. wide by min. 3-1/2 in. deep fabricated from min 0.018 in. thick galv steel, attached to floor and ceiling with fasteners spaced 24 in. OC max.
**RESCUE METAL FRAMING, L L C** — AlphaTRAK

1M. **Framing Members* — Floor and Ceiling Runners —** Not Shown — As an alternate to Item 1 — For use with Item 2O, proprietary channel shaped runners, min width to accommodate stud size, galv steel, attached to floor and ceiling with fasteners spaced 24 in. OC max.
**RONDO BUILDING SERVICES PTY LTD** — Rondo Wall Track

1N. **Framing Members* — Floor and Ceiling Runners —** Not Shown — As an alternate to Item 1 — For use with Item 2P, proprietary channel shaped runners, min width to accommodate stud size, galv steel, attached to floor and ceiling with fasteners spaced 24 in. OC max.
**OEG BUILDING MATERIALS** — OEG Track

1O. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2Q, proprietary channel shaped runners, min width to accommodate stud size, fabricated from min. 25 MSG (0.018 in. min. bare metal thickness), attached to floor and ceiling with fasteners spaced 24 in. OC max.
**CALIFORNIA EXPANDED METAL PRODUCTS CO** — Viper X Track

2. **Steel Studs —** Channel shaped, fabricated from min 25 MSG corrosion-protected steel, min depth as indicated under Item 5, spaced a max of 24 in. OC. Studs to be cut 3/8 to 3/4 in. less than assembly height.

2A. **Steel Studs —** (As an alternate to Item 2, For use with Items 5B, 5E, 5H, 5J or Type ULIX) — Channel shaped, fabricated from min 20 MSG corrosion-protected or galv steel, 3-1/2 in. min depth, spaced a max of 16 in. OC. Studs friction-fit into floor and ceiling runners. Studs to be cut 5/8 to 3/4 in. less than assembly height.

2B. **Framing Members* - Steel Studs —** (As an alternate to Item 2, For use with Items 5C, 5I or Type ULIX) — Proprietary channel shaped studs, 3-5/8 in. deep spaced a max of 24 in. OC. Studs to be cut 3/4 in less than the assembly height and installed with a 1/2 in. gap between the end of the stud and track at the bottom of the wall. For direct attachment of gypsum board only.
**CALIFORNIA EXPANDED METAL PRODUCTS CO** — Viper25™

**CRACO MFG INC** — SmartStud25™

UL Product iQ™

# BXUV.U419 - Fire-resistance Ratings - ANSI/UL 263

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

## Fire-resistance Ratings - ANSI/UL 263

### BXUV - Fire Resistance Ratings - ANSI/UL 263 Certified for United States

### BXUV7 - Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada


See General Information for Fire-resistance Ratings - ANSI/UL 263 Certified for United States
Design Criteria and Allowable Variances

See General Information for Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada
Design Criteria and Allowable Variances

Design No. **U419**

March 2, 2022

**Nonbearing Wall Ratings — 1, 2, 3 or 4 Hr (See Items 4 & 5 through 5J)**
*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**




1. **Floor and Ceiling Runners —** (Not Shown) — For use with Item 2 — Channel shaped, fabricated from min 25 MSG corrosion-protected steel, min depth to accommodate stud size, with min 1-1/4 in. long legs, attached to floor and ceiling with fasteners 24 in. OC max.

1A. **Framing Members* — Floor and Ceiling Runner —** Not Shown — In lieu of Item 1 — For use with Item 2B, proprietary channel shaped runners, 3-5/8 in. deep attached to floor and ceiling with fasteners 24 in. OC max.
**CALIFORNIA EXPANDED METAL PRODUCTS CO** — Viper25™ Track

**CRACO MFG INC** — SmartTrack25™

**MARINO/WARE, DIV OF WARE INDUSTRIES INC** — Viper25™ Track

**IMPERIAL MANUFACTURING GROUP INC** — Viper25™ Track

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

**NORTH TERMINAL EXPANSION / IMPROVEMENTS**

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**UL ASSEMBLY DETAILS**

SHEET NUMBER

**G-0.0.7**

5/10/2022 6:01:21 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK 2_R21.rvt

11. **Lead Batten Strips —** (Not Shown, For Use With Item 5B) — Lead batten strips, min 1-1/2 in. wide, max 10 ft long with a max thickness of 0.125 in. Strips placed on the interior face of studs and attached from the exterior face of the stud with two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead batten strips to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Lead batten strips required behind vertical joints of lead backed gypsum wallboard (Item 5B) and optional at remaining stud locations. Required behind vertical joints.

11A. **Lead Batten Strips —** (Not Shown, For Use With Item 5H) — Lead batten strips, 2 in. wide, max 10 ft long with a max thickness of 0.140 in. Strips placed on the face of studs and attached to the stud with two min. 1 in. long min. Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip or with one min. 1 in. long min. Type S-8 pan head steel screw at the top of the strip. Lead batten strips to have a purity of 99.5% meeting the Federal specification QQ-L-201f, Grades "B, C or D". Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations.

12. **Lead Discs or Tabs —** (Not Shown, For Use With Item 5B) — Used in lieu of or in addition to the lead batten strips (Item 11) or optional at other locations - Max 3/4 in. diam by max 0.125 in. thick lead discs compression fitted or adhered over steel screw heads or max 1/2 in. by 1-1/4 in. by max 0.125 in. thick lead tabs placed on gypsum boards (Item 5B) underneath screw locations prior to the installation of the screws. Lead discs or tabs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C".

12A. **Lead Discs —** (Not Shown, for use with Item 5H) — Max 5/16 in. diam by max 0.140 in. thick lead discs compression fitted or adhered over steel screw heads. Lead discs to have a purity of 99.5% meeting the Federal Specification QQ-L-201f, Grades "B, C or D".

13. **Lead Batten Strips —** (Not Shown, For Use With Item 5E) — Lead batten strips, 2 in. wide, max 10 ft long with a max thickness of 0.142 in. Strips placed on the face of studs and attached to the stud with two min. 1 in. long min. Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip or with one min. 1 in. long min. Type S-8 pan head steel screw at the top of the strip. Lead batten strips to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Lead batten strips required behind vertical joints of lead backed gypsum wallboard (Item 5E) and optional at remaining stud locations.

14. **Lead Tabs —** (Not Shown, For Use With Item 5E) — 2 in. wide, 5 in. long with a max thickness of 0.142 in. Tabs friction-fit around front face of stud, the stud folded back flange, and the back face of the stud. Tabs required at each location where a screw (that secures the gypsum boards, Item 5E) will penetrate the steel stud. Lead tabs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Lead tabs may be held in place with standard adhesive tape if necessary.

15. **Barrier Mesh —** (Optional, Not Shown) - Attached to steel studs on one or both sides of the wall using Barrier Mesh Clips spaced at maximum 12 inches on center vertically, using a flat head type screw penetrating through the steel at least 3/8 of an inch. For Steel Studs less than 0.033 inches in thickness, use self-piercing screws. For Steel Studs equal to or greater than 0.033 inches in thickness, use steel drill screws (self-tapping). Gypsum Board (Item 5) to be installed directly over the Barrier Mesh using prescribed screw patterns with lengths increased by a minimum 1/8 in. Barrier Mesh may be installed with the long dimension of the diamond pattern positioned vertically or horizontally. Barrier Mesh joints may occur as butt joints at the framing members and secured using the Barrier Mesh Clips or occur in between framing members as overlapping joints secured using 18 SWG wire ties spaced a maximum 12 in. on center.
**CLARKDIETRICH BUILDING SYSTEMS** — Barrier Mesh, Barrier Mesh Clips

*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**

Last Updated on 2022-03-02

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

spaced 24 in. OC. Second layer- 1-5/8 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. OC. Third layer- 2-1/4 in. long for 1/2 in., 5/8 in. thick panels or 2-5/8 in. long for 5/8 in. thick panels, spaced 12 in. OC. Screws offset min 6 in. from layer below. **Four-layer systems:** First layer- 1 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. OC. Second layer- 1-5/8 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. OC. Third layer- 2-1/4 in. long for 1/2 in. thick panels or 2-5/8 in. long for 5/8 in. thick panels, spaced 24 in. OC. Fourth layer- 2-5/8 in. long for 1/2 in. thick panels or 3 in. long for 5/8 in. thick panels, spaced 12 in. OC. Screws offset min 6 in. from layer below.

7. **Furring Channels —** (Optional, Not Shown, for single or double layer systems) — Resilient furring channels fabricated from min 25 MSG corrosion-protected steel, spaced vertically a max of 24 in. OC. Flange portion attached to each intersecting stud with 1/2 in. long Type S-12 steel screws. Not for use with Item 5A.

7A. **Framing Members* —** (Optional on one or both sides, not shown, for single or double layer systems) — As an alternate to Item 7, furring channels and Steel Framing Members as described below:
a. **Furring Channels —** Formed of No. 25 MSG galv steel. 2-9/16 in. or 2-23/32 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board attached to furring channels as described in Item 6. Not for use with Item 5A.

b. **Steel Framing Members* —** Used to attach furring channels (Item 7Aa) to studs (Item 2). Clips spaced max. 48 in. OC. RSIC-1 and RSIC-1 (2.75) clips secured to studs with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center grommet. RSIC-V and RSIC-V (2.75) clips secured to studs with No. 8 x 9/16 in. minimum self-drilling, S-12 steel screw through the center hole. Furring channels are friction fitted into clips. RSIC-1 and RSIC-V clips for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) and RSIC-V (2.75) clips for use with 2-23/32 in. wide furring channels.
**PAC INTERNATIONAL L L C** — Types RSIC-1, RSIC-V, RSIC-1 (2.75), RSIC-V (2.75).

7B. **Framing Members* —** (Optional, Not Shown) — As an alternate to Item 7, for single or double layer systems, furring channels and Steel Framing Members on only one side of studs as described below:
a. **Furring Channels —** Formed of No. 25 MSG galv steel, spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Batts and Blankets placed in stud cavity as described in Item 5. Two layers of gypsum board attached to furring channels as described in Item 5. Not for use with Item 5A.

b. **Steel Framing Members* —** Used to attach furring channels (Item 7Ba) to one side of studs (Item 2) only. Clips spaced 48 in. OC., and secured to studs with two No. 8 x 2-1/2 in. coarse drywall screws, one through the hole at each end of the clip. Furring channels are friction fitted into clips.
**KINETICS NOISE CONTROL INC** — Type Isomax

7C. **Framing Members* —** (Not Shown) — (Optional on one or both sides, not shown, for single or double layer systems) — As an alternate to Item 7, furring channels and Steel Framing Members as described below:
a. **Furring Channels —** Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board attached to furring channels as described in Item 6. Not for use with Item 5A.

b. **Steel Framing Members* —** Used to attach furring channels (Item 7Ca) to studs (Item 2). Clips spaced max. 48 in. OC. GENIECLIPS secured to studs with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center grommet. Furring channels are friction fitted into clips.
**PLITEQ INC** — Type GENIECLIP

7D. **Steel Framing Members* —** (Optional on one or both sides, not shown, for single or double layer systems) — Furring channels and Steel Framing Members as described below:
a. **Furring Channels —** Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire.. Gypsum board attached to furring channels as described in Item 6. Not for use with Item 5A.

b. **Steel Framing Members* —** Used to attach furring channels (Item 7Da) to studs. Clips spaced 48 in. OC., and secured to studs with 2 in. coarse drywall screw with 1 in. diam washer through the center hole. Furring channels are friction fitted into clips
**STUDCO BUILDING SYSTEMS** — RESILMOUNT Sound Isolation Clips - Type A237 or A237R

7E. **Steel Framing Members* —** (Optional on one or both sides, not shown, for single or double layer systems) — Furring channels and Steel Framing Members as described below:
a. **Furring Channels —** Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item 7Eb. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire.. Gypsum board attached to furring channels as described in Item 6. Not for use with Item 5A and 5E.

b. **Steel Framing Members* —** Used to attach furring channels (Item 7Ea) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips.
**REGUPOL AMERICA** — Type SonusClip

7F. **Steel Framing Members* —** (Optional on one or both sides, not shown, for single or double layer systems) — Resilient channels and Steel Framing Members as described below:
a. **Resilient Channels —** Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and secured in place with two No. 8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 in. from the center of the overlap. Gypsum board attached to resilient channels as described in Item 5. Not for use with Item 5A and 5E.

b. **Steel Framing Members* —** Used to attach resilient channels (Item 7Fa) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Resilient channels are secured to clips with one No. 10 x 1/2 in. pan-head self-drilling screw.
**KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip

7G. **Framing Members* —** (Optional on one or both sides, not shown, for single or double layer systems) — As an alternate to Item 7, furring channels and Steel Framing Members as described below:
a. **Furring Channels —** Formed of No. 25 MSG galv steel. 2-23/32 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board attached to furring channels as described in Item 6. Not for use with Item 5A.

b. **Steel Framing Members* —** Used to attach furring channels (Item 7Ga) to studs (Item 2). Clips spaced max. 48 in. OC. Clips secured to studs with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center hole. Furring channels are friction fitted into clips.
**CLARKDIETRICH BUILDING SYSTEMS** — Type ClarkDietrich Sound Clip

8. **Joint Tape and Compound —** Vinyl or casein, dry or premixed joint compound applied in two coats to joints and screw heads of outer layers. Paper tape, nom 2 in. wide, embedded in first layer of compound over all joints of outer layer panels. Paper tape and joint compound may be omitted when gypsum panels are supplied with a square edge.

9. **Siding, Brick or Stucco —** (Optional, Not Shown) — Aluminum, vinyl or steel siding, brick veneer or stucco, meeting the requirements of local code agencies, installed over gypsum panels. Brick veneer attached to studs with corrugated metal wall ties attached to each stud with steel screws, not more than each sixth course of brick.

10. **Caulking and Sealants* —** (Optional, Not Shown) — A bead of acoustical sealant applied around the partition perimeter for sound control.
**UNITED STATES GYPSUM CO** — Type AS

5D. **Gypsum Board* —** (As an alternate to Item 5) — 5/8 in. thick, 48 in. wide, applied vertically or horizontally. Secured as described in Item 6. For use with Items 1 and 2 only.
**CGC INC** — Type USGX

**UNITED STATES GYPSUM CO** — Type USGX

**USG BORAL DRYWALL SFZ LLC** — Type USGX

**USG MEXICO S A DE C V** — Type USGX

5E. **Gypsum Board* —** (Not Shown) — (As an alternate to Item 5 when used as the base layer on one or both sides of wall when 1/2 in. or 5/8 in thick products are specified, For direct attachment only to steel studs Item 2A, not to be used with Item 3). Nominal 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-1/4 in. long Type S-12 (or No. 6 by 1-1/4 in. long bugle head fine driller) steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field.
**NEW ENGLAND LEAD BURNING CO INC, DBA NELCO** — Nelco

5F. **Gypsum Board* —** (As an alternate to Item 5) — For use with Items 1E and 2E and limited to 1 Hour Rating only, Gypsum panels with beveled, square or tapered edges, applied vertically, and fastened to the steel studs with 1 in. long Type S screws spaced 8 in. OC along vertical and bottom edges and 12 in. OC in the field. Vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Steel stud depth shall be a minimum 3-5/8 in.
**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — Type SCX

**UNITED STATES GYPSUM CO** — 5/8 in. thick Type SCX, SGX, ULIX

**USG BORAL DRYWALL SFZ LLC** — 5/8 in. thick Type SCX, SGX

5G. **Gypsum Board* —** (As an alternate to Item 5) — For use with Items 1E and 2E only, Gypsum panels with beveled, square or tapered edges, applied vertically or horizontally, as specified in the table below and fastened to the steel studs as described in Item 6. Vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Vertical joints in adjacent layers (multilayer systems) staggered one stud cavity. Horizontal joints need not be backed by steel framing. Horizontal edge joints and horizontal butt joints on opposite sides of studs need not be staggered. Horizontal edge joints and horizontal butt joints in adjacent layers (multilayer systems) staggered a min of 12 in. The thickness and number of layers for the 2 hr, 3 hr and 4 hr ratings are as follows:

**Gypsum Board Protection on Each Side of Wall**

| Rating, Hr | Min Stud Depth, in. Item 2E | No. of Layers & Thickness of Panel | Min Thkns of Insulation (Item 4) |
|---|---|---|---|
| 2 | 1-5/8 | 2 layers, 1/2 in. thick | Optional |
| 2 | 1-5/8 | 2 layers, 5/8 in. thick | Optional |
| 3 | 1-5/8 | 3 layers, 1/2 in. thick | Optional |
| 3 | 1-5/8 | 3 layers, 5/8 in. thick | Optional |
| 4 | 1-5/8 | 4 layers, 5/8 in. thick | Optional |
| 4 | 1-5/8 | 4 layers, 1/2 in. thick | Optional |

**CGC INC** — 1/2 in. thick Type C, IP-X2 or IPC-AR;, 5/8 in. thick Type AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULIX or 3/4 in. thick Types IP-X3 or ULTRACODE

**THE SIAM GYPSUM INDUSTRY (SONGKHLA) CO** — 1/2 in. thick Types C and 5/8 in. thick SCX

**UNITED STATES GYPSUM CO** — 1/2 in. thick Type C, IP-X2, IPC-AR or; 5/8 in. thick Type SCX, SGX, SHX, IP-X1, AR, C, , FRX-G, IP-AR, IP-X2, IPC-AR, ULIX, 3/4 in. thick Types IP-X3 or ULTRACODE

**USG BORAL DRYWALL SFZ LLC** — 1/2 in. Type C; 5/8 in. Types C, SCX, SGX, ULTRACODE

**USG MEXICO S A DE C V** — 1/2 in. thick Type C, IP-X2, IPC-AR or; 5/8 in. thick Type AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, or; 3/4 in. thick Types IP-X3 or ULTRACODE

5H. **Gypsum Board* —** (Not Shown) — (As an alternate to Item 5 when used as the base layer on one or both sides of wall when 5/8 or 3/4 in thick products are specified, For direct attachment only to steel studs Item 2A, (not to be used with Item 3) – Nom 5/8 or 3/4 in. may be used as alternate to all 5/8 or 3/4 in. shown in Item 5, Wallboard Protection on Each Side of Wall table. Nom 5/8 or 3/4 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over 20 MSG steel studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-1/4 in. long Type S-12 steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. Gypsum board secured to 20 MSG steel studs Item 2B with 1-1/4 in. long Type S-12 steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. For Joint Compound see Item 5. To be used with Lead Batten Strips (see Item 11A) or Lead Discs (see Item 12A).
**MAYCO INDUSTRIES INC** — Type X-Ray Shielded Gypsum

5I. **Gypsum Board* —** (As an alternate to Item 5) — Nom. 5/8 in. thick gypsum panels with beveled, square or tapered edges installed as described in Item 5. Steel stud minimum depth shall be as indicated in Item 5.
**CGC INC** — Type ULIX, ULX

**UNITED STATES GYPSUM CO** — Type ULIX, ULX

**USG MEXICO S A DE C V** — Type ULX

5J. **Gypsum Board* —** (Not Shown) — (As an alternate to Item 5 when used as the base layer on one or both sides of wall when 1/2 in. or 5/8 in thick products are specified, For direct attachment only to steel studs Item 2A, not to be used with Item 3). Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-1/4 in. long Type S-12 steel screws gypsum panel steel screws spaced 8 in. OC at perimeter and 12 in. OC in the field. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 8 ft long with a max thickness of 0.14 in. placed on the face of studs and attached to the stud with construction adhesive and two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs, nominal 3/8 in. diam by max 0.085 in. thick. Compression fitted or adhered over the screw heads. Lead batten strips and discs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C".
**RADIATION PROTECTION PRODUCTS INC** — Type RPP - Lead Lined Drywall

5K. **Gypsum Board* —** (As an alternate to Item 5 when Foam Plastic insulation (Item 4C) is used) — Any 5/8 in. thick, 4 ft. wide, Gypsum Board listed in Item 5 above. Applied vertically with vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Gypsum panels secured to studs with 1 in. long Type S steel screws spaced 8 in. OC at perimeter and in the field. For 2 layer assemblies outer layer will be attached to studs over inner layer with the 1-5/8 in. long steel screws spaced 8 in. OC.

6. **Fasteners —** (Not Shown) — For use with Items 2 and 2F - Type S or S-12 steel screws used to attach panels to studs (Item 2) or furring channels (Item 7). **Single layer systems:** 1 in. long for 1/2 and 5/8 in. thick panels or 1-1/4 in. long for 3/4 in. thick panels, spaced 8 in. OC when panels are applied horizontally, or 8 in. OC along vertical and bottom edges and 12 in. OC in the field when panels are applied vertically. **Single layer system with Type ULIX:** 1 in. long, spaced 12 in. OC in the field and perimeter, when panels are applied horizontally or vertically.**Two layer systems:** First layer- 1 in. long for 1/2 and 5/8 in. thick panels or 1-1/4 in. long for 3/4 in. thick panels, spaced 16 in. OC. Second layer- 1-5/8 in. long for 1/2 in., 5/8 in. thick panels or 2-1/4 in. long for 3/4 in. thick panels, spaced 16 in. OC with screws offset 8 in. from first layer.**Three-layer systems:** First layer- 1 in. long for 1/2 in., 5/8 in. thick panels,

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**UL ASSEMBLY DETAILS**

SHEET NUMBER

**G-0.0.8**

5/10/2022 6:01:23 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

| | | | | |
|---|---|---|---|---|
| 16X12X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 16X16X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 18X6X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 20X4X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 20X8X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 20X12X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 8X8X5/8 | 0.55 | 0.069 | 0.126 | 0.184 |
| 10X10X5/8 | 0.55 | 0.069 | 0.126 | 0.184 |
| 12X8X5/8 | 0.55 | 0.069 | 0.126 | 0.184 |
| 16X12X5/8 | 0.56 | 0.068 | 0.124 | 0.181 |

| | | Required Thickness (in) | | |
|---|---|---|---|---|
| **HSS Pipe Size** | **A/P** | **60 min.** | **90 min.** | **120 min.** |
| 3x0.216 | 0.19 | 0.161 | 0.238 | 0.353 |
| 3.5x0.216 | 0.19 | 0.161 | 0.238 | 0.353 |
| 2.5X0.25 | 0.21 | 0.149 | 0.223 | 0.331 |
| 3X0.25 | 0.22 | 0.143 | 0.216 | 0.320 |
| 3.5X0.25 | 0.22 | 0.143 | 0.216 | 0.320 |
| 4X0.25 | 0.22 | 0.143 | 0.216 | 0.320 |
| 5X0.25 | 0.22 | 0.143 | 0.216 | 0.320 |
| 6X0.25 | 0.22 | 0.143 | 0.216 | 0.320 |
| 6.625X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 7X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 7.5X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 8.625X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 9.625X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 10X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 12.5X0.25 | 0.23 | 0.137 | 0.209 | 0.309 |
| 5X0.258 | 0.23 | 0.137 | 0.209 | 0.309 |
| 6X0.28 | 0.25 | 0.128 | 0.197 | 0.292 |
| 3 X 0.3 | 0.25 | 0.128 | 0.197 | 0.292 |
| 3.5X0.300 | 0.26 | 0.124 | 0.192 | 0.284 |
| 3.5X0.313 | 0.27 | 0.120 | 0.187 | 0.277 |
| 4X0.313 | 0.27 | 0.120 | 0.187 | 0.277 |
| 5X0.312 | 0.27 | 0.120 | 0.187 | 0.277 |
| 6X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 6.625X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 7X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 7.5X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 9.625X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 10X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 12.5X0.312 | 0.28 | 0.116 | 0.183 | 0.271 |
| 14X0.312 | 0.29 | 0.113 | 0.179 | 0.265 |
| 16X0.312 | 0.29 | 0.113 | 0.179 | 0.265 |
| 4X0.337 | 0.29 | 0.113 | 0.179 | 0.265 |
| 5X0.375 | 0.33 | 0.102 | 0.166 | 0.244 |
| 10X0.375 | 0.34 | 0.099 | 0.162 | 0.239 |
| 14X0.375 | 0.34 | 0.099 | 0.162 | 0.239 |
| 16X0.375 | 0.34 | 0.099 | 0.162 | 0.239 |
| 18X0.375 | 0.34 | 0.099 | 0.162 | 0.239 |
| 20X0.375 | 0.34 | 0.099 | 0.162 | 0.239 |
| 16X0.438 | 0.40 | 0.087 | 0.148 | 0.217 |
| 5X0.5 | 0.43 | 0.083 | 0.142 | 0.208 |
| 6X0.5 | 0.43 | 0.083 | 0.142 | 0.208 |
| 7X0.5 | 0.43 | 0.083 | 0.142 | 0.208 |
| 10X0.5 | 0.44 | 0.081 | 0.140 | 0.206 |
| 12.5X0.5 | 0.45 | 0.080 | 0.139 | 0.203 |
| 14X0.5 | 0.45 | 0.080 | 0.139 | 0.203 |
| 16X0.5 | 0.45 | 0.080 | 0.139 | 0.203 |
| 18X0.5 | 0.45 | 0.080 | 0.139 | 0.203 |
| 20X0.5 | 0.45 | 0.080 | 0.139 | 0.203 |
| 10X0.625 | 0.55 | 0.069 | 0.126 | 0.184 |
| 11.25X0.625 | 0.55 | 0.069 | 0.126 | 0.184 |
| 12X0.625 | 0.55 | 0.069 | 0.126 | 0.184 |

**LEIGH'S PAINTS** — FIRETEX FX5120 INVESTIGATED FOR INTERIOR CONDITIONED SPACE AND INTERIOR GENERAL PURPOSE

**SHERWIN WILLIAMS CO** — FIRETEX FX5120 INVESTIGATED FOR INTERIOR CONDITIONED SPACE AND INTERIOR GENERAL PURPOSE

*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**

Last Updated on 2013-03-22

The appearance of a company's name or product in this database does not in itself assure that products so identified have been manufactured under UL's Follow-Up Service. Only those products bearing the UL Mark should be considered to be Certified and covered under UL's Follow-Up Service. Always look for the Mark on the product.

UL permits the reproduction of the material contained in the Online Certification Directory subject to the following conditions: 1. The Guide Information, Assemblies, Constructions, Designs, Systems, and/or Certifications (files) must be presented in their entirety and in a non-misleading manner, without any manipulation of the data (or drawings). 2. The statement "Reprinted from the Online Certifications Directory with permission from UL" must appear adjacent to the extracted material. In addition, the reprinted material must include a copyright notice in the following format: "© 2022 UL LLC"

| | | | | |
|---|---|---|---|---|
| 14X14X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 16X12X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 16X16X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 20X8X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 4X4X3/8 | 0.32 | 0.104 | 0.168 | 0.247 |
| 5X3X3/8 | 0.32 | 0.104 | 0.168 | 0.247 |
| 6X2X3/8 | 0.32 | 0.104 | 0.168 | 0.247 |
| 5X4X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 6X3X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 5X5X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 6X4X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 6X6X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 7X3X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 7X4X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 7X5X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 8X2X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 8X3X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 8X4X3/8 | 0.33 | 0.102 | 0.166 | 0.244 |
| 7X7X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 8X6X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 10X4X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 8X8X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 10X6X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 10X10X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 12X4X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 12X6X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 12X8X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 12X12X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 14X4X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 14X6X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 14X10X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 14X14X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 16X4X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 16X8X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 16X12X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 18X6X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 20X4X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 20X8X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 16X16X3/8 | 0.34 | 0.099 | 0.162 | 0.239 |
| 4X4X1/2 | 0.42 | 0.084 | 0.144 | 0.211 |
| 5X3X1/2 | 0.42 | 0.084 | 0.144 | 0.211 |
| 5X5X1/2 | 0.43 | 0.083 | 0.142 | 0.208 |
| 6X4X1/2 | 0.43 | 0.083 | 0.142 | 0.208 |
| 6X6X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 7X5X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 7X7X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 8X4X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 8X6X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 10X4X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 8X8X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 10X6X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 12X4X1/2 | 0.44 | 0.081 | 0.140 | 0.206 |
| 12X6X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 14X4X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 10X10X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 12X8X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 12X12X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 14X6X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 14X10X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 14X14X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 16X4X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |
| 16X8X1/2 | 0.45 | 0.080 | 0.139 | 0.203 |

| | | | | |
|---|---|---|---|---|
| 5x3x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 6x2x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 5x4x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 5x5x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 6x3x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 6x4x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 7x3x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 8x2x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 7x4x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 7x7x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 8x3x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 8x4x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 8x6x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 8x8x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 10x2x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 10x4x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 10x6x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 10x10x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 12x2x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 12x4x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 12X6X1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 12x8x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 12x12x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 14x4x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 14x6x1/4 | 0.23 | 0.137 | 0.209 | 0.309 |
| 3X3X5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 3.5X3.5X5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 4x2x5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 4X3X5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 5x2x5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 4X4X5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 5X3X15/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 6x2x5/16 | 0.27 | 0.120 | 0.187 | 0.277 |
| 5X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 5X5X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 6X3X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 6X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 7X3X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 7X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 8X2X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 8X3X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 6X6X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 7X5X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 7X7X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 8X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 8X6X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 8X8X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 10X2X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 10X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 10X6X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 10X10X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 12X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 12X6X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 12X8X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 14X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 14X6X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 16X4X5/16 | 0.28 | 0.116 | 0.183 | 0.271 |
| 12X12X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 14X10X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 16X8X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 18X6X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |
| 20X4X5/16 | 0.29 | 0.113 | 0.179 | 0.265 |

UL Product iQ®

# BXUV.Y624 - Fire-resistance Ratings - ANSI/UL 263

Design/System/Construction/Assembly Usage Disclaimer

- Authorities Having Jurisdiction should be consulted in all cases as to the particular requirements covering the installation and use of UL Certified products, equipment, system, devices, and materials.
- Authorities Having Jurisdiction should be consulted before construction.
- Fire resistance assemblies and products are developed by the design submitter and have been investigated by UL for compliance with applicable requirements. The published information cannot always address every construction nuance encountered in the field.
- When field issues arise, it is recommended the first contact for assistance be the technical service staff provided by the product manufacturer noted for the design. Users of fire resistance assemblies are advised to consult the general Guide Information for each product category and each group of assemblies. The Guide Information includes specifics concerning alternate materials and alternate methods of construction.
- Only products which bear UL's Mark are considered Certified.

## BXUV - Fire Resistance Ratings - ANSI/UL 263 Certified for United States

## BXUV7 - Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada

See General Information for Fire-resistance Ratings - ANSI/UL 263 Certified for United States
Design Criteria and Allowable Variances


See General Information for Fire Resistance Ratings - CAN/ULC-S101 Certified for Canada
Design Criteria and Allowable Variances

### Design No. Y624

March 22, 2013

**Ratings - 1, 1-1/2 and 2 Hr (See Item 3)**

*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**




1. **Steel Tube Column —** Steel rectangular tube (ST) or pipe (SP) columns with the minimum sizes shown in the tables below.

2. **Primer Coating —** 50 micron (2 mil) thickness of an epoxy primer 100 micron (4 mil) thickness of a modified alkyd primer or 50 micron (2 mil) of an acrylic primer.

3. **Mastic & Intumescent Coating* —** Coating spray or brush applied in accordance with the manufacturer's instructions at the minimum average dry thickness shown in the thickness below. The thickness shown does not include primer thickness.

| | Required Thickness (mm) | | |
|---|---|---|---|
| **Hp/A** | **60 min.** | **90 min.** | **120 min.** |
| 210 | 4.09 | 6.04 | 8.96 |
| 205 | 4.01 | 5.94 | 8.80 |
| 200 | 3.92 | 5.83 | 8.65 |
| 195 | 3.84 | 5.73 | 8.49 |
| 190 | 3.75 | 5.63 | 8.34 |
| 185 | 3.67 | 5.52 | 8.18 |
| 180 | 3.58 | 5.42 | 8.03 |
| 175 | 3.50 | 5.32 | 7.87 |
| 170 | 3.41 | 5.22 | 7.72 |
| 165 | 3.33 | 5.11 | 7.56 |
| 160 | 3.25 | 5.01 | 7.40 |
| 155 | 3.16 | 4.91 | 7.25 |
| 150 | 3.08 | 4.80 | 7.09 |
| 145 | 2.99 | 4.70 | 6.94 |
| 140 | 2.91 | 4.60 | 6.78 |
| 135 | 2.82 | 4.49 | 6.63 |
| 130 | 2.74 | 4.39 | 6.47 |
| 125 | 2.65 | 4.29 | 6.32 |
| 120 | 2.57 | 4.18 | 6.16 |
| 115 | 2.49 | 4.08 | 6.00 |
| 110 | 2.40 | 3.98 | 5.85 |
| 105 | 2.32 | 3.87 | 5.69 |
| 100 | 2.23 | 3.77 | 5.54 |
| 95 | 2.15 | 3.67 | 5.38 |
| 90 | 2.06 | 3.57 | 5.23 |
| 85 | 1.98 | 3.46 | 5.07 |
| 80 | 1.89 | 3.36 | 4.92 |
| 75 | 1.81 | 3.26 | 4.76 |
| 70 | 1.72 | 3.15 | 4.61 |
| 65 | 1.64 | 3.05 | 4.45 |

| | | Required Thickness (in) | | |
|---|---|---|---|---|
| **HSS Tube Size** | **A/P** | **60 min.** | **90 min.** | **120 min.** |
| 2x2x1/4 | 0.21 | 0.149 | 0.223 | 0.331 |
| 2.5x2.5x1/4 | 0.21 | 0.149 | 0.223 | 0.331 |
| 3x2x1/4 | 0.21 | 0.149 | 0.223 | 0.331 |
| 3x3x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 3.5x3.5x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 4x2x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 4x3x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 4x4x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |
| 5x2x1/4 | 0.22 | 0.143 | 0.216 | 0.320 |

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**UL ASSEMBLY DETAILS**

SHEET NUMBER

**G-0.0.9**


5/10/2022 6:01:25 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## OCCUPANCY AREA LEGEND

- AIRPORT TERMINAL - CONCOURSE
- ASSEMBLY (A-3)
- BUSINESS (B)
- CIRCULATION
- RESTROOMS
- STORAGE (S)
- UTILITY AND MISCELLANEOUS (U)

## LIFE SAFETY PLAN LEGEND

- OCCUPANCY BOUNDARY
- EXIT TRAVEL DISTANCE - PATH OF TRAVEL
- AED — AUTOMATED EXTERNAL DEFIBRILLATOR
- FEC — FIRE EXTINGUISHER CABINET
- AED — EXISTING AUTOMATED EXTERNAL DEFIBRILLATOR
- FDVC W/FE — EXISTING FIRE HOSE CABINET
- FEC — EXISTING FIRE EXTINGUISHER CABINET
- EMERGENCY EXIT
- 1 HOUR RATED PARTITION
- 2 HOUR RATED PARTITION




**01 LIFE SAFETY PLAN - LEVEL 1**
1/8" = 1'-0"

5/10/2022 6:01:31 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**LIFE SAFETY PLAN - LEVEL 01**

SHEET NUMBER

**G-1.0.0**

## OCCUPANT LOAD SCHEDULE


| LEVEL | NAME | USE GROUP | OCCUPANCY TYPE | AREA | LOAD FACTOR | OCCUPANT LOAD |
|---|---|---|---|---|---|---|
| LEVEL 1 | | | | | | |
| LEVEL 1 | STORAGE | ACCESSORY STORAGE AREA | STORAGE (S) | 78 SF | 300 SF | 1 |
| LEVEL 1 | STORAGE | ACCESSORY STORAGE AREA | STORAGE (S) | 53 SF | 300 SF | 1 |
| | | | | 131 SF | | |
| LEVEL 2 | | | | | | |
| LEVEL 2 | WAITING AREA 5 | AIRPORT TERMINAL - WAITING AREA | ASSEMBLY (A-3) | 2432 SF | 15 SF | 162 |
| LEVEL 2 | BOARDING VESTIBULE | CIRCULATION | CIRCULATION | 213 SF | 0 SF | |
| LEVEL 2 | MECHANICAL ROOM | MECHANICAL EQUIPMENT ROOM | UTILITY AND MISCELLANEOUS (U) | 1847 SF | 300 SF | 6 |
| LEVEL 2 | CIRCULATION | CIRCULATION | CIRCULATION | 153 SF | 0 SF | |
| LEVEL 2 | WAITING AREA 2 | AIRPORT TERMINAL - WAITING AREA | ASSEMBLY (A-3) | 645 SF | 15 SF | 43 |
| LEVEL 2 | CONCOURSE | AIRPORT TERMINAL - CONCOURSE | CONCOURSE | 6003 SF | 100 SF | 60 |
| LEVEL 2 | ELECTRICAL | ELECTRICAL EQUIPMENT ROOM | UTILITY AND MISCELLANEOUS (U) | 104 SF | 300 SF | 1 |
| LEVEL 2 | WAITING AREA 1 | AIRPORT TERMINAL - WAITING AREA | ASSEMBLY (A-3) | 112 SF | 15 SF | 7 |
| LEVEL 2 | FUTURE CONCESSIONS | ACCESSORY AREA | BUSINESS (B) | 1277 SF | 100 SF | 13 |
| LEVEL 2 | RESTROOM 1 | RESTROOM | RESTROOM | 496 SF | 0 SF | |
| LEVEL 2 | RESTROOM 2 | RESTROOM | RESTROOM | 478 SF | 0 SF | |
| LEVEL 2 | RESTROOM 3 | RESTROOM | RESTROOM | 62 SF | 0 SF | |
| LEVEL 2 | JANITOR | ACCESSORY STORAGE AREA | STORAGE (S) | 43 SF | 300 SF | 1 |
| LEVEL 2 | STORAGE | ACCESSORY STORAGE AREA | STORAGE (S) | 46 SF | 300 SF | 1 |
| LEVEL 2 | WAITING AREA 3 | AIRPORT TERMINAL - WAITING AREA | ASSEMBLY (A-3) | 60 SF | 15 SF | 4 |
| LEVEL 2 | WAITING AREA 4 | AIRPORT TERMINAL - WAITING AREA | ASSEMBLY (A-3) | 113 SF | 15 SF | 8 |
| LEVEL 2 | COMM ROOM | IT EQUIPMENT ROOM | UTILITY AND MISCELLANEOUS (U) | 111 SF | 300 SF | 1 |
| | | | | 14193 SF | | |
| | | | | 14324 SF | | |

## OCCUPANCY AREA LEGEND

- AIRPORT TERMINAL - CONCOURSE
- ASSEMBLY (A-3)
- BUSINESS (B)
- CIRCULATION
- RESTROOMS
- STORAGE (S)
- UTILITY AND MISCELLANEOUS (U)

## LIFE SAFETY PLAN LEGEND

- OCCUPANCY BOUNDARY
- EXIT TRAVEL DISTANCE - PATH OF TRAVEL
- AED — AUTOMATED EXTERNAL DEFIBRILLATOR
- FEC — FIRE EXTINGUISHER CABINET
- AED — EXISTING AUTOMATED EXTERNAL DEFIBRILLATOR
- FDVC W/FE — EXISTING FIRE HOSE CABINET
- FEC — EXISTING FIRE EXTINGUISHER CABINET
- EMERGENCY EXIT
- 1 HOUR RATED PARTITION
- 2 HOUR RATED PARTITION







**01 LIFE SAFETY PLAN - LEVEL 2**
1/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**LIFE SAFETY PLAN - LEVEL 02**

SHEET NUMBER

**G-2.0.0**

5/10/2022 6:01:43 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK 2_R21.rvt



**03** **DEMOLITION PHOTO 02**
12" = 1'-0"



**02** **DEMOLITION PHOTO 01**
12" = 1'-0"

## DEMOLITION PLAN KEYNOTES:

| | |
|---|---|
| 1 | REMOVE EXISTING PARTITION. PATCH AND REPAIR EXISTING SURFACES THAT ARE TO REMAIN TO PREPARE FOR NEW FINISHES AS REQUIRED |
| 2 | REMOVE EXISTING DOOR, FRAME AND HARDWARE |
| 3 | REMOVE EXISTING STAIR AND HANDRAILS. PATCH AND REPAIR WALLS AS REQUIRED |
| 4 | REMOVE EXISTING CONCRETE SLAB |

## DEMOLITION FLOOR PLAN LEGEND:

- EXISTING OR BASE BUILDING PARTITIONS TO REMAIN
- EXISTING OR BASE BUILDING PARTITIONS TO BE REMOVED
- EXISTING DOOR TO BE REMOVED
- EXISTING SLAB TO BE REMOVED
- EXISTING FINISH FLOOR TO BE REMOVED


## GENERAL NOTES:

REFER TO MEP DRAWINGS FOR FURTHER COORDINATION.


CORE SLAB - COORDINATE WITH ELECTRICAL FOR FLOOR BOX LOCATIONS.

1

## AIRSIDE APRON




**01** **DEMOLITION PLAN - LEVEL 01**
1/8" = 1'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**DEMOLITION FLOOR PLAN - LEVEL 01**

SHEET NUMBER

# A-1.0.1

5/10/2022 5:58:42 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## GENERAL NOTES:

REFER TO MEP DRAWINGS FOR FURTHER COORDINATION.


CORE SLAB - COORDINATE WITH ELECTRICAL FOR FLOOR BOX LOCATIONS.

## DEMOLITION PLAN KEYNOTES:


| | |
|---|---|
| 1 | REMOVE EXISTING PARTITION. PATCH AND REPAIR EXISTING SURFACES THAT ARE TO REMAIN TO PREPARE FOR NEW FINISHES AS REQUIRED |
| 2 | REMOVE EXISTING DOOR, FRAME AND HARDWARE |
| 3 | REMOVE EXISTING STAIR AND HANDRAILS. PATCH AND REPAIR WALLS AS REQUIRED |
| 4 | REMOVE EXISTING CONCRETE SLAB |

## DEMOLITION FLOOR PLAN LEGEND:

- EXISTING OR BASE BUILDING PARTITIONS TO REMAIN
- EXISTING OR BASE BUILDING PARTITIONS TO BE REMOVED
- EXISTING DOOR TO BE REMOVED
- EXISTING SLAB TO BE REMOVED
- EXISTING FINISH FLOOR TO BE REMOVED




**01 DEMOLITION PLAN - LEVEL 02**
1/8" = 1'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**DEMOLITION FLOOR PLAN - LEVEL 02**

SHEET NUMBER

**A-1.0.2**

5/10/2022 5:58:46 PM BIM 360://210211 - NWFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## GENERAL NOTES:

REFER TO MEP DRAWINGS FOR FURTHER COORDINATION.

COORDINATE NEW FLOOR BOX LOCATIONS AND CONDUIT ABOVE WITH ELECTRICAL.


1

## DEMOLITION CEILING PLAN KEYNOTES:


| | |
|---|---|
| 1 | REMOVE EXISTING CEILING |

## DEMOLITION REFLECTED CEILING PLAN LEGEND:

- EXISTING OR BASE BUILDING PARTITIONS TO REMAIN
- EXISTING OR BASE BUILDING PARTITIONS TO BE REMOVED
- EXISTING CEILING TO BE DEMOLISHED
- EXISTING GYPSUM SOFFIT TO REMAIN
- EXISTING CEILING TILES TO REMAIN (1)




**01 DEMOLITION CEILING PLAN - LEVEL 01**
1/8" = 1'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**DEMOLITION CEILING PLAN - LEVEL 01**

SHEET NUMBER

**A-1.1.1**


5/10/2022 5:58:49 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## DEMOLITION CEILING PLAN KEYNOTES:


| | |
|---|---|
| 1 | REMOVE EXISTING CEILING |

## DEMOLITION REFLECTED CEILING PLAN LEGEND:

- EXISTING OR BASE BUILDING PARTITIONS TO REMAIN
- EXISTING OR BASE BUILDING PARTITIONS TO BE REMOVED
- EXISTING CEILING TO BE DEMOLISHED
- EXISTING GYPSUM SOFFIT TO REMAIN
- EXISTING CEILING TILES TO REMAIN




**01 DEMOLITION CEILING PLAN - LEVEL 02**
1/8" = 1'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**DEMOLITION CEILING PLAN - LEVEL 02**

SHEET NUMBER

# A-1.1.2

5/10/2022 5:58:52 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK 2_R21.rvt




**01 SITE PLAN**
1" = 40'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**SITE PLAN**


SHEET NUMBER

**A-2.0.1**


5/10/2022 5:58:58 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## REFERENCE PLAN LEGEND

NOT IN SCOPE




**01** **FLOOR PLAN - LEVEL 01**
1" = 20'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**REFERENCE PLAN - LEVEL 01**


SHEET NUMBER

# A-2.0.2


5/10/2022 5:59:02 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK-2_R21.rvt

## REFERENCE PLAN LEGEND

NOT IN SCOPE




**01** **FLOOR PLAN - LEVEL 02**
1" = 20'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**REFERENCE PLAN - LEVEL 02**

SHEET NUMBER

**A-2.0.3**


5/10/2022 5:59:12 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK-2_R21.rvt

## PLAN NOTES

1. ALL ACCESSIBLE ENTRANCES SHALL HAVE NO MORE THAN A 2 PERCENT SLOPE FOR A DISTANCE OF 60" PERPENDICULAR TO THE DOOR.
2. ALL COMMON USE DOOR THRESHOLDS TO BE ACCESSIBLE. REFER TO TYPICAL DOOR THRESHOLDS.
3. COORDINATE WORK WITH STRUCTURAL, MECHANICAL, ELECTRICAL, FIRE PROTECTION, PLUMBING, AND TELE/COMM DRAWINGS. IF DISCREPANCIES EXIST, OBTAIN CLARIFICATION FROM ARCHITECT PRIOR TO CONSTRUCTION. PANELS, RISERS, AND TELE/COMM ARE LOCATED ON THE PLANS FOR REFERENCE ONLY.
4. AREA CALCULATIONS, REFER TO BUIDING CODE INFORMATION.
5. FIRE EXTINGUISHERS ARE TO BE LOCATED EVERY FLOOR WITH A MAXIMUM TRAVEL DISTANCE OF 75'-0" AT WALKWAYS.
6. INTERIOR PARTITION TYPES, REFER TO SHEET G-0.0.4
7. ALL DIMENSIONS INDICATED ON PLANS ARE FINISH FACE OF PARTITIONS TO FINISH FACE OF PARTITIONS, UNLESS NOTED OTHERWISE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL SPECIFIC DIMENSION DISCREPANCIES TO THE ATTENTION OF THE ARCHITECT / INTERIOR DESIGNER TO OBTAIN DIMENSION CLARIFICATION AND APPROVAL TO PROCEED WITH WORK.
8. ALL RATED PARTITIONS SHALL BE PERMANENTLY IDENTIFIED IN A MANNER ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION. STENCILING (MIN 2" HIGH) AS EXAMPLE: "FIRE AND SMOKE BARRIER - PROTECT ALL OPENINGS" AND BE PLACED ABOVE THE CEILING OR IN A CONCEALED SPACE.
9. DOOR FRAMES SHALL BE LOCATED 4" FROM FACE OF ADJACENT PARTITION TO INSIDE FACE OF JAMB, UNLESS NOTED OTHERWISE.
10. CEILING AND SOFFIT LOCATIONS AND HEIGHTS, REFER TO REFLECTED CEILING PLANS
11. PROVIDE REINFORCING BEHIND WALL MOUNTED AND CEILING MOUNTED EQUIPMENT.
12. ALL POWER, TELEPHONE AND TV OUTLETS TO HAVE COVER PLATES TO MATCH ELECTRICAL AND ADJACENT FINISH. WHITE ON LIGHT SURFACES AND BLACK ON DARK SURFACES.
13. ALL OUTLETS ABOVE COUNTERTOPS TO BE INSTALLED HORIZONTALLY.
14. SEALANTS AND CAULKING TO MATCH DOMINANT ADJACENT SURFACE IN WHICH THEY OCCUR. PROVIDE SAMPLE. NO VOC SEALANTS TO BE USED PER WELL.
15. FURNITURE SHOWN & COUNTED FOR SPACE PLANNING PURPOSES ONLY. ALL FURNITURE TO BE PROVIDED & INSTALLED BY OWNER. ALL PLANS INDICATE TYPICAL CONDITIONS UNLESS OTHERWISE NOTED.

## FLOOR PLAN LEGEND:

- EXISTING OR BASE BUILDING PARTITIONS - SHADED. TO REMAIN
- NEW PARTITIONS - SEE PARTITION TYPES
- 101 — NEW DOOR. SEE SCHEDULE
- A1 — WALL TYPE TAG. SEE PARTITION TYPES
- CR — CARD READER DOOR DEVICE
- HO — HOLD OPEN DOOR DEVICE




**01 ENLARGED FLOOR PLAN - LEVEL 01**
1/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

# ENLARGED FLOOR PLAN - LEVEL 01

SHEET NUMBER

# A-2.1.0


5/10/2022 5:59:17 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## PLAN NOTES


1. ALL ACCESSIBLE ENTRANCES SHALL HAVE NO MORE THAN A 2 PERCENT SLOPE FOR A DISTANCE OF 60" PERPENDICULAR TO THE DOOR.
2. ALL COMMON USE DOOR THRESHOLDS TO BE ACCESSIBLE. REFER TO TYPICAL DOOR THRESHOLDS.
3. COORDINATE WORK WITH STRUCTURAL, MECHANICAL, ELECTRICAL, FIRE PROTECTION, PLUMBING, AND TELE/COMM DRAWINGS. IF DISCREPANCIES EXIST, OBTAIN CLARIFICATION FROM ARCHITECT PRIOR TO CONSTRUCTION. PANELS, RISERS, AND TELE/COMM ARE LOCATED ON THE PLANS FOR REFERENCE ONLY.
4. AREA CALCULATIONS, REFER TO BUIDING CODE INFORMATION.
5. FIRE EXTINGUISHERS ARE TO BE LOCATED EVERY FLOOR WITH A MAXIMUM TRAVEL DISTANCE OF 75'-0" AT WALKWAYS.
6. INTERIOR PARTITION TYPES, REFER TO SHEET G-0.0.4
7. ALL DIMENSIONS INDICATED ON PLANS ARE FINISH FACE OF PARTITIONS TO FINISH FACE OF PARTITIONS, UNLESS NOTED OTHERWISE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL SPECIFIC DIMENSION DISCREPANCIES TO THE ATTENTION OF THE ARCHITECT / INTERIOR DESIGNER TO OBTAIN DIMENSION CLARIFICATION AND APPROVAL TO PROCEED WITH WORK.
8. ALL RATED PARTITIONS SHALL BE PERMANENTLY IDENTIFIED IN A MANNER ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION. STENCILING (MIN 2" HIGH) AS EXAMPLE: "FIRE AND SMOKE BARRIER - PROTECT ALL OPENINGS" AND BE PLACED ABOVE THE CEILING OR IN A CONCEALED SPACE.
9. DOOR FRAMES SHALL BE LOCATED 4" FROM FACE OF ADJACENT PARTITION TO INSIDE FACE OF JAMB, UNLESS NOTED OTHERWISE.
10. CEILING AND SOFFIT LOCATIONS AND HEIGHTS, REFER TO REFLECTED CEILING PLANS
11. PROVIDE REINFORCING BEHIND WALL MOUNTED AND CEILING MOUNTED EQUIPMENT.
12. ALL POWER, TELEPHONE AND TV OUTLETS TO HAVE COVER PLATES TO MATCH ELECTRICAL AND ADJACENT FINISH. WHITE ON LIGHT SURFACES AND BLACK ON DARK SURFACES.
13. ALL OUTLETS ABOVE COUNTERTOPS TO BE INSTALLED HORIZONTALLY.
14. SEALANTS AND CAULKING TO MATCH DOMINANT ADJACENT SURFACE IN WHICH THEY OCCUR. PROVIDE SAMPLE. NO VOC SEALANTS TO BE USED PER WELL.
15. FURNITURE SHOWN & COUNTED FOR SPACE PLANNING PURPOSES ONLY. ALL FURNITURE TO BE PROVIDED & INSTALLED BY OWNER. ALL PLANS INDICATE TYPICAL CONDITIONS UNLESS OTHERWISE NOTED.

## FLOOR PLAN LEGEND:

- EXISTING OR BASE BUILDING PARTITIONS - SHADED. TO REMAIN
- NEW PARTITIONS - SEE PARTITION TYPES
- 101 — NEW DOOR. SEE SCHEDULE
- A1 — WALL TYPE TAG. SEE PARTITION TYPES
- CR — CARD READER DOOR DEVICE
- HO — HOLD OPEN DOOR DEVICE




**01** ENLARGED FLOOR PLAN - LEVEL 02
1/8" = 1'-0"




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**ENLARGED FLOOR PLAN - LEVEL 02**

SHEET NUMBER


**A-2.1.1**

5/10/2022 5:59:59 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt


## PLAN NOTES

1. ALL ACCESSIBLE ENTRANCES SHALL HAVE NO MORE THAN A 2 PERCENT SLOPE FOR A DISTANCE OF 60" PERPENDICULAR TO THE DOOR.
2. ALL COMMON USE DOOR THRESHOLDS TO BE ACCESSIBLE. REFER TO TYPICAL DOOR THRESHOLDS.
3. COORDINATE WORK WITH STRUCTURAL, MECHANICAL, ELECTRICAL, FIRE PROTECTION, PLUMBING, AND TELE/COMM DRAWINGS. IF DISCREPANCIES EXIST, OBTAIN CLARIFICATION FROM ARCHITECT PRIOR TO CONSTRUCTION. PANELS, RISERS, AND TELE/COMM ARE LOCATED ON THE PLANS FOR REFERENCE ONLY.
4. AREA CALCULATIONS, REFER TO BUIDING CODE INFORMATION.
5. FIRE EXTINGUISHERS ARE TO BE LOCATED EVERY FLOOR WITH A MAXIMUM TRAVEL DISTANCE OF 75'-0" AT WALKWAYS.
6. INTERIOR PARTITION TYPES, REFER TO SHEET G-0.0.4
7. ALL DIMENSIONS INDICATED ON PLANS ARE FINISH FACE OF PARTITIONS TO FINISH FACE OF PARTITIONS, UNLESS NOTED OTHERWISE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL SPECIFIC DIMENSION DISCREPANCIES TO THE ATTENTION OF THE ARCHITECT / INTERIOR DESIGNER TO OBTAIN DIMENSION CLARIFICATION AND APPROVAL TO PROCEED WITH WORK.
8. ALL RATED PARTITIONS SHALL BE PERMANENTLY IDENTIFIED IN A MANNER ACCEPTABLE TO THE AUTHORITY HAVING JURISDICTION. STENCILING (MIN 2" HIGH) AS EXAMPLE: "FIRE AND SMOKE BARRIER - PROTECT ALL OPENINGS" AND BE PLACED ABOVE THE CEILING OR IN A CONCEALED SPACE.
9. DOOR FRAMES SHALL BE LOCATED 4" FROM FACE OF ADJACENT PARTITION TO INSIDE FACE OF JAMB, UNLESS NOTED OTHERWISE.
10. CEILING AND SOFFIT LOCATIONS AND HEIGHTS, REFER TO REFLECTED CEILING PLANS
11. PROVIDE REINFORCING BEHIND WALL MOUNTED AND CEILING MOUNTED EQUIPMENT.
12. ALL POWER, TELEPHONE AND TV OUTLETS TO HAVE COVER PLATES TO MATCH ELECTRICAL AND ADJACENT FINISH. WHITE ON LIGHT SURFACES AND BLACK ON DARK SURFACES.
13. ALL OUTLETS ABOVE COUNTERTOPS TO BE INSTALLED HORIZONTALLY.
14. SEALANTS AND CAULKING TO MATCH DOMINANT ADJACENT SURFACE IN WHICH THEY OCCUR. PROVIDE SAMPLE. NO VOC SEALANTS TO BE USED PER WELL.
15. FURNITURE SHOWN & COUNTED FOR SPACE PLANNING PURPOSES ONLY. ALL FURNITURE TO BE PROVIDED & INSTALLED BY OWNER. ALL PLANS INDICATE TYPICAL CONDITIONS UNLESS OTHERWISE NOTED.


1





**04** ENLARGED FLOOR PLAN - CONCESSIONS
1/4" = 1'-0"




**03** ENLARGED FLOOR PLAN - LOUNGE SEATING
1/4" = 1'-0"




**02** ENLARGED FLOOR PLAN - LOUNGE SEATING
1/4" = 1'-0"




**01** ENLARGED FLOOR PLAN - RESTROOMS
1/4" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**ENLARGED FLOOR PLANS**

SHEET NUMBER

**A-2.1.2**

5/10/2022 5:59:56 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK 2_R21.rvt




**02** SECTION
3/4" = 1'-0"

**01** SECTION - EXIT LANE
3/4" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

## BUILDING SECTIONS


SHEET NUMBER

**A-4.0.1**


5/10/2022 5:59:59 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK 2_R21.rvt





10 **INTERIOR ELEVATION - RESTROOM ENTRANCE**
1/4" = 1'-0"





09 **INTERIOR ELEVATION - EXIT LANE**
1/4" = 1'-0"





08 **MEN 08**
1/4" = 1'-0"





07 **MEN 07**
1/4" = 1'-0"





06 **MEN 06**
1/4" = 1'-0"





05 **MEN 05**
1/4" = 1'-0"





04 **WOMEN 04**
1/4" = 1'-0"




03 **WOMEN 03**
1/4" = 1'-0"




02 **WOMEN 02**
1/4" = 1'-0"




01 **WOMEN 01**
1/4" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,
PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

## INTERIOR ELEVATIONS


SHEET NUMBER

**A-5.0.1**


5/10/2022 6:05:26 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt





**07** **INTERIOR ELEVATION - CONCOURSE**
1/4" = 1'-0"





**06** **INTERIOR ELEVATION - CONCOURSE**
1/4" = 1'-0"




**05** **INTERIOR ELEVATION - LOUNGE**
1/4" = 1'-0"





**04** **INTERIOR ELEVATION - LOUNGE**
1/4" = 1'-0"




**03** **INTERIOR ELEVATION - LOUNGE**
1/4" = 1'-0"




**02** **INTERIOR ELEVATION - CONCOURSE**
1/4" = 1'-0"




**01** **INTERIOR ELEVATION - CONCOURSE**
1/4" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

## INTERIOR ELEVATIONS

SHEET NUMBER

**A-5.0.2**


5/10/2022 6:31:04 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## NOTE:

REFER ELECTRICAL FOR LIGHTING.

## REFLECTED CEILING PLAN LEGEND

- GWB
- 2x2 ACOUSTICAL CEILING TILE
- LINEAR METAL CEILING TO MATCH EXISTING
- 1x4 EMERGENCY FIXTURE (REFER TO ELEC.)
- CEILING TYPE (A / 1'-0")
- CEILING HEIGHT AFF
- RECESSED CAN LIGHTING
- SURFACE MOUNTED LIGHTING
- SLOT RECESSED LIGHTING




**01 REFLECTED CEILING PLAN - LEVEL 01**
1/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**REFLECTED CEILING PLAN - LEVEL 01**

SHEET NUMBER

**A-6.0.1**


5/11/2022 9:29:59 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## NOTE:

REFER ELECTRICAL FOR LIGHTING.

## REFLECTED CEILING PLAN LEGEND

- GWB
- 2 x 2 ACOUSTICAL CEILING TILE
- LINEAR METAL CEILING TO MATCH EXISTING
- 1x4 EMERGENCY FIXTURE (REFER TO ELEC.)
- CEILING TYPE (A / 1'-0")
- CEILING HEIGHT AFF
- RECESSED CAN LIGHTING
- SURFACE MOUNTED LIGHTING
- SLOT RECESSED LIGHTING




**01 REFLECTED CEILING PLAN - LEVEL 02**
1/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**REFLECTED CEILING PLAN - LEVEL 02**

SHEET NUMBER

**A-6.0.2**

5/10/2022 6:00:22 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210211 - Panama City Airport NWFB_TASK-2_R21.rvt




**01** **FINISH FLOOR PLAN - LEVEL 02**
1/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**FINISH FLOOR PLAN**


SHEET NUMBER

**A-6.0.3**

5/10/2022 6:09:26 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

| SIGNAGE SCHEDULE | | | | |
|---|---|---|---|---|
| SIGN | HEIGHT | MOUNTING | DETAIL | COMMENTS |
| S1 | 9' - 0" | SUSPENDED | 01/A-7.0.5 | SUSPEND WITH CABLES AND HARDWARE |
| S2 | 9' - 0" | SUSPENDED | 04/A-7.0.5 | SUSPEND WITH CABLES AND HARDWARE |
| S3 | 9' - 0" | FLAG | | EXISTING SIGN |
| S4 | 4' - 0" | PLAQUE | 10/A-7.0.5 | |
| S5 | 4' - 0" | PLAQUE | 10/A-7.0.5 | |
| S6 | 4' - 0" | PLAQUE | 10/A-7.0.5 | |
| S7 | 4' - 0" | PLAQUE | 10/A-7.0.5 | |
| S8 | 4' - 0" | PLAQUE | 08/A-7.0.5 | |
| S9 | 4' - 0" | PLAQUE | 08/A-7.0.5 | |
| S10 | 8' - 0" | FLAG | 05/A-7.0.5 | |
| S11 | 8' - 0" | FLAG | 02/A-7.0.5 | |
| S12 | 6' - 6" | WALL | 06/A-7.0.5 | |
| S13 | 6' - 6" | WALL | 03/A-7.0.5 | |
| S14 | 4' - 0" | PLAQUE | 07/A-7.0.5 | |
| S15 | 4' - 0" | PLAQUE | 09/A-7.0.5 | |

NOTE: PROVIDE BLOCKING AS REQUIRED




**01 SIGNAGE PLAN - LEVEL 02**
1/8" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

## SIGNAGE PLAN

SHEET NUMBER


# A-6.0.4

5/10/2022 6:00:30 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt





**HEAD -1**

## 04 DOOR HEAD DETAIL - INTERIOR
3" = 1'-0"





**JAMB -1**

## 03 DOOR JAMB DETAIL - INTERIOR
3" = 1'-0"





**FRAME - A**

## 02 DOOR FRAME
3" = 1'-0"





## 05 TILE TRIM @ CORNER
12" = 1'-0"




## 01 TRANSITION - TERRAZZO TO CONCRETE
12" = 1'-0"

## DOOR TYPES




FINISH SCHEDULE

| ROOM | NO. | FLOOR MATERIAL | MANUFACTURER | STYLE | COLOR | SIZE | BASE | WALLS | CEILING | CEILING HEIGHT | NOTES | Area |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| STOR. | 1102 | VCT | | | | | | GWB | GWB | 8'-0" | | 78 SF |
| STOR. | 1103 | VCT | | | | | | GWB | GWB | 8'-0" | | 53 SF |
| EXIT LANE | 1132 | | | | | | | | | | | 341 SF |
| COMM | 2101B | EXISTING | | | | | | GWB | EXPOSED STRUCTURE | | | 111 SF |
| BOARDING VESTIBULE | 2103 | TERR | SHERWIN WILLIAMS | | | | | GWB | GWB | 9'-0" | | 213 SF |
| STOR. | 2104 | VCT | | | | | | GWB | GWB | 8'-0" | | 47 SF |
| TICKETING | 2105 | TERR | SHERWIN WILLIAMS | | | | | GWB | LMC | VARIES | | 508 SF |
| LOUNGE | 2106 | TERR | SHERWIN WILLIAMS | | | | | GWB | GWB | VARIES | | 1386 SF |
| CONCOURSE WAITING | 2107 | TERR | SHERWIN WILLIAMS | | | | | GWB | LMC | VARIES | | 7579 SF |
| FUTURE CONCESSIONS | 2108 | SC | | | | | | GWB | GWB | 9'-0" | | 1278 SF |
| JAN. CLOSET | 2113 | SC | | | | | | GWB | GWB | 8'-0" | | 43 SF |
| FAMILY | 2114 | TERR | SHERWIN WILLIAMS | | | | TERR | CT | GWB | 8'-0" | | 62 SF |
| WOMEN | 2115 | TERR | SHERWIN WILLIAMS | | | | TERR | CT | GWB | 9'-0" | | 496 SF |
| MEN | 2116 | TERR | SHERWIN WILLIAMS | | | | TERR | CT | GWB | 9'-0" | | 478 SF |
| CONCOURSE | 2404 | TERR | SHERWIN WILLIAMS | | | | | GWB | LMC | VARIES | | 292 SF |
| Grand total: 15 | | | | | | | | | | | | 12964 SF |

LEGEND:

| | |
|---|---|
| CT: | CERAMIC TILE |
| LMC: | LINEAR METAL CEILING |
| TERR: | TERRAZZO |
| VCT: | VINYL COMPOSITE TILE |
| SC: | SEALED CONCRETE |
| SS: | STAINLESS STEEL |
| SSR: | SOLID SURFACE |

DOOR SCHEDULE

| DOOR NO. | DOOR TYPE | DOOR MATERIAL | WIDTH | HEIGHT | THICKNESS | FRAME TYPE | FRAME MATERIAL | HEAD DETAIL | JAMB DETAIL | SILL DETAIL | FIRE RATING (minute) | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 101 | B | HM | 6' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | - | |
| 102 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | 90 | |
| 200 | A | HM | 4' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | | | | - | SECURITY DOOR. ACCESS CONTROL |
| 201 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | 1 | |
| 202 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | 90 | SECURITY DOOR. ACCESS CONTROL |
| 203 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | 01/A-7.0.1 | - | |
| 204 | B | HM | 6' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | - | SECURITY DOOR. ACCESS CONTROL |
| 205 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | 01/A-7.0.1 | 45 | |
| 206 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | 01/A-7.0.1 | 45 | |
| 207 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | 01/A-7.0.1 | - | |
| 208 | A | HM | 3' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | - | |
| 209 | B | HM | 6' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | 90 | |
| 1108A | | | 6' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1108B | | | 6' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1108C | | | 6' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1109A | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1110A | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1111A | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1121A | | | 6' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1121B | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1121C | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1123 | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1130A | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1130B | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1130C | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1132A | A | HM | 11' - 2 1/2" | 7' - 0" | 0' - 1 3/4" | - | | | | | | EXISTING DOOR, FRAME AND HARDWARE TO BE REMOVED AND REINSTALLED. PROVIDE ASSA ABLOY DOOR ASSEMBLY SL500 AS BASIS OF DESIGN SHOULD NEW DOORS BE REQUIRED |
| 1132B | A | HM | 6' - 0" | 7' - 0" | 0' - 1 3/4" | A | HM | 02/A-7.0.1 | 03/A-7.0.1 | | 90 | EXISTING DOOR, FRAME AND HARDWARE TO BE REINSTALLED |
| 1132C | A | HM | 11' - 2 1/2" | 7' - 0" | 0' - 1 3/4" | - | | | | | | EXISTING DOOR, FRAME AND HARDWARE TO BE REMOVED AND REINSTALLED. PROVIDE ASSA ABLOY DOOR ASSEMBLY SL500 AS BASIS OF DESIGN SHOULD NEW DOORS BE REQUIRED |
| 1135 | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1136 | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1139 | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1152A | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1152B | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 1154 | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 2101 | | | 3' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 2102 | | | 6' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | 01/A-7.0.1 | | EXISTING DOOR |
| 2111 | | | 6' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 2114 | | | 3' - 0" | 7' - 0" | | | | | | | | EXISTING DOOR |
| 2402A | | | 4' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 2402B | | | 3' - 6" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |
| 2402D | | | 4' - 0" | 7' - 0" | 0' - 1 3/4" | | | | | | | EXISTING DOOR |

ACCESSORIES FIXTURE SCHEDULE

| Type Mark | DESCRIPTION | MANUFACTURER | MODEL | MATERIAL | COMMENTS |
|---|---|---|---|---|---|
| AED | AUTOMATED EXTERNAL DEFIBRILLATOR | ACTIVAR CONSTRUCTION PRODUCTS GROUP | 1710 | | |
| BCT | SURFACE MOUNTED BABY CHANGING STATION | BRADLEY | 962-11 | STAINLESS STEEL | |
| FEC | FIRE EXTINGUISHER CABINET | ACTIVAR CONSTRUCTION PRODUCTS GROUP | 8135 | STAINLESS STEEL | |
| GB36 | 36" GRAB BAR | BRADLEY | 832 | STAINLESS STEEL | CONFIGURTION 001-36" |
| GB42 | 42" GRAB BAR | BRADLEY | 832 | STAINLESS STEEL | CONFIGURTION 001-42" |
| HD | WALL MOUNTED HAND DRYER | DYSON | DYSON AIRBLADE V AB12 | STAINLESS STEEL | |
| MR | FRAMELESS MIRROR, CLIP FASTENERS, 24" x 36" | BRADLEY | 747-024360 | STAINLESS STEEL | |
| SD | WALL MOUNTED FOAM SOAP DISPENSER | BOBRICK | B-2013 | | |
| TD | TOWEL DISPENSER | BRADLEY | 250-150000 | STAINLESS STEEL | |
| TP1 | 1-STALL SEAT COVER/PAPER DISPENSER | BRADLEY | 5922 | STAINLESS STEEL | |
| TP2 | 2-STALL SEAT COVER/PAPER DISPENSER | BRADLEY | 5921 | | |
| TP3 | 1-STALL SEAT COVER/PAPER DISPENSER, NAPKIN DISPOSAL | BRADLEY | 5912 | STAINLESS STEEL | |
| TP4 | 2-STALL SEAT COVER/PAPER DISPENSER, NAPKIN DISPOSAL | BRADLEY | 5911 | STAINLESS STEEL | |

FINISH LEGEND

| TAG | APPLICATION | MATERIAL | CLASS | MFGR/STYLE | COLOR/FINISH/SIZE | NOTES |
|---|---|---|---|---|---|---|
| PT-1 | WALLS | GWB/PAINT | NC* | SHERWIN WILLIAMS | SW 6204: SEA SALT | TYP UNLESS NOTED. SEE WALL TYPE SHEET FOR FULL ASSEMBLY. |
| LAM-1 | CASEWORK/ CABINETS | LAMINATE | C (3) | PAPERSTONE | PEWTER | |
| MTL | COLUMN COVER | FORMS AND SURFACES | | STAINLESS STEEL | SEASTONE FLAT (NO PATTERN) | |
| SSR-1 | COUNTERTOP | SOLID SURFACE | | WILSONART | SOOTHING GREY 9116GS | |
| TZ-1 | FLOOR | TERRAZZO | | SHERWIN WILLIAMS | RESUFLOR TERRAZZO TG, SW-1056TZ | |
| TZ-2 | FLOOR | TERRAZZO | | SHERWIN WILLIAMS | RESUFLOR TERRAZZO TG, SW-1047TZ | |
| WT-1 | WALL TILE | CERAMIC TILE | NC | DALTILE COLOR WHEEL | 4" x 12" MATTE ARCTIC WHITE 0790 (1) | INSTALL: VERTICAL |
| WT-2 | WALL TILE | CERAMIC TILE | NC | DALTILE MULTITUDE | 12" x 24" NOSTALGIC BLUE MU19 (WAVE) | INSTALL: HORIZONTAL |

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**DETAILS & SCHEDULES**


SHEET NUMBER

**A-7.0.1**


5/11/2022 11:00:59 AM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/21021 - Panama City Airport NWFB_TASK 2_R21.rvt





## 17 CURTAIN WALL CORNER DETAIL
6" = 1'-0"





## 16 STOREFRONT VERTICAL DETAIL
6" = 1'-0"





## 15 CURTAIN WALL JAMB DETAIL
6" = 1'-0"





## 11 SOFFIT DETAIL
1 1/2" = 1'-0"





## 14 CURTAIN WALL HORIZONTAL DETAIL
6" = 1'-0"





## 13 CURTAIN WALL HEAD DETAIL
6" = 1'-0"





## 12 CURTAIN WALL SILL DETAIL
6" = 1'-0"





## 10 STOREFRONT CORNER DETAIL
6" = 1'-0"





## 09 STOREFRONT HORIZONTAL DETAIL
6" = 1'-0"





## 08 DETAIL
1 1/2" = 1'-0"





## 07 DETAIL
1 1/2" = 1'-0"





## 06 STOREFRONT VERTICAL DETAIL
6" = 1'-0"





## 05 STOREFRONT HEAD DETAIL
6" = 1'-0"




## 02 STOREFRONT - WEST
1/4" = 1'-0"




## 01 STOREFRONT - SOUTH
1/4" = 1'-0"




## 04 STOREFRONT SILL DETAIL
6" = 1'-0"




## 03 STOREFRONT JAMB DETAIL
6" = 1'-0"

### GLAZING NOTES

1. INTERIOR GLASS: ALL INTERIOR GLAZING TO BE 1/4" THICK TEMPERED GLASS, U.N.O
2. STOREFRONT/ CURTAIN WALL FRAME AND MULLIONS: ALL FRAMES AND MULLIONS TO BE ANODIZED, U.N.O.

**GLAZING TYPES:**

G1 SINGLE PANE GLASS UNIT, ALL GLAZING U.N.O.
LITE: CLEAR
COMMENTS: -

G2 SINGLE PANE GLASS UNIT WITH FILM
LITE: CLEAR
COMMENTS: -

TP TEMPERED GLAZING

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE


**STOREFRONT ELEVATIONS AND DETAILS**

SHEET NUMBER


A-7.0.2





**12 COLUMN COVER PANEL TOP**
6" = 1'-0"





**11 COLUMN COVER PANEL REVEAL**
6" = 1'-0"





**10 COLUMN COVER PANEL BASE**
6" = 1'-0"





**09 COLUMN COVER**
1 1/2" = 1'-0"





**08 COLUMN COVER**
1 1/2" = 1'-0"





**07 COLUMN COVER - SQUARE**
1 1/2" = 1'-0"





**06 COLUMN COVER - SQUARE**
1 1/2" = 1'-0"





**05 STEEL COLUMN DETAIL**
3/4" = 1'-0"





**04 CONCRETE COLUMN DETAIL - TYP**
1 1/2" = 1'-0"





**03 COLUMN DETAIL**
3/4" = 1'-0"





**02 COLUMN DETAIL - TYP**
1 1/2" = 1'-0"




**01 GUARDRAIL DETAIL**
1 1/2" = 1'-0"




**14 BULKHEAD DETAIL**
1 1/2" = 1'-0"




**13 BULKHEAD DETAIL**
1 1/2" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**DETAILS**


SHEET NUMBER

**A-7.0.3** 1


5/10/2022 6:55:23 PM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/21021 - Panama City Airport NWFB_TASK 2_R21.rvt





## 12 INTERIOR WINDOW SILL DETAIL
3" = 1'-0"





## 11 SECTION - LOUNGE SEATING
1/2" = 1'-0"





## 10 TICKET COUNTER SECTION
1" = 1'-0"





## 09 TICKET COUNTER ELEVATION
1" = 1'-0"





## 08 TICKET COUNTER ELEVATION
1" = 1'-0"





## 07 TICKET COUNTER SECTION
1" = 1'-0"





## 06 TICKET COUNTER ELEVATION
1" = 1'-0"





## 05 TICKET COUNTER PLAN
1" = 1'-0"





## 04 TICKET COUNTER PLAN
1" = 1'-0"




## 03 COUNTERTOP
1 1/2" = 1'-0"




## 02 VANITY COUNTERTOP WITH SLOPED FRONT
1 1/2" = 1'-0"




## 01 VANITY COUNTERTOP
1 1/2" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**DETAILS**


SHEET NUMBER

A-7.0.4


5/11/2022 11:09:09 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt





**12 TYPICAL FLAG MOUNTED TOP VIEW**
1 1/2" = 1'-0"





**11 TYPICAL WALL MOUNTED ROOM IDENTITY SIGNS**
6" = 1'-0"





**10 TYPICAL GRAPHIC LAYOUTS**
**TWO LINE ADA ROOM PLAQUE**
6" = 1'-0"





**09 TYPICAL GRAPHIC LAYOUTS**
**ONE LINE ADA ROOM PLAQUE**
6" = 1'-0"





**08 TYPICAL GRAPHIC LAYOUTS**
**ONE LINE ADA ROOM PLAQUE**
6" = 1'-0"





**07 TYPICAL SUSPENDED TOP VIEW**
1 1/2" = 1'-0"





**06 WALL MOUNTED - GATE 9**
1 1/2" = 1'-0"





**05 FLAG MOUNTED - GATE 9**
1 1/2" = 1'-0"





**04 SIGNAGE - DIRECTIONAL**
1 1/2" = 1'-0"




**03 WALL MOUNTED - GATE 8**
1 1/2" = 1'-0"




**02 FLAG MOUNTED - GATE 8**
1 1/2" = 1'-0"




**01 SIGNAGE - DIRECTIONAL**
1 1/2" = 1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS 05/10/2022 | |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,
PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**SIGNAGE DETAILS**

SHEET NUMBER

**A-7.0.5**

5/11/2022 11:55:44 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/210211 - Panama City Airport NWFB_TASK 2_R21.rvt

## STRUCTURAL GENERAL NOTES
## MISCELLANEOUS

1. THESE ABBREVIATED DRAWING NOTES ARE WRITTEN TO MATCH THE BOOK SPECIFICATIONS. IF THERE ARE ANY ITEMS THAT DO NOT CORRESPOND EXACTLY AS WRITTEN, THE MORE STRINGENT WILL TAKE PRECEDENCE.

2. THE STRUCTURAL SYSTEM IS UNSTABLE UNTIL ALL CONNECTIONS HAVE BEEN MADE AND ALL CONCRETE HAS REACHED ITS MINIMUM DESIGN STRENGTH, AS SHOWN IN THE STRUCTURAL DOCUMENTS.

3. CONTRACTOR IS RESPONSIBLE FOR MEANS AND METHODS OF CONSTRUCTION TO ENSURE THE SAFETY OF THE BUILDING UNTIL STRUCTURAL SYSTEM IS COMPLETED. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF WHATEVER TEMPORARY BRACING, SHORING, GUYS OR TIE-DOWNS THAT MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER COMPLETION OF THE PROJECT.

4. CONTRACTOR TO SUPPORT, BRACE AND SECURE EXISTING STRUCTURE AS REQUIRED. CONTRACTOR IS SOLELY RESPONSIBLE FOR THE SAFETY OF THE BUILDING DURING CONSTRUCTION.

5. APPLICABLE BUILDING CODE: 7TH EDITION (2020) FLORIDA BUILDING CODE.

6. GRAVITY DESIGN LOADS:

| AREA | SUPERIMPOSED LIVE LOAD | TOTAL DEAD LOAD |
|---|---|---|
| TERMINAL 2ND FLOOR | 100 PSF | 65 PSF |
| ⚠ INFILL STAIR FLOOR | 125 PSF | 55 PSF |

7. WIND DESIGN CRITERIA:
   ULTIMATE WIND SPEED: $V_{ULT}$ = 143 MPH (3 SECOND GUST)
   EQUIVALENT NOMINAL BASIC WIND SPEED $V_{ASD}$ = 111 MPH (3 SECOND GUST)
   RISK CATEGORY = III
   EXPOSURE CATEGORY = D
   ENCLOSED BUILDING INTERNAL PRESSURE COEFFICIENT, $GC_{Pi}$= +/-0.18
   WIND BORNE DEBRIS REGION

8. ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REFERENCED BUILDING CODE.

9. COORDINATE ALL DIMENSIONS AND ELEVATIONS WITH THE ARCHITECTURAL DRAWINGS. DO NOT SCALE DRAWINGS.

10. CONTACT ENGINEER WITH ANY QUESTIONS OR DISCREPANCIES FOUND ON DRAWINGS.

11. BUILDING EXPANSION JOINTS (EJ), WHERE SHOWN, WILL EXPAND AND CONTRACT OVER THE LIFE OF THE BUILDING. JOINT SEALANTS AND COVERS MUST ACCOMMODATE THIS MOVEMENT.

12. SECTIONS AND DETAILS ARE REFERENCED IN TYPICAL LOCATIONS BUT ALSO APPLY TO ALL OTHER SIMILAR CONDITIONS.

13. CONTRACTOR TO VERIFY ALL EXISTING DIMENSIONS, ELEVATIONS, AND CONDITIONS PRIOR TO BEGINNING CONSTRUCTION.

14. SUBMIT SHOP DRAWINGS AS REQUIRED HEREIN. ALLOW FOR TWO WEEKS REVIEW TIME AFTER RECEIPT OF SUBMITTALS BY THIS FIRM. ALL SUBMITTALS SHALL BE CHECKED AND SIGNED BY THE GENERAL CONTRACTOR AND SIGNED/SEALED BY THE DELEGATED ENGINEER, WHERE SPECIFIED HEREIN.

15. CONTRACTOR SHALL NOT BE RELIEVED FROM RESPONSIBILITY FOR ERRORS OR OMISSIONS IN SHOP DRAWINGS OR MIX DESIGNS BY THE ENGINEER'S REVIEW THEREOF.

16. ANY CHANGES TO THE STRUCTURE SHALL HAVE BEEN REVIEWED AND APPROVED IN WRITING BY THE ENGINEER PRIOR TO COMMENCING WORK ON ITEMS AFFECTED.

17. CONTRACTOR SHALL NOTIFY THIS OFFICE WHEN THE STRUCTURAL SYSTEM IS SUBSTANTIALLY COMPLETED, AND BEFORE SHEATHING, CEILINGS, OR ROOFING IS INSTALLED.

## HAND RAILS

1. AN ENGINEER REGISTERED IN THE STATE OF FLORIDA SHALL DESIGN RAILING SYSTEM AND CONNECTION OF IT TO THIS STRUCTURE.

2. SUBMIT SHOP DRAWINGS BEARING THE EMBOSSED SEAL AND THE SIGNATURE OF THE ENGINEER FOR REVIEW PRIOR TO FABRICATION.

3. THE CONFIGURATION OF THE RAILING SYSTEM SHALL BE AS SHOWN ON THE ARCHITECTURAL DRAWINGS.

4. RAILING SYSTEM AND CONNECTIONS SHALL BE DESIGNED FOR APPLICABLE LOADS AS INDICATED ON THE PLANS AND IN THE BUILDING CODE. THE LOADS SHALL BE CLEARLY INDICATED ON SHOP DRAWINGS.

5. SHOP DRAWINGS SHALL SHOW AND SPECIFY CONNECTIONS UTILIZED WITHIN THE RAILING SYSTEM AS WELL AS CONNECTIONS TO AND LOADS IMPOSED UPON THE STRUCTURAL SYSTEM SHOWN ON THESE PLANS.

## DELEGATED ENGINEER

1. WHERE NOTED HEREIN, A LICENSED PROFESSIONAL (DELEGATED) ENGINEER SHALL BE RETAINED TO DESIGN THE PRODUCT OR ASSEMBLY.

2. THE DELEGATED ENGINEER SHALL BE EXPERIENCED IN THE DESIGN OF THE REFERENCED PRODUCT OR ASSEMBLY.

3. THE DELEGATED ENGINEER MUST BE PROVIDED WITH A COPY OF THESE DRAWINGS AND SPECIFICATIONS.

4. IT IS THE DELEGATED ENGINEER'S RESPONSIBILITY TO REVIEW THE ENGINEER OF RECORD'S WRITTEN ENGINEERING REQUIREMENTS AND AUTHORIZATION FOR THE DELEGATED ENGINEERING DOCUMENT TO DETERMINE THE APPROPRIATE SCOPE OF ENGINEERING.

5. THE DELEGATED ENGINEERING DOCUMENT SHALL COMPLY WITH THE WRITTEN ENGINEERING REQUIREMENTS RECEIVED FROM THE ENGINEER OF RECORD. THEY SHALL INCLUDE THE PROJECT IDENTIFICATION AND THE CRITERIA USED AS A BASIS FOR ITS PREPARATION. IF A DELEGATED ENGINEER DETERMINES THERE ARE DETAILS, FEATURES OR UNANTICIPATED PROJECT LIMITS WHICH CONFLICT WITH THE WRITTEN ENGINEERING REQUIREMENTS PROVIDED BY THE ENGINEER OF RECORD, THE DELEGATED ENGINEER SHALL TIMELY CONTACT THE ENGINEER OF RECORD FOR RESOLUTION OF CONFLICTS.

6. THE DELEGATED ENGINEER SHALL FORWARD THE DELEGATED ENGINEERING DOCUMENT TO THE ENGINEER OF RECORD FOR REVIEW. ALL FINAL DELEGATED ENGINEERING DOCUMENTS REQUIRE THE IMPRESSED SEAL AND SIGNATURE OF THE DELEGATED ENGINEER AND INCLUDE:
   A) DRAWINGS INTRODUCING ENGINEERING INPUT SUCH AS DEFINING THE CONFIGURATION OR STRUCTURAL CAPACITY OF STRUCTURAL COMPONENTS AND/OR THEIR ASSEMBLY INTO STRUCTURAL SYSTEMS.
   B) CALCULATIONS.

## EXISTING BUILDINGS

INFORMATION ON THE EXISTING BUILDING, SHOWN ON THESE PLANS, IS OBTAINED FROM EXISTING BUILDING PLANS BY HNTB ARCHITECTURE & PBS & J, DATED MAY 22, 2008 & DECEMBER 5, 2008 "ISSUED FOR CONSTRUCTION. EXISTING INFORMATION DOES NOT NECESSARILY REFLECT AS-BUILT CONDITIONS. THE CONTRACTOR SHALL VERIFY ALL INFORMATION SHOWN ON THESE PLANS AND NOTIFY THE ENGINEER OF ANY VARIATION.

## SITE WORK

1. A SUBSURFACE INVESTIGATION HAS BEEN COMPLETED AT THE PROJECT SITE BY NOVA. SOIL BORING LOGS AND SITE PREPARATION PROCEDURES ARE INCLUDED IN THE PROJECT SOILS REPORT 10111-2021211, DATED OCTOBER 7, 2021, WHICH IS AN INTEGRAL PART OF THESE CONTRACT DOCUMENTS.

2. SITE WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE PROJECT SOILS REPORT.

3. CONTRACTOR SHALL REVIEW THE SOILS REPORT AND VERIFY THAT TEST BORINGS HAVE BEEN DONE UNDER ALL BUILDING(S) PRIOR TO BEGINNING EARTHWORK.

4. INFORMATION FROM GEOTECHNICAL REPORT:
   A) DESIGN SOIL BEARING PRESSURE = 2,000PSF.
   B) ESTIMATED MAXIMUM SETTLEMENT = 1 INCH.
   C) ESTIMATED DIFFERENTIAL SETTLEMENT = ½ INCHES.

5. A QUALIFIED TESTING LABORATORY SHALL BE RETAINED TO PERFORM THE FOLLOWING MINIMUM TESTS. REFER TO SOILS REPORT FOR ANY ADDITIONAL TESTING.
   A) ONE DENSITY TEST FOR EACH 2,000 SQUARE FEET OF COMPACTED SUBGRADE AND COMPACTED FILL.
   B) ONE DENSITY TEST AT EACH COLUMN FOOTING.
   C) ONE DENSITY TEST PER 50 FEET OF WALL FOOTING.

6. ONE COPY OF ALL TEST REPORTS SHALL BE SENT DIRECTLY TO OWNER, ARCHITECT, STRUCTURAL ENGINEER, AND GENERAL CONTRACTOR.

7. FOUNDATION WALLS THAT RETAIN EARTH SHALL BE BRACED AGAINST BACKFILLING PRESSURES UNTIL FLOOR SLABS AT TOP AND BOTTOM ARE IN PLACE.

8. THE SIDES OF FOOTINGS MAY BE EARTH_FORMED IF THE EXCAVATION CAN BE KEPT VERTICAL, CLEAN, AND STABLE, OTHERWISE, PLYWOOD FORMS MUST BE USED.

9. EXERCISE CARE WHEN COMPACTING NEAR ADJACENT STRUCTURES. FOLLOW THE RECOMMENDATIONS IN THE SOILS REPORT AND DOCUMENT EXISTING CONDITIONS WITH PHOTOGRAPHS PRIOR TO STARTING WORK.

10. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL LOCATE ALL EXISTING UNDERGROUND UTILITY LINES, TANKS, ETC. WITHIN THE CONSTRUCTION AREA AND RELOCATE THEM AS DIRECTED BY THE CIVIL ENGINEER.

## CAST IN PLACE CONCRETE

1. ALL CAST-IN-PLACE CONCRETE WORK INCLUDES REINFORCING STEEL AND RELATED WORK SHOWN INCLUDING FORMWORK, SETTING ANCHOR BOLTS, PLATES, FRAMES, DOWELS FOR MASONRY OR OTHER ITEMS EMBEDDED IN CONCRETE.

2. APPLICABLE STANDARDS

| ACI NUMBER | TITLE |
|---|---|
| 117 | STANDARD SPECIFICATIONS FOR TOLERANCES FOR CONCRETE CONSTRUCTION |
| 226 | GROUND GRANULATED BLAST-FURNACE SLAG |
| 301 | STANDARD SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS |
| 302 | GUIDE FOR CONCRETE FLOOR AND SLAB CONSTRUCTION |
| 304 | GUIDE FOR MEASURING MIXING, TRANSPORTING AND PLACING CONCRETE |
| 304.2R | PLACING CONCRETE BY PUMPING METHODS. |
| 305R | HOT WEATHER CONCRETING |
| 306R | COLD WEATHER CONCRETING |
| 308 | STANDARD PRACTICE FOR CURING CONCRETE |
| 309R | GUIDE FOR CONSOLIDATION OF CONCRETE |
| 315 | MANUAL OF STANDARD PRACTICE FOR DETAILING CONCRETE STRUCTURES |
| 318 | BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE |
| 347 | RECOMMENDED PRACTICE FOR CONCRETE FORMWORK |

| CRSI NUMBER | TITLE |
|---|---|
| 63 | RECOMMENDED PRACTICE FOR PLACING REINFORCING BARS |

3. CONCRETE MATERIALS
   A) PORTLAND CEMENT – ASTM C 150, TYPE I
   B) AGGREGATES – NORMAL WEIGHT CONCRETE, COARSE AND FINE, ASTM C33. STRUCTURAL LIGHT WEIGHT ASTM C330.
   C) AIR-ENTRAINING – ASTM C260
   D) WATER REDUCING – ASTM C494, TYPE A
   E) WATER – FRESH, CLEAN AND POTABLE
   F) NO ACCELERATORS, RETARDERS OR ADMIXTURES CONTAINING CHLORIDES WILL BE PERMITTED
   G) FLY-ASH – ASTM C618, CLASS F, 20% MAXIMUM OF CEMENTITIOUS MATERIAL BY WEIGHT. DO NOT USE FOR EXPOSED SLABS OR ARCHITECTURAL CONCRETE.
   H) SUPER PLASTICIZER – ASTM C494, TYPE F OR G, WHERE AUTHORIZED BY THE ENGINEER.
   I) GROUND GRANULATED BLAST-FURNACE SLAG CEMENT – ASTM C989, 50% MAXIMUM BY WEIGHT.
   J) MAXIMUM AGGREGATE SIZE – FOOTINGS = #57, OTHERS #67

4. REINFORCING MATERIALS
   A) DEFORMED BARS – ASTM A615, GRADE 60
   B) SMOOTH DOWELS – ASTM A615, PLAIN BARS, MINIMUM YIELD STRENGTH OF 60,000 PSI.
   C) CORROSION RESISTANT UNCOATED STEEL (MMFX-2) – ASTM A615, GRADE 75 AND ASTM A1035 LOW-CARBON (8% MINIMUM) CHROMIUM BY MMFX OR EQUAL.
   D) WELDED WIRE FABRIC – ASTM A1064, PLAIN WIRE FABRIC IN FLAT SHEETS ONLY.
   E) ACCESSORIES TO CONFORM TO ACI 315.
   F) WHERE CONCRETE SURFACES ARE EXPOSED, MAKE THOSE PORTIONS OF ALL ACCESSORIES IN CONTACT WITH THE CONCRETE SURFACE OR WITHIN 1/2 INCH THEREOF, OF PLASTIC OR STAINLESS STEEL.

5. PROVIDE THE FOLLOWING MINIMUM CONCRETE STRENGTHS AT 28 DAYS:
   A) FOOTINGS, SLAB-ON-GRADE---------- 3000 PSI
   B) REGULAR/LIGHTWEIGHT FILL ON METAL DECK---------- 3000 PSI
   ⚠

6. CONCRETE MUST BE BATCHED, MIXED AND TRANSPORTED IN ACCORDANCE WITH THE SPECIFICATIONS FOR READY-MIXED CONCRETE ASTM C94.

7. REQUIRED SLUMP = 4 PLUS OR MINUS ONE INCH.

8. CONCRETE MUST BE PLACED WITHIN 90 MINUTES OF BATCH TIME. WHEN AIR TEMPERATURE IS BETWEEN 85 AND 90 DEGREES F, REDUCE MIXING AND DELIVERY TIME TO 75 MINUTES. WHEN AIR TEMPERATURE IS HIGHER THAN 90 DEGREES F, REDUCE MIXING AND DELIVERY TIME TO 60 MINUTES.

9. DO NOT ADD WATER AT THE JOB SITE WITHOUT APPROVAL OF THE PROJECT SUPERINTENDENT. DO NOT EXCEED THE SLUMP LIMITATION. USE ONLY COLD WATER FROM THE TRUCK TANK. ANY ADDED WATER MUST BE INDICATED ON THE DELIVERY TICKET PLUS THE NAME OF THE PERSON AUTHORIZING. TEST CYLINDERS SHALL BE TAKEN AFTER THE ADDITION OF WATER.

10. LAP SPLICE REINFORCING PER CONCRETE LAP SCHEDULE MINIMUM UNLESS OTHERWISE SHOWN OR NOTED.

11. PROVIDE CORNER BARS AT ALL WALL FOOTING, WALL AND BEAM CORNERS. SIZE AND NUMBER TO MATCH HORIZONTAL BARS.

12. PROVIDE FOUNDATION DOWELS TO MATCH SIZE AND NUMBER OF VERTICAL BARS. EMBED DOWELS TO:
   A) 3" ABOVE BOTTOM OF FOOTINGS

13. REINFORCEMENT SHALL BE FASTENED AND SECURED TOGETHER TO PREVENT DISPLACEMENT BY CONSTRUCTION LOADS OR THE PLACING OF CONCRETE.

14. REINFORCING BAR COVER
   A) FOOTINGS 2" (TOP), 3" (SIDES AND BOTTOM)
   B) COLUMNS AND BEAMS 1-1/2"
   C) SLABS 3/4" (INTERIOR), 1-1/2" (EXTERIOR)

15. WHERE BAR LENGTHS ARE GIVEN ON THE DRAWINGS, LENGTH OF HOOK, IF REQUIRED, IS NOT INCLUDED.

16. SELECT PROPORTIONS IN ACCORDANCE WITH ACI 301 TO PROVIDE CONCRETE CAPABLE OF BEING PLACED WITHOUT EXCESSIVE SEGREGATION AND WITH ACCEPTABLE FINISHING PROPERTIES, DURABILITY, SURFACE HARDENERS, APPEARANCE, AND STRENGTH REQUIREMENTS REQUIRED BY THESE SPECIFICATIONS.

17. CHAIR WELDED WIRE FABRIC REINFORCING AT 3'-0" ON CENTER MAXIMUM IN EACH DIRECTION.

18. MAXIMUM WATER TO CEMENT RATIO WHEN NO BACK-UP DATA IS AVAILABLE:
   A) 3000 PSI, 28-DAY COMPRESSIVE STRENGTH; W/C RATIO, 0.58 MAXIMUM (NON-AIR-ENTRAINED), 0.47 MAXIMUM (AIR-ENTRAINED).
   ⚠

19. DATA TO BE SUBMITTED:
   A) INTENDED USAGE AND LOCATION FOR EACH TYPE
   B) MIX DESIGN FOR EACH TYPE
   C) CEMENT CONTENT IN POUNDS-PER-CUBIC YARD
   D) COARSE AND FINE AGGREGATE IN POUNDS/CUBIC YARD
   E) WATER CEMENT RATIO BY WEIGHT
   F) CEMENT TYPE AND MANUFACTURER
   G) SLUMP RANGE
   H) AIR CONTENT
   I) ADMIXTURE TYPE AND MANUFACTURER
   J) PERCENT ADMIXTURE BY WEIGHT
   K) STRENGTH TEST DATA REQUIRED TO ESTABLISH MIX DESIGN.
   L) COMPLETE DETAIL AND PLACING SHOP DRAWINGS FOR ALL REINFORCING STEEL INCLUDING ACCESSORIES THAT HAVE BEEN REVIEWED AND STAMPED BY THE GENERAL CONTRACTOR. INCLUDE ALL REQUIRED DIMENSIONS AND ELEVATIONS (IE. TOP OF CONCRETE)

20. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE CONSTRUCTION OF FORMWORK, SHORING AND RE-SHORING IN ACCORDANCE WITH ACI 347.
   A) FORM AND SHORING DESIGN BY A P.E. REGISTERED IN THE STATE OF FLORIDA.

21. SUBMIT FORM WORK AND SHORING DRAWINGS TO LOCAL BUILDING DEPARTMENT WHEN REQUIRED BY FLORIDA THRESHOLD LAW.

22. CONSTRUCTION JOINTS NOT SHOWN ON THE DRAWINGS MUST BE MADE AND LOCATED TO LEAST IMPAIR THE STRENGTH OF THE STRUCTURE.
   A) NO HORIZONTAL CONSTRUCTION JOINTS WILL BE PERMITTED IN BEAMS, GIRDERS AND SLABS.
   B) LOCATION OF ANY CONSTRUCTION JOINT NOT SHOWN IS SUBJECT TO REVIEW AND ACCEPTANCE BY ENGINEER.

23. INTERNAL VIBRATION, PROPERLY APPLIED IS THE REQUIRED METHOD OF CONSOLIDATING PLASTIC CONCRETE.

24. PROVIDE 3/4" CHAMFER ON ALL EXPOSED CORNERS OF COLUMNS, BEAMS AND WALLS UNLESS OTHERWISE NOTED ON ARCHITECTURAL DRAWINGS.

25. CONTRACTOR SHALL VERIFY LOCATIONS OF ALL OPENINGS, SLEEVES, AND SLAB RECESSES AS REQUIRED BY OTHER TRADES BEFORE CONCRETE IS PLACED. NO SLEEVE, OPENINGS, OR INSERT MAY BE PLACED IN BEAMS, JOISTS, OR COLUMN UNLESS APPROVED BY THE ENGINEER.

26. CONTRACTOR SHALL VERIFY EMBEDDED ITEMS INCLUDING, BUT NOT LIMITED TO, ANCHOR BOLTS, BOLT CLUSTERS, WELD PLATES, ETC., BEFORE PLACING CONCRETE. NOTIFY ENGINEER OF ANY CONFLICTS WITH REBAR.

27. ALL EXPOSED CONCRETE SURFACES TO BE IN ACCORDANCE WITH ACI 301 SECTION 5.3.3.(C), INCLUDING SURFACE TOLERANCE CLASS A AS SPECIFIED IN ACI 117.U.N.O.

28. SEE ARCHITECTURAL DRAWINGS FOR REQUIRED CONCRETE FINISHES.

29. SLOPE WALKWAYS AND BALCONIES TO DRAIN AWAY FROM THE BUILDING.

30. BUILDING FLOOR AND SITE SLABS-ON-GRADE SHALL BE 4" MINIMUM THICKNESS, UNLESS NOTED OTHERWISE.
   A) REINFORCED WITH 6X6 – W1.4 X W1.4 W.W.F.
   B) PLACED ON 10 MIL POLYETHYLENE VAPOR RETARDER. LAP 6" AND TAPE ALL JOINTS.
   C) SAW-CUT CONTROL JOINTS @ LESS THAN OR EQUAL TO 15'-0" EACH WAY.
   D) PROVIDE HOUSEKEEPING PADS AS REQUIRED.
   E) SEE DRAWINGS FOR ANY ADDITIONAL CONDITIONS.

31. TESTING
   A) A QUALIFIED TESTING LAB SHALL BE RETAINED TO PERFORM QUALITY CONTROL WORK AND ON-SITE TESTING.
   B) SLUMP TEST – ASTM 143
   C) MOLD AND CURE TEST CYLINDERS (ASTM C-31) AND TEST CYLINDERS FOR STRENGTH (ASTM C39). TAKE ONE TEST – THREE CYLINDERS MINIMUM FOR EACH DAYS POUR OF 100 CUBIC YARDS, OR FRACTION THEREOF. TEST ONE CYLINDER AT 7 DAYS, TWO AT 28 DAYS. THE CONTRACTOR CAN REQUEST ADDITIONAL TEST CYLINDERS AT DIFFERENT INTERVALS IF DEEMED NECESSARY FOR THE CONSTRUCTION SCHEDULE AS APPROVED BY THE OWNER. TEST CYLINDER SAMPLES SHALL BE TAKEN AT THE POINT OF DISCHARGE WHEN USING A PUMP.
   D) ONE COPY OF ALL TEST REPORTS SHALL BE SENT DIRECTLY TO THE OWNER, ENGINEER, ARCHITECT AND GENERAL CONTRACTOR.

32. CONTRACTOR SHALL PROVIDE FLATNESS AND LEVELNESS IN CONCRETE SLABS PER ACI 302.1R, FIG. 10.7 MINIMUM REQUIRED "F" NUMBERS FOR TYPE OF SLAB USE. REFER TO ACI 117 FOR FLOOR TOLERANCES.

33. REPAIR ANY CRACKS OR DEFECTIVE AREAS THAT WILL RESTORE THE AFFECTED SURFACE OR AREAS TO THEIR FULL DESIGN STRENGTH AND APPEARANCE. CONTACT THE STRUCTURAL ENGINEER FOR ADVICE AND EVALUATION.

34. ACCEPTANCE OF THE STRUCTURE WILL BE MADE IN CONFORMANCE WITH ACI 301.

35. ALL CAST-IN-PLACE CONCRETE MUST BE MAINTAINED WITH MINIMAL MOISTURE LOSS AT A RELATIVELY CONSTANT TEMPERATURE FOR A MINIMUM OF 7 DAYS FOLLOWING THE PLACING OF THE CONCRETE BY THE USE OF A WATER SPRAY, WATER SATURATED FABRIC, MOISTURE RETAINING MEMBRANE OR LIQUID CURING COMPOUND.

36. CURE SLABS-ON-GRADE FOR THE FIRST 72 HOURS BY THE USE OF:
   A) FOG SPRAYING
   B) PONDING
   C) SPRINKLING
   D) CONTINUOUSLY WET ABSORPTIVE MATS OR FABRIC
   E) CONTINUE CURING BY USE OF MOISTURE RETAINING COVER UNTIL CONCRETE HAS OBTAINED ITS SPECIFIED 28 DAY COMPRESSIVE STRENGTH.
   F) OR LIQUID CURING COMPOUND AFTER FINISHING PROCESS IS COMPLETED.
   G) CONCRETE WET CURE TIME TO BE 7 DAYS MINIMUM AT 50 DEGREES MINIMUM TEMPERATURE.

37. SUBMIT MATERIALS AND METHOD OF CURING FOR REVIEW.

38. DO NOT USE MOISTURE RETAINING CURING COMPOUNDS FOR CURING SURFACES TO RECEIVE CARPET, FLEXIBLE FLOORING, CERAMIC TILED FLOORS OR OTHER SPECIFIED FLOOR SYSTEMS, UNLESS IT HAS BEEN DEMONSTRATED THAT SUCH COMPOUNDS WILL NOT PREVENT BOND.

39. DO NOT PERMIT CONCRETE NOT FULLY CURED TO BE EXPOSED TO EXCESSIVE TEMPERATURE CHANGES OR HIGH WINDS.

40. POUR ALL GROUND SLABS ON 10 MIL MINIMUM VAPOR RETARDER IN COMPLIANCE WITH ASTM E1745, LAPPED 6" MINIMUM AND FULLY TAPED.

41. EQUIPMENT MADE OF ALUMINUM OR ALUMINUM ALLOYS, SHALL NOT BE USED FOR PUMP LINES, TREMIES, OR CHUTES OTHER THAN SHORT CHUTES SUCH AS THOSE USED TO CONVEY CONCRETE FROM A TRUCK MIXER.

42. THE CODE PROHIBITS THE USE OF ALUMINUM (CONDUIT, PIPES, ETC.) IN STRUCTURAL CONCRETE UNLESS IT IS EFFECTIVELY COATED OR COVERED.

## DRILL-IN BOLTS, SCREWS AND DOWELS

1. ADHESIVE DOWELING RODS/BOLTS SHALL BE CARBON STEEL THREADED ROD CONFORMING TO ISO 898 5.8 WITH A MINIMUM TENSILE STRENGTH OF 72.5 KSI (500MPa) AND A MINIMUM YIELD OF 58 KSI (400MPa). THREADED RODS WITH NUTS AND WASHERS INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

2. ANCHORING ADHESIVE SHALL BE A TWO-COMPONENT SYSTEM SUPPLIED IN MANUFACTURER'S STANDARD SIDE-BY-SIDE FOIL PACKAGE AND DISPENSED THROUGH A STATIC-MIXING NOZZLE SUPPLIED BY THE MANUFACTURER. ADHESIVE SHALL BE TESTED AND APPROVED TO MEET THE MINIMUM REQUIREMENTS OF ACI 355.4 FOR CRACKED AND UNCRACKED CONCRETE RECOGNITION. PROVIDE HILTI HY 200 SAFE SET (ESR 3187) OR RE 500 V3 (ESR 3814) ANCHORS BY HILTI OR EQUAL (E.G. SIMPSON SET-XP, ATC ULTRABOND 365CC)UNLESS SPECIFIED OTHERWISE IN THE STRUCTURAL DOCUMENT.

3. DRILL-IN REBAR DOWELS SHALL BE SET USING A TWO-PART ADHESIVE AS DESCRIBED ABOVE.

4. EXPANSION BOLTS SHALL BE HILTI KB TZ (ESR 1917) OR EQUAL. BOLT SHALL MEET DUCTILITY REQUIREMENTS OF ACI 318 SECTION D1.

5. EXPANSION BOLTS SHALL HAVE CARBON STEEL ANCHOR BODY AND NUT AND WASHER SHALL BE ELECTROPLATED ZINC COATING CONFORMING TO ASTM B633 TO A MINIMUM OF 5µM. THE STAINLESS STEEL ANCHOR BODY, NUT AND WASHER, AND EXPANSION SLEEVE SHALL CONFORM TO TYPE 316 STAINLESS STEEL. EXPANSION ANCHORS SHALL MEET THE MINIMUM REQUIREMENTS OF ACI 355.2 FOR CRACKED AND UNCRACKED CONCRETE. INSTALL IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

6. MASONRY SCREWS SHALL BE 1/4" DIAMETER WITH 1-5/8" MINIMUM EMBEDMENT INSTALLED IN DRILLED HOLES USING AN APPROPRIATE BIT DIAMETER.

7. SCREWS SHALL HAVE A BODY MADE OF CARBON STEEL AND SHALL BE HEAT TREATED AND SHALL HAVE 8µM ZINC COATING IN ACORDANCE WITH EN ISO 4042. PROVIDE HUS EZ (ESR 3027) SCREWS BY HILTI OR EQUAL.

8. HEAVY-DUTY CONCRETE AND MASONRY SCREWS SHALL BE TESTED AND APPROVED TO MEET THE MINIMUM REQUIREMENTS OF ACI 355.2. HILTI KWICK HUS EZ (ESR-3027 FOR CONCRETE, ESR-3056 FOR GROUT FILLED MASONRY). HEAVY DUTY SCREWS BY HILTI OR EQUAL.

9. THE CONTRACTOR SHALL ARRANGE FOR AN ANCHOR MANUFACTURER'S REPRESENTATIVE TO PROVIDE ONSITE INSTALLATION TRAINING FOR ALL OF THE ANCHORING PRODUCTS SPECIFIED. PENNONI TO RECEIVE DOCUMENTED CONFIRMATION THAT ALL OF THE CONTRACTOR'S PERSONNEL WHO ARE TO INSTALL ANCHORS ARE TRAINED PRIOR TO THE COMMENCEMENT OF INSTALLATION.

## STRUCTURAL STEEL

1. STRUCTURAL STEEL SHALL CONFORM TO THE AISC "SPECIFICATION FOR BUILDINGS", LATEST EDITION.

2. WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISED CODE OF THE AMERICAN WELDING SOCIETY, AWS D1.1. ALL WELDING SHALL BE PERFORMED USING E70XX, LOW HYDROGEN ELECTRODES. ELECTRODES ARE TO BE PROTECTED FROM MOISTURE.

3. CONNECTIONS TO BE DOUBLE ANGLE FRAMED BEAM CONNECTION PER AISC UNLESS NOTED OTHERWISE. ALL BOLTS TO BE 3/4" DIAMETER UNLESS NOTED OTHERWISE. SHOP CONNECTIONS MAY BE WELDED OR BOLTED. WELDS ARE TO BE EQUAL IN STRENGTH TO BOLTS. ALL FIELD CONNECTIONS ARE TO BE BOLTED WITH ASTM A325N OR A490 BOLTS (BEARING TYPE BOLTS WITH THREADS IN THE SHEAR PLANE) INCLUDING SUITABLE NUTS AND PLAIN HARDENED WASHERS. ALL BOLTS SHALL BE TIGHTENED SNUG TIGHT UNLESS OTHERWISE NOTED. DESIGN CONNECTIONS FOR THE LARGER OF EITHER THE SHEAR SHOWN ON THE DRAWINGS, (INDICATED AS "V =K" AT ENDS OF MEMBER) OR 55% OF THE MAXIMUM LOAD(IN KIPS) LISTED IN THE TABLES FOR "MINIMUM TOTAL FACTORED UNIFORM LOADS IN KIPS FOR BRACED, SIMPLE SPAN BEAMS BENT ABOUT THE STRONG AXIS" OF THE LATEST EDITION OF THE AISC "MANUAL OF STEEL CONSTRUCTION".

4. SIZE AND USE OF HOLES: SEE AISC TABLE J3.3.
   A) LARGER HOLES ARE PERMITTED IN STANDARD COLUMN BASE PLATES. MAXIMUM HOLE DIAMETER = BOLT DIAMETER + 3/8". HARDENED WASHERS, TO COVER THE LARGER HOLE, SHALL BE PROVIDED.
   B) LARGER HOLES ARE NOT PERMITTED IN WIND FRAME COLUMN BASE PLATES. MAXIMUM HOLE DIAMETER = BOLT DIAMETER + 1/16".
   C) SLOTTED HOLES: A PLATE WASHERS OR A CONTINUOUS BAR WITH STANDARD HOLES, HAVING A SIZE SUFFICIENT TO COMPLETELY COVER THE SLOT AFTER INSTALLATION, AND A MIN. OF 5/16" THICK SHALL BE PROVIDED. TACK WELD NUT TO BOLT AFTER ERECTION.

5. STEEL BEAMS SHALL BE FABRICATED WITH THE NATURAL CAMBER (WITHIN THE MILL TOLERANCE) LOCATED ABOVE THE HORIZONTAL CENTERLINE BETWEEN THE END CONNECTIONS.

6. VERIFY THE EXACT SIZE AND LOCATION OF ALL FLOOR AND ROOF OPENINGS FOR MECHANICAL EQUIPMENT WITH THE MECHANICAL CONTRACTOR PRIOR TO FABRICATION OF MATERIALS.

7. SHOP PRIME STEEL SURFACES EXCEPT THE FOLLOWING:
   A) SURFACES EMBEDDED IN CONCRETE OR MORTAR. EXTEND PRIMING OF PARTIALLY EMBEDDED MEMBERS TO A DEPTH OF 2 INCHES.
   B) SURFACES TO BE FIELD WELDED.
   C) SURFACES TO BE HIGH-STRENGTH BOLTED WITH SLIP-CRITICAL CONNECTIONS.
   D) SURFACES TO RECEIVE SPRAYED FIRE-RESISTIVE MATERIALS.
   E) GALVANIZED SURFACES.

8. SURFACE PREPARATION: CLEAN SURFACES TO BE PAINTED. REMOVE LOOSE RUST AND MILL SCALE AND SPATTER, SLAG, OR FLUX DEPOSITS. PREPARE SURFACES ACCORDING TO THE FOLLOWING SPECIFICATIONS AND STANDARDS.

9. PRIMING: IMMEDIATELY AFTER SURFACE PREPARATION, APPLY PRIMER ACCORDING TO MANUFACTURER'S WRITTEN INSTRUCTIONS AND AT RATE RECOMMENDED BY SSPC TO PROVIDE A DRY FILM THICKNESS OF NOT LESS THAN 1.5 MILS. USE PRIMING METHODS THAT RESULT IN FULL COVERAGE OF JOINTS, CORNERS, EDGES, AND EXPOSED SURFACES.
   A) STRIPE PAINT CORNERS, CREVICES, BOLTS, WELDS, AND SHARP EDGES.
   B) APPLY TWO COATS OF SHOP PAINT TO INACCESSIBLE SURFACES AFTER ASSEMBLY OR ERECTION. CHANGE COLOR OF SECOND COAT TO DISTINGUISH IT FROM FIRST.

10. PRIME AND PAINT ALL FIELD WELDS AFTER INSPECTION.

11. A QUALIFIED TESTING LABORATORY SHALL BE RETAINED TO PERFORM THE FOLLOWING TESTS.
   A) VISUALLY INSPECT ALL STEEL MEMBERS AND CONNECTIONS.
   B) TEST 50 PERCENT OF FULL PENETRATION WELDS.

12. ONE COPY OF ALL TEST REPORTS SHALL BE SENT DIRECTLY TO OWNER, ARCHITECT, STRUCTURAL ENGINEER, AND GENERAL CONTRACTOR.

13. STEEL SHALL CONFORM TO:
   WIDE FLANGE (WF)(WT)---------- ASTM A992 (50 KSI)
   SHAPES (S, L, C, MC)---------- ASTM A36
   HOLLOW STRUCTURAL SECTIONS (HSS)---ASTM A500 GRADE C (RECTANGULAR 50 KSI; ROUND 46 KSI)
   STEEL PIPE---------- ASTM A53
   ANCHOR RODS---------- ASTM F1554 (55 KSI W/S1 SUPPLEMENT)
   ANCHOR BOLTS---------- ASTM A307
   FRAMING BOLTS---------- ASTM A325N OR A490N
   SHEAR STUDS---------- ASTM A108
   WELDING ELECTRODES---------- E70XX

14. FASTENERS AND MATERIALS USED FOR WELDING OR OTHERWISE SECURING COMPONENTS ONE TO ANOTHER SHALL BE OF DOMESTIC (USA MADE

| VERTICAL REINFORCEMENT BAR LAP SCHEDULE | | | | |
|---|---|---|---|---|
| BAR SIZE | COMPRESSION LAP | CLASS "B" TENSION LAP | | |
| | | 3,000 PSI | 4,000 PSI | 5,000 PSI |
| #4 | 15" | 28" | 25" | 23" |
| #5 | 25" | 36" | 31" | 28" |
| #6 | 30" | 43" | 37" | 33" |
| #7 | 35" | 63" | 54" | 49" |
| #8 | 40" | 72" | 62" | 55" |
| #9 | 44" | 81" | 70" | 63" |
| #10 | 50" | 91" | 79" | 70" |

NOTES:
1.BASED ON NORMAL WEIGHT CONCRETE & GRADE 60 REINFORCING BARS.

## VERTICAL REINFORCEMENT BAR LAP SCHEDULE - CONCRETE

1

| CONCRETE BEAM TENSION LAP SPLICE SCHEDULE | | | | |
|---|---|---|---|---|
| BAR SIZE | LOCATION | CONCRETE STRENGTH | | |
| | | 3,000 PSI | 4,000 PSI | 5,000 PSI |
| #4 | TOP BARS | 37" | 32" | 29" |
| | OTHER BARS | 29" | 25" | 22" |
| #5 | TOP BARS | 47" | 40" | 36" |
| | OTHER BARS | 36" | 31" | 28" |
| #6 | TOP BARS | 56" | 48" | 43" |
| | OTHER BARS | 43" | 37" | 33" |
| #7 | TOP BARS | 81" | 70" | 63" |
| | OTHER BARS | 63" | 54" | 49" |
| #8 | TOP BARS | 93" | 80" | 72" |
| | OTHER BARS | 72" | 62" | 55" |
| #9 | TOP BARS | 105" | 91" | 81" |
| | OTHER BARS | 81" | 70" | 63" |
| #10 | TOP BARS | 118" | 102" | 91" |
| | OTHER BARS | 91" | 79" | 70" |

NOTES:
1. BASED ON NORMAL WEIGHT CONCRETE & GRADE 60 REINFORCING BARS.
2. TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.
3. FOR LIGHTWEIGHT AGGREGATE, MULTIPLY ABOVE VALUES BY 1.3.

## CONCRETE BEAM TENSION LAP SPLICE SCHEDULE

2

Pennoni
1705 South Gadsden Street, Suite 100
Tallahassee, FL. 32301
(850) 671-7230
Florida Coa 7819
Justin W. Duncan, P.E.
Florida P.E. 78524
Pennoni Project No. FCGRP21003

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

**SCHEDULES**

SHEET NUMBER

# S-0.0.2




## NORTH TERMINAL RENOVATION FOUNDATION PLAN


SCALE : 1/8" = 1'-0"

**FOUNDATION PLAN NOTES:**

1. TOP OF FOOTING = SEE PLAN
2. CENTER ALL FOOTINGS BELOW COLUMN U.N.O.
3. REFER TO SHEET S-1.0.1 FOR FOOTING SCHEDULE.
4. SEE S-3.0.1 FOR TYPICAL FOUNDATION DETAILS.
5. VERIFY ALL DIMENSIONS W/ ARCH. AND EXISTING CONDITIONS PRIOR TO FABRICATION AND CONSTRUCTION.
6. REFER TO SHEETS S-0.0.1 FOR SPECIFICATIONS.
7. INFORMATION ON THE EXISTING BUILDING, SHOWN ON THESE PLANS, IS OBTAINED FROM EXISTING BUILDING PLANS BY HNTB ARCHITECTURE & PBS & J, DATED MAY 22, 2008 & DECEMBER 5, 2008 (ISSUED FOR CONSTRUCTION). EXISTING INFORMATION DOES NOT NECESSARILY REFLECT AS-BUILT CONDITIONS. THE CONTRACTOR SHALL VERIFY ALL INFORMATION SHOWN ON THESE PLANS AND NOTIFY THE ENGINEER OF ANY VARIATION.

### FOOTING SCHEDULE

| MARK | SIZE | DEPTH | REINF. EA. WAY | REMARKS | DWL/A.B. EMBEDMENT |
|---|---|---|---|---|---|
| F36 | 3'-6"x3'-6" | 1'-0" | (4) #5 | | 9" |
| F50 | 5'-0"x5'-0" | 1'-0" | (5) #5 | | 9" |




Pennoni
1705 South Gadsden Street, Suite 100
Tallahassee, FL. 32301
(850) 671-7230
Florida Coa 7819
Justin W. Duncan, P.E.
Florida P.E. 78524
Pennoni Project No. FCGRP21003

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

**NORTH TERMINAL RENOVATION FOUNDATION PLAN**


SHEET NUMBER

# S-1.0.1




## NORTH TERMINAL RENOVATION FLOOR FRAMING PLAN

SCALE : ⅛" = 1'-0"





## EXISTING STAIR INFILL

SCALE : ⅛" = 1'-0"


REFER TO ARCHITECT FOR LOCATION OF STAIR INFILL

**FLOOR FRAMING PLAN NOTES:**

1. FLOOR SLAB SHALL BE 5¼" LIGHTWEIGHT STRUCTURAL CONCRETE (120 PCF) ON 2" (20 GA.) COMPOSITE METAL DECK (TOTAL THICKNESS = 5¼") U.N.O. SLAB SHALL BE REINFORCED WITH 6x6- W2.1xW2.1 W.W.F. U.N.O. (⟷) INDICATES DIRECTION OF DECK SPAN.
2. INSTALL DECK IN (3) SPAN CONDITION, MIN.
3. TOP OF FLOOR SLAB EL. = (+) 14'-0" (MATCH EXISTING FIELD VERIFY) U.N.O. TOP OF STEEL BEAM EL. = (+) 13'-6⅜" U.N.O.
4. REFER TO ARCH. DWGS. FOR EDGE OF SLAB CONDITIONS.
5. REFER TO SHEET S-0.0.1 FOR SPECIFICATIONS.
6. ◀▶ INDICATES STEEL MOMENT CONNECTION.
7. COMPOSITE BEAMS ARE EQUALLY SPACED BETWEEN SUPPORTS, U.N.O. SEE S-3.0.2 FOR TYPICAL COMPOSITE BEAM DETAILS.
8. #4 x 5'-0 @ 12" O.C. TOP BARS OVER ALL INTERIOR GIRDERS. SEE DETAIL 5/S-3.0.2.
9. REFER TO SHEETS S-3.0.1 FOR TYPICAL FRAMING DETAILS.
10. REFER TO ARCH. FOR ANY DIMENSIONS OR ELEVATIONS MISSING OR DISCREPANCIES. VERIFY PRIOR TO FABRICATION AND INSTALLATION.
11. (2)#4x4'-0" @ SLAB MID. POINT
12. INFORMATION ON THE EXISTING BUILDING, SHOWN ON THESE PLANS, IS OBTAINED FROM EXISTING BUILDING PLANS BY HNTB ARCHITECTURE & PBS & J, DATED MAY 22, 2008 & DECEMBER 5, 2008 (ISSUED FOR CONSTRUCTION). EXISTING INFORMATION DOES NOT NECESSARILY REFLECT AS-BUILT CONDITIONS. THE CONTRACTOR SHALL VERIFY ALL INFORMATION SHOWN ON THESE PLANS AND NOTIFY THE ENGINEER OF ANY VARIATION.
13. STOREFRONT ABOVE SECOND FLOOR TO ATTACH TO EXISTING ROOF FRAMING ABOVE. IF SUPPLEMENTAL FRAMING IS REQUIRED ABOVE THE STOREFRONT, GC SHALL ACCOUNT FOR MINIMUM L4X4 DROP ANGLES, HEADER ANGLES, AND KICKER ANGLES AT 48" O.C. MAX FULLY WELDED TO ROOF FRAMING ABOVE. IF REQUIRED, CONTACT A/E FOR DETAIL ONCE EXISTING FRAMING HAS BEEN EXPOSED.




**COMPOSITE BEAM DESIGNATION DIAGRAM**




Pennoni
1705 South Gadsden Street, Suite 100
Tallahassee, FL 32301
(850) 671-7230
Florida Coa 7819
Justin W. Duncan, P.E.
Florida P.E. 78524
Pennoni Project No. FCGRP21003

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE


**NORTH TERMINAL RENOVATION FLOOR FRAMING PLAN**

SHEET NUMBER


# S-2.0.1





## COLUMN FOOTING 1




## COLUMN FOOTING 2





## BEAM-COLUMN CONNECTION 3




NOTE: SEE STRUCTURAL SPEC'S FOR CONNECTION DESIGN

## BEAM TO GIRDER WEB CONNECTION 4





## FLOOR OPENING REINFORCEMENT (PLAN) 5

### FLOOR OPENING SCHEDULE


| L ✱ | REINFORCEMENT |
|---|---|
| TO 10" | FORM OPENING TO EXCLUDE CONCRETE AND CUT DECK AFTER CONC. HAS ATTAINED 75% OF ITS DESIGN STRENGTH. NO REBARS. |
| 10" TO 16" | (2) #5 |
| 16" TO 24" | (3) #5 |
| 24" TO 30" | (4) #5 |
| OVER 30" | REQUIRES STRUCTURAL STEEL FRAME. |

✱ L- IS MEASURED AT RIGHT ANGLE TO FLOOR DECK SPAN

## FLOOR OPENING REINFORCEMENT (SCHEDULE) 6





## SECTION THRU SLAB OPENING. 7




NOTES:
1) TOP PLATE IS NOT TO BE WELDED TO SUPPORTING GIRDER FLANGE.
2) SHEAR STUDS FOR SUPPORTING GIRDER ARE NOT TO BE PLACED ON CONNECTION PLATE.
3) TOP CONNECTION PLATE TO BE CENTERED ON SUPPORTING BEAM CL

| SUPPORTING GIRDER | SUPPORTED BEAM | TOP PLATE | | | BOTTOM PLATE | | | WELD SIZE |
|---|---|---|---|---|---|---|---|---|
| | | LENGTH | WIDTH | THICKNESS | LENGTH | WIDTH | THICKNESS | |
| W18x65 | W16x36 | 33" | 6" | 1/2" | 16" | 8" | 1/2" | 3/8" |
| W18x65 | W16x40 | 33" | 6" | 1/2" | 16" | 8" | 1/2" | 3/8" |
| W18x40 | W12x26 | 31" | 5½" | 3/8" | 15" | 7½" | 3/8" | 1/4" |

## MOMENT CONNECTION DETAIL BEAM TO GIRDER 8




## BEAM TO COLUMN CONN. 9

Pennoni
1705 South Gadsden Street, Suite 100
Tallahassee, FL 32301
(850) 671-7230
Florida Coa 7819
Justin W. Duncan, P.E.
Florida P.E. 78524
Pennoni Project No. FCGRP21003

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE


**NORTH TERMINAL RENOVATION DETAILS**

SHEET NUMBER


# S-3.0.1





## COMPOSITE BEAM 1





## TYPICAL STUD PLACEMENT ON BEAMS 2





## TYPICAL STUD PLACEMENT ON GIRDERS 3




## TYPICAL STUD PLACEMENT ON BEAMS 4





## COMPOSITE GIRDER 5





NOTE 1: SHORE BENT PLATE UNTIL CONCRETE HAS CURED IF O.H. EXCEEDS 12"

## EDGE OF SLAB 6





NOTE 1: SHORE BENT PLATE UNTIL CONCRETE HAS CURED IF O.H. EXCEEDS 12"


## EDGE OF SLAB 7





## TYPICAL CLOSURE DETAIL 8





## TYPICAL COMPOSITE DECK ATTACHMENT (20 GAGE MIN.) 9




## TYPICAL CLOSURE DETAIL 10





## EDGE OF SLAB 11





NOTES:
1. DO NOT INSTALL ANGLE UNTIL AFTER THE CONCRETE DECK HAS BEEN POURED.
2. INSTALL BOLT AT THE BOTTOM OF THE SLOTTED HOLE W/ OVERSIZED WASHERS

## EDGE OF SLAB 12





NOTE 1: PROVIDE PENNONI W/ COLUMN DIMENSIONS PRIOR TO INSTALLING NEW BEAM ONCE FIREPROOFING IS REMOVED.


## CONN. TO EXISTING COLUMN 13




## INFILL AT EXISTING CB 14




## INFILL AT MASONRY WALL 15




## RAILING ATTACHMENT 16


Pennoni
1705 South Gadsden Street, Suite 100
Tallahassee, FL 32301
(850) 671-7230
Florida Coa 7819
Justin W. Duncan, P.E.
Florida P.E. 78524
Pennoni Project No. FCGRP21003


© 2018 All reproduction & intellectual property rights reserved.


FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**COMPOSITE DECK DETAILS**

SHEET NUMBER

**S-3.0.2**

# LEGEND

| | |
|---|---|
| RTU-1 | EQUIPMENT TAG |
| 1 / M3 | DETAIL TAG("1" INDICATES IDENTIFICATION NUMBER; "M3" INDICATES SHEET NUMBER DRAWN ON) |
| | SHEET NOTE |
| | SUPPLY DUCT SECTION POSITIVE PRESSURE |
| | RETURN OR EXHAUST DUCT NEGATIVE PRESSURE |
| AxB | RECTANGULAR DUCT SIZE ("A" INDICTES SIDE SHOWN; "B" INDICATES SIDE NOT SHOWN) |
| A/B | FLAT OVAL DUCT SIZE ("A" INDICATES SIDE SHOWN,"B" INDICATES SIDE NOT SHOWN) |
| AØ | ROUND DUCT SIZE |
| | EXTERNALLY INSULATED DUCTWORK |
| | DUCT ELBOW WITH TURNING VANES |
| | RADIUSED DUCT ELBOW |
| | FLEXIBLE DUCT CONNECTION |
| | MANUAL VOLUME BALANCING DAMPER |
| | HIGH PRESSURE DUCTWORK |
| | DOUBLE WALL HIGH PRESSURE DUCTWORK |
| | DUCTWORK TO BE DEMOLISHED |
| | DOUBLE WALL SPIRAL DUCTWORK |
| | GATE VALVE |
| | BUTTERFLY VALVE |
| | TWO-WAY CONTROL VALVE |
| | THREE-WAY CONTROL VALVE |
| | STRAINER WITH BLOW DOWN VALVE AND CAP |
| | THERMOMETER |
| | THERMOMETER WELL OR PRESSURE TEMPERATURE PORT AS INDICATED |
| VFD | VARIABLE FREQUENCY DRIVE |
| DDC | DIGITAL CONTROLS ENCLOSURE |
| | BUTTERFLY VALVE- VALVE HANDLE OPENS IN DIRECTION OF FLOW HANDLE |
| | BALL VALVE- VALVE HANDLE OPENS IN DIRECTION OF FLOW |

| | |
|---|---|
| | MOTORIZED DAMPER |
| FD | FIRE DAMPER WITH ACCESS DOOR |
| SD | SMOKE DAMPER WITH ACCESS DOOR |
| FSD | FIRE/SMOKE DAMPER WITH ACCESS DOOR |
| BD | BACKDRAFT DAMPER |
| | TEE WITH TURNING VANES AND BALANCING DAMPERS IN EACH LEG |
| | FLEX DUCT TAKEOFF WITH MVD. RUNOUT SIZE EQUALS DIFFUSER NECK SIZE UNLESS OTHERWISE INDICATED |
| | BRANCH DUCT TAKEOFF WITH MVD |
| | AUTOMATIC AIR VENT |
| | PRESSURE GAUGE AND 1/4" BALL VALVE |
| AFM | AIRFLOW MEASURING STATION |
| SR-1 / 100 | AIR DEVICE TAG. TOP LINE INDICATES TYPE OF DEVICE. BOTTOM LINE INDICATES AIRFLOW IN CFM. |
| (2)SR-1 / 100 | AIR DEVICE TAG. TOP LINE INDICATES TYPE OF DEVICE. BOTTOM LINE INDICATES AIRFLOW IN CFM. (2) INDICATES TYPICAL OF TWO DEVICES |
| SR-E / 100 | EXISTING AIR DEVICE TAG. TOP LINE INDICATES TYPE OF DEVICE. BOTTOM LINE INDICATES AIRFLOW IN CFM. |
| | UNION |
| LPS<br>HPS<br>XFR<br>EH<br>TF<br>APD | LOW PRESSURE SUPPLY<br>HIGH PRESSURE SUPPLY<br>TRANSFER<br>ELETRIC HEATER<br>TRANSFER FAN<br>AIR PRESSURE DROP |
| | POINT OF CONNECTION TO EXISTING |

| | |
|---|---|
| TYP | TYPICAL |
| TEMP | TEMPERATURE |
| SA | SUPPLY AIR |
| RA | RETURN AIR |
| EA | EXHAUST AIR |
| OA | OUTDOOR AIR |
| TA | TRANSFER AIR |
| EF | EXHAUST FAN |
| CD | CEILING DIFFUSER |
| RG | RETURN GRILLE |
| EG | EXHAUST GRILLE |
| SWG | SIDEWALL SUPPLY GRILLE |
| LVR | LOUVER |
| CEF | CEILING EXHAUST FAN |
| AHU | INDOOR AIR HANDLING UNIT |
| CHWP | CHILLED WATER PUMP |
| HWP | HEATING HOT WATER PUMP |
| T | THERMOSTAT, "1" INDICATES UNIT CONTROLLED. MOUNT WITH TOP AT 48" AFF. |
| S | DUCT MOUNTED SMOKE DETECTOR |
| UC | UNDERCUT DOOR 3/4" |
| | 16x16 DOOR GRILL |
| N.I.C | NOT IN CONTRACT |
| AFF | ABOVE FINISHED FLOOR |
| FD | FLOOR DRAIN |
| TG | TRANSFER GRILLE |
| SG | SOFFIT GRILLE |
| SWS | SIDEWALL SUPPLY GRILLE |
| SWR | SIDEWALL RETURN GRILLE |
| DDC | DIRECT DIGITAL CONTROL |
| CHW | CHILLED WATER |
| CHWS | CHILLED WATER SUPPLY |
| CHWR | CHILLED WATER RETURN |
| NO | NORMALLY OPEN |
| NC | NORMALLY CLOSED |
| VFM | VENTURI FLOW METER |
| AI | ANALOG INPUT |
| AO | ANALOG OUTPUT |
| DI | DIGITAL INPUT |
| DO | DIGITAL OUTPUT |
| TAB | TESTING, ADJUSTING AND BALANCING |
| TU | TERMINAL UNIT |
| NOM | NOMINAL |
| VFD | VARIABLE FREQUENCY DRIVE |
| E | EXISTING |
| MVD | MANUAL VOLUME DAMPER |
| UH | UNIT HEATER |
| H | HUMIDITY SENSOR |
| MHP | MINI SPLIT SYSTEM HEAT PUMP |
| WM | WALL MOUNTED UNIT |

# DUCTWORK AND INSULATION GENERAL NOTES

1. ALL ROUND FLEXIBLE DUCT SHALL BE FLEXMASTER TYPE 8M OR ENGINEER APPROVED EQUAL. MAXIMUM LENGTH OF ANY FLEXIBLE DUCT RUNOUT SHALL BE 5'-0". WHERE LENGTH REQUIRED EXCEEDS 5'-0", INSTALL EXTERNALLY INSULATED ROUND SNAPLOCK DUCT FOR BALANCE OF DISTANCE TO SPIN-IN TAP AT MAIN DUCT TRUNK.
2. SEAL ALL DUCT PENETRATIONS OF WALLS AND FLOORS AIRTIGHT, REGARDLESS OF WHETHER WALLS AND FLOORS ARE FIRE RATED OR NOT.
3. UNLESS OTHERWISE INDICATED, ALL SUPPLY AIR DUCTWORK UPSTREAM OF TERMINAL UNITS SHALL BE OVAL OR ROUND, SMACNA STATIC PRESSURE CLASS 3" W.G., SEAL CLASS A. DUCT SIZES INDICATED ARE INSIDE CLEAR DIMENSIONS.
4. ALL SUPPLY AIR DUCTWORK UPSTREAM OF TERMINAL UNITS WITHIN 40' OF AHU DISCHARGE SHALL BE DOUBLE WALL SPIRAL WITH PERFORATED INNER LINER.
5. ALL SUPPLY AIR DUCTWORK DOWNSTREAM OF TERMINAL UNITS (EXCEPT TAKEOFFS TO SUPPLY AIR DIFFUSERS) SHALL BE LOW PRESSURE RECTANGULAR, SMACNA STATIC PRESSURE CLASS 2" W.G., SEAL CLASS A, EXTERNALLY INSULATED. DUCT SIZES INDICATED ARE INSIDE CLEAR DIMENSIONS.
6. ALL RETURN AIR DUCTWORK SHALL BE LOW PRESSURE RECTANGULAR, SMACNA STATIC PRESSURE CLASS 2" W.G., SEAL CLASS A, EXTERNALLY INSULATED. DUCT SIZES INDICATED ARE INSIDE CLEAR DIMENSIONS.
7. ALL AHU RETURN DUCT WITHIN 40' OF AHU RETURN PLENUM SHALL BE LINED WITH 2" DUCT LINER PER PROJECT SPECIFICATIONS.
8. ALL AHU RETURN PLENUMS SHALL BE LINED WITH 2" DUCT LINER PER PROJECT SPECIFICATIONS.
9. ALL OUTSIDE AIR INTAKE DUCTWORK SHALL BE LOW PRESSURE RECTANGULAR, SMACNA STATIC PRESSURE CLASS 2" W.G., SEAL CLASS A, EXTERNALLY INSULATED. DUCT SIZES INDICATED ARE INSIDE CLEAR DIMENSIONS.
10. STANDARD EXHAUST AIR DUCTWORK SHALL BE LOW PRESSURE RECTANGULAR, SMACNA STATIC PRESSURE CLASS 1/2" W.G., SEAL CLASS A, INSULATION NOT REQUIRED.
11. AVOID ROUTING DUCTWORK AND TU'S WITHIN 6" OF TOP OF LIGHT FIXTURES WHEREVER POSSIBLE. MAINTAIN CLEARANCE BETWEEN TU'S AND DUCT INSULATION TO TOP OF LIGHTS. PROVIDE CLEARANCE ALL AROUND AIR TERMINAL UNITS AS REQUIRED FOR ROUTINE MAINTENANCE.
12. PROVIDE MVD'S AT ALL TAKEOFFS FROM MAIN DUCTS.
13. CONTRACTOR SHALL SUBMIT COORDINATED DUCTWORK SHOP DRAWINGS INDICATING COORDINATION WITH ELECTRICAL AND PLUMBING PRIOR TO BEGINNING WORK. SHOP DRAWINGS SHALL INCLUDE LOCATIONS OF THERMOSTATS, ACCESS PANELS, AIR DEVICES, DUCTWORK, ETC.

# GENERAL NOTES

1. ALL DUCT DIMENSIONS ARE NET INSIDE.
2. VERIFY COLLAR SIZES ON ALL AIR TERMINALS, EQUIPMENT OUTLETS AND INLETS, TRANSITION DUCTWORK AS NECESSARY. EXTERNALLY INSULATE TRANSITIONS AT EQUIPMENT CONNECTIONS.
3. FIELD VERIFY CLEAR SPACE AVAILABLE, ROUTING PATH, AND CONFLICTS WITH STRUCTURE AND THE WORK OF OTHER TRADES PRIOR TO FABRICATING DUCTWORK. PROVIDE OFFSETS IN DUCTWORK AS REQUIRED, WHETHER SPECIFICALLY INDICATED ON DRAWINGS OR NOT. SUBMIT SHOP DRAWINGS ON DUCTWORK LAYOUT PRIOR TO COMMENCING WORK. MAINTAIN CLEARANCE AROUND ALL LIGHT FIXTURES AS REQUIRED TO REMOVE AND SERVICE FIXTURES. COORDINATE WITH ROOF TRUSSES/STRUCTURE. PRESSURE TEST ALL DUCTWORK FOR LEAKS. SEE SPECIFICATIONS.
4. CONTRACTOR SHALL INSTALL ALL EQUIPMENT, PIPING, AND DUCTWORK SUCH THAT MANUFACTURERS' RECOMMENDED CLEARANCES ARE MET FOR ALL ACCESS PANELS, MOTORS, FANS, BELTS, FILTERS AND AIR INTAKES. CONDENSATE LINES SHALL BE CLEAR OF FILTER RACK ACCESS.
5. PROVIDE DUCT FLEX CONNECTIONS & VIBRATION ISOLATION FOR ALL UNITS NOT INTERNALLY ISOLATED.
6. WASTE VENT STACKS, EXHAUST FANS, ETC. SHALL BE A MINIMUM OF 10 FT. FROM OUTSIDE AIR INTAKES.
7. ALL SUPPLY, RETURN, EXHAUST AND OUTSIDE AIR INTAKE DUCTWORK SHALL BE GALVANIZED SHEET METAL.
8. ALL AHU FILTERS SHALL BE OF A READILY AVAILABLE SIZE, OF DISPOSABLE TYPE, AND BE ACCESSIBLE WITHOUT THE USE OF SCREWS OR OTHER MECHANICAL DEVICES REQUIRING TOOLS.
9. PROVIDE ACCESS PANELS IN HARD CEILINGS AS REQUIRED FOR MAINTENANCE AND ADJUSTMENT OF EQUIPMENT LOCATED ABOVE CEILING.
10. ALL BIRD AND INSECT SCREENS SHALL BE ANODIZED ALUMINUM.
11. BECAUSE OF THE SMALL SCALE OF CONTRACT DOCUMENTS IT IS NOT POSSIBLE TO SHOW ALL OFFSETS, TRANSITIONS, ETC. THE CONTRACT DOCUMENTS ARE ESSENTIALLY DIAGRAMATIC. THE CONTRACTOR SHALL PROVIDE SHOP DRAWINGS COORDINATED WITH THE STRUCTURE AND ARCHITECTURAL WORK FOR REVIEW PRIOR TO COMMENCING WORK
12. ALL WORK SHALL COMPLY WITH 7TH EDITION (2020) FLORIDA BUILDING CODE.

## AIR PURIFICATION EQUIPMENT SCHEDULE

| ZONE AHU | SA (CFM) | OA (CFM) | PRESS (IN W.C.) | BASIS OF DESIGN | MODEL | QUANTITY | ELECTRICAL VOLTS/PHASE | ELECTRICAL WATTS | NOTES |
|---|---|---|---|---|---|---|---|---|---|
| 2-2(E) | 10355 | 1745 | 1.05 | GPS | iMOD | 1 | 120/1 | 8 | 1,2,3,4 |

1. BI-POLAR IONIZATION SYSTEMS REQUIRING PERISHABLE GLASS TUBES ARE NOT ACCEPTABLE.
2. MANUFACTURER MUST PASS UL-867-2007 OZONE CHAMBER TESTING BY EITHER UL OR ETL.
3. UNIT SHALL BE MOUNTED IN SUPPLY AIR DUCT.
4. PROVIDE 12V DC POWER SUPPLY FOR CONTROL PANEL.

## GRAVITY VENTILATOR SCHEDULE

| UNIT | THROAT SIZE | BASIS OF DESIGN | MODEL | NOTES |
|---|---|---|---|---|
| GV-1 | 20x20 | GREENHECK | FGR | 1,2,3 |
| GV-2 | 12x12 | GREENHECK | FGR | 1,2,3 |

1. PROVIDE ROOF CURB.
2. PROVIDE ALUMINUM BIRDSCREEN.
3. PROVIDE WITH AND INSTALL IN ACCORDANCE WITH FLORIDA PRODUCT APPROVAL.

## EXISTING AIR HANDLING UNIT SCHEDULE

| UNIT DESIG-NATION | FAN DATA: AIR VOLUME CONTROL | MAX AIRFLOW (CFM) | MIN. AIRFLOW (CFM) | MIN. OA DAMPER (CFM) | APPROX. ESP (IN. W.G.) | TOTAL SP (IN. W.G.) | CHILLED WATER COIL DATA: UNIT TOTAL CAPACITY (MBH) | UNIT SENSIBLE CAPACITY (MBH) | AIR SIDE EAT (°F) DB | AIR SIDE EAT (°F) WB | AIR SIDE LAT (°F) DB | AIR SIDE LAT (°F) WB | WATER SIDE FLOW (GPM) | WATER SIDE EWT (°F) | WATER SIDE LWT (°F) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AHU-2-2(E) | VAV | 10355 | 3105 | 1745 | 2.5 | 4.44 | 390.2 | 248.0 | 75.8 | 65.6 | 53.4 | 52.6 | 55.74 | 44 | 58 |

1

## VARIABLE VOLUME TERMINAL UNIT SCHEDULE

| MARK | TOTAL CFM | COOL CFM MIN. | HEATING CFM MAX. | HEATING COIL EAT (°F) | HEATING COIL LAT (°F) | HEATING COIL KW | HEATING COIL VOLTS/PHASE | HEATING COIL MCA | HEATING COIL MOP | SOUND POWER AT 1.0' REF. CFM | SOUND POWER AT 1.0' DISCHARGE NC | SOUND POWER AT 1.0' RADIATED NC | INLET SIZE (IN.) | MANUFACTURER | MODEL NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | | | |
| VAV-2-2-6 | 1560 | 470 | 470 | 53.4 | 85 | 5.0 | 480/3 | 7.5 | 15 | 1730 | - | - | 14 | TITUS | DESV |
| VAV-2-2-7 | 1785 | 535 | 535 | 53.4 | 85 | 5.0 | 480/3 | 7.5 | 15 | 1725 | - | - | 14 | TITUS | DESV |
| VAV-2-2-8 | 325 | 105 | 105 | 53.4 | 85.1 | 1.0 | 277/1 | 4.5 | 15 | 355 | 17 | 20 | 6 | TITUS | DESV |
| VAV-2-2-9 | 335 | 100 | 100 | 53.4 | 86.6 | 1.0 | 277/1 | 4.5 | 15 | 335 | 15 | 18 | 6 | TITUS | DESV |
| VAV-2-2-10 | 340 | 100 | 100 | 53.4 | 86.6 | 1.0 | 277/1 | 4.5 | 15 | 340 | - | 18 | 6 | TITUS | DESV |
| VAV-2-2-11 | 360 | 105 | 105 | 53.4 | 85.1 | 1.0 | 277/1 | 4.5 | 15 | 360 | 17 | 20 | 6 | TITUS | DESV |
| VAV-2-2-12 | 340 | 100 | 100 | 53.4 | 86.6 | 1.0 | 277/1 | 4.5 | 15 | 340 | - | 18 | 6 | TITUS | DESV |

1

TERMINAL UNIT SCHEDULE NOTES:

1. ALL VAV TERMINAL UNITS SHALL BE PRESSURE INDEPENDENT.
2. PROVIDE ALL VAV TERMINAL UNITS WITH ACCESS PANEL TO ALLOW SERVICING OF AIR VALVE WITHOUT DISCONNECTING DUCT WORK.
3. PROVIDE ALL VAV TERMINAL UNITS WITH 1.5 PCF CLOSED CELL FOAM INSULATION.
4. SOUND DATA FOR DISCHARGE NC BASED ON 10 dB ROOM ABSORPTION, 5' LINED DUCT (12"x12") WITH 1" THICK FIBERGLASS INSULATION, 6' LINED FLEX DUCT (8") TO DIFFUSER, AND MAX 300 CFM PER DIFFUSER. CALCULATED PER AHRI 880-2011.
5. SOUND DATA FOR RADIATED NC BASED ON 10 dB ROOM ABSORPTION, 5' DEEP CEILING CAVITY, AND 5/8" THICK, 3.5 LB/CU. FT. FIBER CEILING TILE.
6. PROVIDE VAV TERMINAL UNITS WITH FACTORY MULTIPOINT FLOW SENSOR.
7. PROVIDE FACTORY MOUNTED 120V CONTROLS TRANSFORMER TO SUPPLY 24 VOLT POWER TO DAMPER ACTUATOR AND CONTROLS.

## AIR DEVICE SCHEDULE

| MARK | MAX AIRFLOW CFM | AIR DEVICE SIZE | DUCT CONNECTION SIZE | TITUS MODEL |
|---|---|---|---|---|
| CD-1 / CFM | 80 | 9x9 | 6Ø | TDC |
| CD-2 / CFM | 230 | 12x12 | 8Ø | TDC |
| CD-3 / CFM | 350 | 12x12 | 10Ø | TDC |
| CD-4 / CFM | 250 | 24x48 PLENUM | 8Ø | N/A |
| SWG-1 / CFM | 60 | 6x6 | 6x6 | 272RL |
| RG,EG,SG,TG,RR,ER | | | | |
| xx-1 / CFM | 530 | 12x12 | 12x12 | 350FL |
| xx-2 / CFM | 1800 | 22x22 | 22x22 | 350FL |
| xx-3 / CFM | 3170 | 30x30 | 30x30 | 350FL |

NOTES:
1. MAX NC=20
2. PROVIDE 2x2 LAY IN PANEL FOR AIR DEVICES IN LAY IN CEILINGS.
3. PROVIDE BEVELED MOUNTING FRAME FOR CEILING DIFFUSERS IN HARD CEILINGS.
4. PROVIDE FLAT MOUNTING FRAME FOR GRILLES LOCATED IN HARD CEILINGS.
5. PAINT ALL DUCT VISIBLE THROUGH GRILLES FLAT BLACK.

## EXISTING TERMINAL UNIT SCHEDULE

| MARK | TOTAL CFM | COOL CFM MIN. | HEATING CFM MAX. | HEATING COIL EAT (°F) | HEATING COIL LAT (°F) | HEATING COIL KW |
|---|---|---|---|---|---|---|
| VAV-2-2-1(E) | 250 | 75 | 75 | 53.4 | 85 | 5 |
| VAV-2-2-2(E) | 960 | 290 | 290 | 53.4 | 85 | 5 |
| VAV-2-2-3(E) | 1210 | 365 | - | - | - | - |
| VAV-2-2-5(E) | 1890 | 575 | 575 | 53.4 | 85 | 10 |

1

## FAN SCHEDULE

| UNIT | TYPE | CFM | MAX. FAN RPM | ESP (IN. H20) | MAX. MOTOR POWER | SONES/db (MAX) | BASIS OF DESIGN | MODEL | CONTROL | ELECRICAL VOLTS/PHASE | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|
| EF-1 | INLINE | 790 | 1020 | 0.3 | 0.17 BHP | 1.5 | GREENHECK | CSP-A1050-VG | INTERLOCK WITH AHU-2-2(E) OA DAMPER | 120/1 | 1,2,3,4,5,6 |

1. PROVIDE DISCONNECT
2. PROVIDE SOLID STATE SPEED CONTROLLER
3. PROVIDE BACKDRAFT DAMPER
4. PROVIDE THERMAL OVERLOAD
5. PROVIDE DIRECT DRIVE FAN WITH EC MOTOR.
6. PROVIDE RUBBER IN SHEAR VIBRATION ISOLATION.

## MINI SPLIT SYSTEM CONDENSING UNIT SCHEDULE


| UNIT MHP | BASIS OF DESIGN | MODEL | NOMINAL COOL CAPACITY (BTUH) | DESIGN COOLING OUTDOOR TEMP DB | SEER | NOMINAL HEAT CAPACITY (BTUH) | DESIGN HEATING OUTDOOR TEMP DB | HSPF | VOLTS/PHASE | MCA (AMPS) | MOCP (AMPS) | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | MITSUBISHI | MUZ-GL18NA | 18000 | 95.0 | 20.5 | 21600 | 25.0 | 11.2 | 208/1 | 14 | 15 | 1,2,3 |

1. NOMINAL COOLING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 80/67°F (DB/WB), OUTDOOR OF 95°F (DB).
2. NOMINAL HEATING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 70°F (DB), OUTDOOR OF 43°F (WB).
3. EFFICIENCY VALUES FOR EER, IEER, AND COP ARE BASED ON AHRI 1230 TEST METHOD FOR MIXTURE OF DUCTED AND NON-DUCTED INDOOR UNITS.

## MINI SPLIT SYSTEM AIR HANDLING UNIT SCHEDULE

| UNIT | BASIS OF DESIGN | MODEL | TYPE | NOMINAL COOL CAPACITY (BTUH) | DESIGN COOLING EAT °F DB/WB | DESIGN COOLING CAPACITY (BTUH): COOLING TOTAL | DESIGN COOLING CAPACITY (BTUH): COOLING SENSIBLE | NOMINAL HEAT CAPACITY (BTUH) | DESIGN HEATING TOTAL CAPACITY (BTUH) | DESIGN HEATING EAT °F DB | AIRFLOW (CFM) | VOLTS/PHASE | MCA (AMPS) | MOP (AMPS) | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| WM-1 | MITSUBISHI | MSZ-GL18NA | WALL UNIT | 18000 | 72/61 | 18000 | 17000 | 18000 | 0 | 70 | 470 | FED FROM HP | NA | NA | 1,2,3,4,5,6,7 |

1. NOMINAL COOLING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 80/67°F (DB/WB), OUTDOOR OF 95°F (DB).
2. NOMINAL HEATING CAPACITIES ARE BASED ON INDOOR COIL EAT OF 70°F (DB), OUTDOOR OF 43°F (WB).
3. DESIGN COOLING CONDITIONS ARE AT 95°F AMBIENT; DESIGN HEATING CONDITIONS ARE AT 25°F AMBIENT.
4. DESIGN CAPACITY IS NET CAPACITY FOR INSTALLATION ACCOUNTING FOR 65 FT PIPE RUN LEGNTHS, ETC.
5. CALCULATE REFRIGERANT LINE SIZES BASED UPON FINAL FIELD PIPING LAYOUT.
6. EXPOSED (INDOOR OR OUTDOOR) REF PIPING SHALL BE HARD DRAWN COPPER
7. PROVIDE BAC-NET MODULE.




© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

# HVAC LEGEND, SCHEDULES, AND NOTES

SHEET NUMBER


# M0.0.1

WATFORD ENGINEERING
850.526.3447
4402 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27525
David N. Watford, PE
Florida License Number: 58208
Project Number 2021-061

5/9/2022 5:35:06 PM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Mechanical.rvt

## SHEET NOTES

1. REMOVE PORTION OF EXISTING DUCT AS SHOWN. SEAL OPENING IN MAIN DUCT AIRTIGHT PER PROJECT SPECIFICATIONS.
2. REMOVE EXISTING VARIABLE AIR VOLUME TERMINAL UNIT AND ALL RELATED CONTROLS.
3. REMOVE EXISTING AIR DEVICE.
4. REMOVE EXISTING THERMOSTAT.
5. REMOVE VAV TERMINAL UNIT AND RELATED THERMOSTAT FOR RELOCATION. REFER TO M2.0.1 FOR NEW LOCATION.




# HVAC DEMOLITION PLAN-LEVEL 2

1 M1.0.1 SCALE: 1/8" = 1'-0"

TRUE PROJECT

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

**NORTH TERMINAL EXPANSION / IMPROVEMENTS**

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER


NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**HVAC DEMOLITION PLAN - LEVEL 2**




WATFORD ENGINEERING
850.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27525
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061


SHEET NUMBER

**M1.0.1**

5/9/2022 5:35:09 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Mechanical.rvt

## SHEET NOTES

1. ENSURE DUCT DOES NOT INTERFERE WITH EXISTING CONDUIT.
2. PROVIDE AVERAGING SENSORS TO CONTROL VAV-2-2-3, VAV-2-2-6, AND VAV-2-2-7.
3. PROVIDE CEILING MOUNTED TEMPERATURE SENSOR.
4. PROVIDE GRAVITY VENTILATOR AND 10" ROUND DUCT FOR FUTURE EXHAUST CONNECTION. CAP DUCT ABOVE CEILING.
5. PROVIDE GRAVITY VENTILATOR FOR FUTURE MAKEUP AIR CONNECTION. DUCT FULL SIZE OF GRAVITY VENTILATOR DOWN AND CAP 12" BELOW BOTTOM OF ROOF.




## 1 HVAC NEW WORK PLAN - LEVEL 2

M2.0.1 SCALE: 1/8" = 1'-0"

TRUE PROJECT


WATFORD ENGINEERING
860.526.3447
4402 Clinton Street
Manvarra, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number 2021-061



© 2018 All reproduction & intellectual property rights reserved.



FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**HVAC NEW WORK PLAN - LEVEL 2**

SHEET NUMBER

**M2.0.1**


5/9/2022 5:35:15 PM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Mechanical.rvt




NOTES:


CONNECT FLEXIBLE DUCT TO FITTING WITH DRAWBAND AND SEALER.

ROUND HARD DUCT RUNOUTS SHOULD START WITH SPIN-IN FITTINGS SIMILART TO THIS DETAIL.


PROVIDE REMOTE CABLE ACTUATOR FOR AIR DEVICE IN HARD CEILINGS WITHOUT ACCESS. MOUNT ACTUATOR IN FACE OF AIR DEVICE.

FLEXIBLE INSULATION SHALL BE 2" THICK, ASTM C553, TYPE 1, CLASS B-3 WITH 1 PCF DENSITY AND UL RATED ALUMINUM FOIL VAPOR BARRIER (FSK)

## 1 TYPICAL FLEX DUCT TAKEOFF DETAIL
M3.0.1 SCALE: NONE




## 2 TERMINAL UNIT MOUNTING DETAIL
M3.0.1 SCALE: NONE




NOTES:


PIPE TYPE 'L' HARD DRAWN COPPER CONDENSATE LINE AT FULL SIZE OF UNIT CONNECTION, BUT IN NO CASE SMALLER THAN 3/4". CONDENSATE LINES SHALL BE INSULATED WITH 1/2" FLEXIBLE UNICELLULAR INSULATION.

LOCATE TRAPS SO AS TO BE ACCESSIBLE FOR CLEANING.

H=AIR UNIT TOTAL STATIC PRESSURE +1"


J=H/2

## 3 NEGATIVE PRESSURE CONDENSATE DRAIN TRAP
M3.0.1 SCALE: NONE





NOTE: TYPICAL FOR LOW PRESSURE DUCTWORK

## 4 TYPICAL DUCT HANGER DETAILS
M3.0.1 SCALE: NONE




## 5 OVERHEAD PIPE SUPPORT
M3.0.1 SCALE: NONE





NOTES:

PROVIDE REMOTE CABLE ACTUATOR FOR AIR DEVICE IN HARD CEILINGS WITHOUT ACCESS. MOUNT ACTUATOR IN FACE OF AIR DEVICE.

FLEXIBLE INSULATION SHALL BE 2" THICK, ASTM C553, TYPE 1, CLASS B-3 WITH 1 PCF DENSITY AND UL RATED ALUMINUM FOIL VAPOR BARRIER (FSK)

## 6 TYPICAL BRANCH DUCT TAKEOFF
M3.0.1 SCALE: NONE




NOTES:

FLEX DUCT SHALL BE NO LONGER THAN 5'-0". FLEXIBLE DUCT SHALL HAVE REINFORCED, METALIZED POLYESTER JACKET WITH NO FIBERGLASS EROSION IN THE AIRSTREAM AND AN ENCAPUSLATED WIRE HELIX. FLEX DUCT SHALL HAVE OPERATING PRESSURE OF 6" W.G. AND NEGATIVE OPERATING PRESSURE OF 0.75" W.G. FLEX DUCT SHALL HAVE R-VALUE OF R-6 AND MEET REQUIREMENTS OF UL-181, 2020 FLORIDA ENERGY CODE, NFPA 90A AND NFPA 90B. ATCO 56 OR APPROVED EQUAL.

PROVIDE 24X24 LAY IN PANEL FOR DIFFUSERS IN LAY IN CEILINGS.

PROVIDE BEVELED MOUNTING FRAME FOR DIFFUSERS IN HARD CEILINGS.

## 7 TYPICAL CEILING DIFFUSER DETAILS
M3.0.1 SCALE: NONE






TABLE 1: CURB-TO-DECK MOUNTING


| THROAT SIZE (LARGEST DIM.) | FASTENERS PER SIDE |
|---|---|
| ≤24 | 2 |
| ≤48 | 3 |
| ≤54 | 3 |
| ≤64 | 4 |

FASTENERS REQUIRED ONLY ON TWO OPPOSITE SIDES OF CURB. FASTEN ON LONGER SIDES OF CURB IF RECTANGULAR. MIN. 3.06" EDGE DISTANCE ON BOTH SIDES.

## 8 GRAVITY VENTILATOR DETAIL
M3.0.1 SCALE: NONE




## 9 INLINE FAN DETAIL
M3.0.1 SCALE: NONE




NOTES:

PLENUM BOX SHALL BE CONSTRUCTED FROM 2" THICK DUCTBOARD.

## 10 PLENUM BOX DETAIL
M3.0.1 SCALE: NONE


WATFORD ENGINEERING
850.526.3447
4402 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number 2021-061


© 2018 All reproduction & intellectual property rights reserved.


FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**HVAC DETAILS**

SHEET NUMBER

**M3.0.1**

5/9/2022 5:35:18 PM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Mechanical.rvt

# DIRECT DIGITAL CONTROLS GENERAL NOTES

1. THE CONTRACTOR SHALL PROVIDE NEW DDC CONTROLLERS TO PERFORM THE INDICATED SEQUENCES, ALL OTHER FUNCTIONS REQUIRED BY THE CONTRACT DOCUMENTS, AND ALL OTHER FUNCTIONS REQUIRED FOR A COMPLETE AND FUNCTIONAL SYSTEM. NEW CONTROLS SHALL TIE INTO EXISTING TRANE SYSTEM.
2. ALL SEQUENCES ARE SUBJECT TO SAFETIES. DDC CONTRACTOR SHALL PROVIDE ALL NECESSARY AND CUSTOMARY SAFETIES.
3. ALL WIRING SHALL BE IN CONDUIT. ALL CONDUIT SHALL BE IN ACCORDANCE WITH ELECTRICAL SPECIFICATIONS, REQUIREMENTS FOR 120 VAC CIRCUITS.
4. ALL CONTROL TUBING SHALL BE RUN IN CONDUIT. ALL CONDUIT SHALL BE IN ACCORDANCE WITH ELECTRICAL SPECIFICATIONS, REQUIREMENTS FOR 120 VAC CIRCUITS.
5. ALL WELLS SHALL BE 316 STAINLESS STEEL AND SHALL BE INSTALLED IN NEW THREDOLETS WHETHER INSTALLED IN NEW OR EXISTING PIPING. IN CHILLED WATER PIPING PROVIDE NEW WELLS WITH EXTENDED NECK TO SUIT INSULATION THICKNESS.
6. THE DDC CONTRACTOR IS CO-RESPONSIBLE, ALONG WITH THE TAB CONTRACTOR FOR COORDINATING THE PROPER INSTALLATION OF WELLS, PRESSURE TAPS, AND P/T TAPS IN ALL LOCATIONS INDICATED AND OTHERWISE AS REQUIRED FOR A COMPLETE AND FULLY FUNCTIONAL SYSTEM.
7. THE DDC CONTRACTOR AND THE TAB CONTRACTOR SHALL UTILIZE P/T'S TO CALIBRATE INSTRUMENTS TO CERTIFIED PRESSURE GAGES, PRESSURE METERS AND THERMOMETERS.
8. CONDUIT SHALL BE RUN PERPENDICULAR AND PARALLEL TO BUILDING LINES IN A FIRST CLASS WORKMANSHIP LIKE MANNER.
9. NEW CONTROLLERS SHALL TIE INTO EXISTING TRANE SYSTEM. 1

# BACnet MONITORED SYSTEMS

DIVISION 26 SYSTEMS

THE DDC SHALL MONITOR SYSTEM CONTROLLERS BY OTHERS THROUGH A FACTORY BACnet INTERFACE. THE DDC SHALL READ AND IDENTIFY ALL POINTS TRANSMITTED BY THE FACTORY CONTROLLER. THE DDC SHALL INCLUDE A SYSTEM GRAPHIC FOR EACH CONTROLLED DEVICE WITH BACnet ADJUSTABLE SET POINTS IDENTIFIED AND ADJUSTABLE FROM THE GRAPHIC. THE FOLLOWING SYSTEMS ARE TO BE INCLUDED:

LIGHTING CONTROL PANEL

COORDINATE WITH THE EQUIPMENT AND CONTROLLERS PROVIDED BY OTHERS.

# SEQUENCE OF OPERATION
# SINGLE DUCT TERMINAL UNIT

EACH TERMINAL UNIT SHALL BE PROVIDED WITH A UNIT CONTROL MODULE (UCM). THE UCM SHALL BE FIELD OR FACTORY MOUNTED. THE ELECTRICAL CONTRACTOR SHALL PROVIDE 120V POWER TO EACH TERMINAL UNIT. PROVIDE 120V TO 24V CONTROLS TRANSFORMER FOR EACH TU.

UNIT AIRFLOW SHALL BE MONITORED BY AN INTEGRAL, MULTIPLE POINT, AVERAGING FLOW SENSING DEVICE AND A TRANSDUCER TO MAINTAIN AIRFLOW WITHIN 5% OF RATED CFM DOWN TO A MINIMUM CFM AS SCHEDULED, INDEPENDENT OF CHANGES IN SYSTEM STATIC PRESSURE.

COOLING MODE: THE UCM SHALL MONITOR THE ZONE TEMPERATURE AGAINST ITS SET POINT (74°F ADJUSTABLE) AND MODULATE THE DAMPER TO MEET THE ZONE SETPOINT. IF THE TU CALLS FOR FULL COOLING AND CANNOT REACH MAXIMUM AIRFLOW FOR FIVE MINUTES, THE DDC SHALL RESET THE AHU STATIC PRESSURE UP 0.1".


HEATING MODE: THE HOT WATER VALVE SHALL MODULATE AS REQUIRED TO MAINTAIN SPACE TEMPERATURE (COOLING SETPOINT MINUS 3°F). THE MAXIMUM HEATING AIR TEMPERATURE SHALL BE 85°F. UPON REACHING THE MAXIMUM HEATING AIR TEMPERATURE, THE DDC SHALL INCREASE THE TERMINAL UNIT AIRFLOW AND MAINTAIN THE DISCHARGE AIR TEMPERATURE OF 85°F UNTIL THE CALL FOR HEATING IS SATISFIED. WHEN THE CALL FOR HEATING IS SATISFIED, THE DDC SHALL REVERSE THE SEQUENCE AS REQUIRED TO MAINTAIN SPACE TEMPERATURE AT SETPOINT.

THE ZONE TEMPERATURE SENSOR WITH SET POINT ADJUSTMENT SHALL BE PROVIDED WITH NIGHT SETBACK OVERRIDE, AND A COMMUNICATIONS JACK. UPPER AND LOWER ZONE TEMPERATURE SET POINTS SHALL BE SET BY THE DDC.

OCCUPIED/UNOCCUPIED MODE: CONTROLS CONTRACTOR SHALL CONSULT WITH OWNER FOR SPACE TEMPERATURE SETPOINTS.

OVERRIDE MODE: THE OVERRIDE TIMER SHALL PLACE THE TU AND AHU IN OCCUPIED MODE FOR ONE HOUR (ADJUSTABLE).

ION SENSOR: TU-2-2-11 SHALL BE EQUIPPED WITH A SUPPLY AIR MOUNTED ION SENSOR WITH ADJUSTABLE SETPOINT AND ANALOG INPUT. THE DDC SHALL POST AN ALARM WHEN THE ION COUNT FALLS BELOW THE SETPOINT. INITIAL SETPOINT MINIMUM SHALL BE 5000 IONS/CC/SEC. DUCT SETPOINT SHALL BE CONFIRMED BY SPACE ION MEASUREMENTS AT A MINIMUM OF 2000 IONS/CC/SEC IN THE SPACE SERVED.




1 SINGLE DUCT TU CONTROL DIAGRAM
M4.0.1 SCALE: NONE

## SINGLE DUCT TU POINTS LIST

| SYSTEM POINT DESCRIPTION | ANALOG INPUT: GRAPHIC | ANALOG INPUT: TEMPERATURE | ANALOG INPUT: PERCENT | ANALOG INPUT: CFM | ANALOG INPUT: ION COUNT | ANALOG OUTPUT: DDC | ANALOG OUTPUT: VARIABLE FREQ. DRIVE | ANALOG OUTPUT: SETPOINT ADJ. | DIGITAL INPUT: PNEU. TRANSDUCER | DIGITAL INPUT: STATUS ON/OFF | DIGITAL INPUT: FILTER STATUS | DIGITAL INPUT: SMOKE | DIGITAL OUTPUT: START/STOP | DIGITAL OUTPUT: LOCK CLOSE | DIGITAL OUTPUT: ENABLE/DISABLE | DIGITAL OUTPUT: RH/DEHUM | SYSTEM FEATURES: ALARMS: HIGH ANALOG | SYSTEM FEATURES: ALARMS: LOW ANALOG | SYSTEM FEATURES: ALARMS: SENSOR FAIL | SYSTEM FEATURES: ALARMS: CLOSURE FAIL | SYSTEM FEATURES: ALARMS: DIGITAL | SYSTEM FEATURES: ALARMS: LATCHING | SYSTEM FEATURES: PROGRAMS: TIME SCHEDULING | SYSTEM FEATURES: PROGRAMS: RUN TIME | SYSTEM FEATURES: PROGRAMS: TIMED OVERRIDE | SYSTEM FEATURES: PROGRAMS: MODE CONTROL | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CONTROL PANEL | | | | | | | | | | | | | | | | | | | X | X | X | X | X | X | X | | | |
| SUPPLY AIR TO SPACE | | X | | | X | | | | | | | | | | | | | X | X | X | | | | | | | | |
| ZONE TEMPERATURE | | X | | | | | | X | | | | | | | | | | X | X | X | | | | | | | | |
| DAMPER | | | | | | X | | | | | | | | | | | | | | | | | | | | | | |
| FLOW SENSOR | | | | X | | | | | | | | | | | | | | | | | X | | | | | | | |

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

**NORTH TERMINAL EXPANSION / IMPROVEMENTS**

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

**HVAC CONTROLS**

SHEET NUMBER

**M4.0.1**




WATFORD ENGINEERING
850.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061

5/9/2022 5:05:19 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2020)/2021-061_ECP Terminal Expansion Mechanical.rvt

# LEGEND

| | | |
|---|---|---|
| ——— | S or W | SOIL OR WASTE PIPING |
| — — — — | V | VENT PIPING |
| —— – —— | CW | COLD WATER SUPPLY PIPING |
| — – – — | HW | HOT WATER SUPPLY PIPING |
| —— - - —— | HWR | HOT WATER RETURN PIPING |
| — · · — | TW | TEMPERED WATER PIPING (85°F) |
| ——G—— | G | GAS PIPING |
| | GV | GATE VALVE |
| | CV | CHECK VALVE |
| | BV | BALL VALVE |
| | HB | HOSE BIBB |
| | WH | WALL HYDRANT |
| | CO | CLEANOUT TO FLOOR |
| | FD | FLOOR DRAIN |
| | FD | FLOOR DRAIN WITH TRAP PRIMER CONNECTION |
| | COTG | CLEANOUT TO GRADE |
| | | UNION |
| | VTR | VENT THRU ROOF |
| 1 | | SHEET NOTE |
| | | POINT OF CONNECTION TO EXISTING |
| S | | SOLENOID VALVE |
| | SS | SERVICE SINK |
| | WC | WATER CLOSET |
| | TP | TRAP PRIMER |
| | EWH | ELECTRIC WATER HEATER |
| | WHA | WATER HAMMER ARRESTOR TYPE A |
| | WHB | WATER HAMMER ARRESTOR TYPE B |
| | WHC | WATER HAMMER ARRESTOR TYPE C |
| | L | LAVATORY |
| | UR | URINAL |
| | KW | KILOWATT |
| | TCV | THERMOSTATIC CONTROL VALVE |
| | (E) | EXISTING |
| | (M) | INDICATES MECHANICAL EQUIPMENT, REFER TO MECHANICAL DRAWINGS. |
| | (C) | INDICATES CIVIL EQUIPMENT, REFER TO CIVIL DRAWINGS. |

# GENERAL NOTES

1. COORDINATE ALL PIPING WITH DUCTWORK SHOP DRAWINGS AND EXISTING CONDITIONS. ROUTE PIPING AS REQUIRED TO AVOID CONFLICTS.
2. PRIOR TO START OF ANY WORK, COORDINATE SANITARY SEWER AND POTABLE WATER PIPING WITH EXISTING SITE UTILITIES. REPORT ANY CONFLICT WITH ARCHITECT.
3. FIELD VERIFY PIPE INVERTS PRIOR TO LAYING OUT SANITARY SEWER PIPING. COORDINATE WITH EXISTING CONDITIONS.
4. ALL PIPING PASSING THROUGH ANY WALL SHALL HAVE A SLEEVE PER SPECIFICATIONS.
5. ALL PIPING PASSING THROUGH FIRE-RATED WALLS SHALL HAVE A FIRE-RATED SLEEVE PER SPECIFICATIONS. ALL PIPING PENETRATIONS THROUGH WALLS OR FLOORS SHALL BE SEALED TO EQUAL THE RATING OF THE WALLS OR FLOORS.
6. ALL PIPING INDICATED IS ABOVE THE CEILING EXCEPT THE OBVIOUS SANITARY SOIL, WASTE, VENT AND POTABLE WATER PIPING BELOW FLOOR OR GRADE.
7. COORDINATE EXACT LOCATION OF ALL EXTERIOR WALL HYDRANTS WITH ARCHITECTURAL DRAWINGS.
8. UNDER SLAB SOIL, WASTE AND VENT PIPING PASSING TO UNDERSIDE OR THROUGH FOUNDATION FOOTING, WALL OR GRADE BEAM SHALL BE PROVIDED WITH A RELIEVING ARCH OR PIPE SLEEVE 2 (TWO) PIPE SIZES GREATER THAN PIPE SIZE INDICATED ON PLANS. COORDINATE FINAL PIPE ROUTING AND LAYOUT WITH STRUCTURAL DRAWINGS.
9. PRIOR TO SUBSTANTIAL COMPLETION OF NEW AND ALTERED WORK AREAS, CONTRACTOR SHALL HAVE SANITARY PLUMBING SYSTEM CLEARED OF DEBRIS OR ANY MATTER THAT WOULD INTERFERE OR PREVENT ADEQUATE CONVEYANCE OF MATERIALS FROM MOVING THROUGH AND TERMINATING INTO BUILDING OR PUBLIC DISPOSAL FACILITIES.
10. ALL (VTR'S) VENT THRU ROOF PENETRATIONS INDICATED ON PLANS ARE PRELIMINARY. FINAL LOCATIONS SHALL BE COORDINATED WITH ALL TRADES. ALL VTR'S SHALL BE A MINIMUM OF 10'-0" FROM ALL FRESH AIR INTAKE OPENINGS.
11. ALL TRAP PRIMERS AND DOMESTIC WATER ISOLATION VALVES SHALL BE ACCESSIBLE. TRAP PRIMERS LOCATED IN THE VICINITY OF WATER CLOSETS SHALL BE ACTIVATED BY WATER CLOSET USAGE. ISOLATION VALVES SHALL BE OF THE QUARTER TURN BALL OR GATE TYPE.
12. CONTRACTOR SHALL DEVELOP AND SUBMIT COORDINATION SHOP DRAWINGS WHICH IDENTIFY ROUTING OF PLUMBING PIPE AND LOCATION OF EQUIPMENT. SHOP DRAWINGS SHALL INDICATE COORDINATION WITH THE WORK OF OTHER TRADES.
13. ALL WORK SHALL COMPLY WITH THE FLORIDA BUILDING CODE 7TH EDITION (2020) PLUMBING.


# PLUMBING FIXTURE SCHEDULE

| MARK | FIXTURE | PIPE SIZE-INCHES | | | | REMARKS |
|---|---|---|---|---|---|---|
| | | CW | HW | TW | W | |
| WC-1 | WATER CLOSET (ADULT HANDICAP,ELECTRONIC) | 1 | - | - | 3 | WALL MOUNT, HANDICAP HEIGHT @ 18", ELONGATED BOWL, 1.5" TOP SPUD, ELECTRONIC FLUSH VALVE, 1.28 GPF |
| WC-2 | WATER CLOSET (CHILD HANDICAP,ELECTRONIC) | 1 | - | - | 3 | WALL MOUNT STANDARD HEIGHT @ 15", ELONGATED BOWL, 1.5" TOP SPUD, ELECTRONIC FLUSH VALVE, 1.28 GPF |
| L-1 | LAVATORY (ADULT HANDICAP, 20"x18" COUNTERTOP) | 3/8 | - | 3/8 | 1-1/4 | WALL MOUNT, CHAIR CARRIER, VITREOUS CHINA, CENTER HOLE, INSULATION KIT, DRAIN, P-TRAP, ANGLE STOPS & FLEXIBLE RISERS, FAUCET, MIXING VALVE |
| L-2 | LAVATORY (STANDARD, 20"x18" COUNTERTOP) | 3/8 | - | 3/8 | 1-1/4 | DROP-IN COUNTERTOP MOUNT, STAINLESS STEEL, CENTER HOLE, INSULATION KIT, DRAIN, P-TRAP, ANGLE STOPS & FLEXIBLE RISERS, CAST BRASS FAUCET, MIXING VALVE, ELECTRONIC |
| UR-1 | URINAL (HANDICAP, ELECTRONIC) | 3/4 | - | - | - | WALL MOUNT, CHAIR CARRIER, CONCEALED 0.5 GPF ELECTRONIC FLUSH VALVE, 1/2" REAR SPUD, COORDINATE WITH ARCHITECTURAL DRAWINGS |
| UR-2 | URINAL (STANDARD, ELECTRONIC) | 3/4 | - | - | - | WALL MOUNT, CHAIR CARRIER, CONCEALED 0.5 GPF ELECTRONIC FLUSH VALVE, 1/2" REAR SPUD, COORDINATE WITH ARCHITECTURAL DRAWINGS |
| MR-1 | MOP RECEPTOR (24"x24"x12") | 1/2 | 1/2 | - | 3 | FLOOR TYPE, NEO-CORNER, TERRAZZO, 8" CENTERS, TOP BRACE FAUCET WITH INTEGRAL STOPS, STRAIGHT LEVER HANDLES, VACUUM BREAKER, RIM GUARD, MOP HANGER |
| EWC-1 | ELECTRIC WATER COOLER (BI-LEVEL) | 1/2 | - | - | 1-1/4 | WALL MOUNTED, CHAIR CARRIER, DUAL LEVEL, SELF CONTAINED, STAINLESS STEEL, PUSH BAR |
| TCV | TEMPERATURE CONTROL VALVE | - | 1/2 | - | - | SELF-ACTING THERMOSTAT RECIRCULATION VALVE SET AT 110 DEGREES F. |
| FD | FLOOR DRAIN | 1/2 | - | - | 3 | DEEP SEAL, TRAP PRIMER CONNECTION |
| MV-1 | WATER MIXING VALVE | 1/2 | 1/2 | 1/2 | - | BRONZE, EXPOSED WALL MOUNTED,VACUUM BREAKER, 0.5-3.5 GPM |
| TP-1 | TRAP PRIMER | 1/2 | - | - | - | PPP MODEL MP-500 ELECTRONIC SOLENOID TRAP PRIMER WITH DISTRIBUTION MANIFOLD, INTEGRAL VACUUM BREAKER, QUARTER TURN BALL ISOLATION VALVE, AND MINIMUM ELEVATION 12" AFF |

1. WATER SUPPLY TAPPING TO EACH PLUMBING FIXTURE SHALL BE FULL SIZE (MINIMUM)
2. SEE ELECTRICAL DWGS FOR FINAL POWER REQUIREMENTS.
3. PROVIDE WATER HAMMER ARRESTERS ON HOT & COLD WATER SUPPLY BRANCHES SERVING SINGULAR, MULTIPLE OR GROUPS OF PLUMBING FIXTURES. ADHERENCE TO THE PLUMBING AND DRAINAGE INSTITUTE STANDARD P.D.I.-WH201 (PER SPECIFICATIONS) SHALL BE EMPLOYED IN DETERMINING PROPER SIZE, SELECTION, PLACEMENT, LOCATION AND INSTALLATION OF ARRESTERS.

1. A FOUNDATION MAY BE REQUIRED IN VERY POOR SOIL CONDITIONS.
2. BEDDING IS REQUIRED PRIMARILY TO BRING THE TRENCH BOTTOM UP TO GRADE. BEDDING MATERIALS SHALL PROVIDE A UNIFORM AND ADEQUATE LONGITUDINAL SUPPORT UNDER THE PIPE. IN DRY SOIL CONDITIONS, CLASS II OR III MATERIAL SHALL BE HAND PLACED IN 4-6", LIGHTLY COMPACTED UNIFORM AND NOT FINER THAN THE FOUNDATION MATERIAL. IN WET CONDITIONS, CLASS I, II OR III MATERIAL SHALL BE HAND PLACED IN 4-6", UNIFORM AND NOT FINER THAN THE FOUNDATION MATERIAL. WHEN UTILIZING CLASS I MATERIAL, SUFFICIENT AMOUNTS OF CLASS II OR III MATERIAL SHALL BE ADDED TO FILL ALL VOIDS CREATED BY THE USE OF CLASS I MATERIAL.
3. HAUNCHING MATERIAL SHALL BE HAND PLACED TO THE SPRINGLINE OF THE PIPE. CLASS II OR III MATERIAL SHALL BE CONSOLIDATED UNDER THE PIPE AND HAND TAMPED TO PROVIDE ADEQUATE SIDE SUPPORT.
4. INITIAL BACKFILL MATERIAL SHALL BE CLASS II OR III. IT SHALL BE PLACED WITHIN 24-30" ABOVE THE TOP OF THE PIPE AND TAMPED BY A PORTABLE VIBRATOR. FINAL BACKFILL MATERIAL MAY BE MACHINE PLACED. THE MATERIAL SHALL BE CLASS II OR III MATERIAL. CLASS IV MATERIAL MAY BE INSTALLED OUTSIDE OF ROADWAY.
5. FINAL BACKFILL UNDER ROADWAYS MAY REQUIRE SPECIAL COMPACTION AND DENSITY TESTS. A MINIMUM OF 30" OF COVER OVER THE TOP OF THE PIPE SHALL BE PROVIDED BEFORE THE TRENCH IS WHEEL- LOADED.

NOTE:
ALL EMBEDMENT MATERIALS SHALL BE NO LESS THAN 95% OF MAXIMUM DENSITY. LABORATORY TESTING OF THE SOIL WILL BE REQUIRED. THIS PROCEDURE SHALL BE REQUIRED ON ALL INSTALLATIONS. ALL TRENCHING, EXCAVATION, AND BACKFILLING SHALL BE IN ACCORDANCE WITH 2020 FLORIDA PLUMBING CODE.




EMBEDMENT MATERIALS

CLASS I: ANGULAR, 1/4"-1-1/2", GRADED STONE, INCLUDING A NUMBER OF FILL MATERIALS THAT HAVE REGIONAL SIGNIFICANCE SUCH AS CORAL, SLAG, CINDERS, CRUSHED STONE AND CRUSHED SHELLS.


CLASS II: COARSE SANDS AND GRAVELS WITH MAXIMUM PARTICLE SIZE OF 1-1/2" INCLUDING VARIOUS GRADED SANDS AND GRAVELS CONTAINING SMALL PERCENTAGES OF FINES, GENERALLY GRANULAR AND NON-COHESIVE, EITHER WET OR DRY. SOIL TYPES GW, GP, SW, AND SP ARE INCLUDED IN THIS CLASS.

CLASS III: FINE SAND AND CLAY GRAVELS, INCLUDING FINE SANDS, SAND-CLAY MIXTURES AND GRAVEL-CLAY MIXTURES. SOIL TYPES GM, GC, SM, AND SC ARE INCLUDED IN THIS CLASS.


CLASS IV: SILT, SILTY CLAYS, AND CLAYS, INCLUDING INORGANIC CLAYS AND SILT OF MEDIUM TO HIGH PLASTICITY AND LIQUID LIMITS. SOIL TYPES MH, ML, CH, AND CL ARE INCLUDED IN THIS CLASS. THESE MATERIALS ARE NOT TO BE USED FOR BEDDING, HAUNCHING, OR INITIAL BACKFILL.

CLASS V: THIS CLASS INCLUDES THE ORGANIC SOILS, AS WELL AS SOILS CONTAINING FROZEN EARTH, DEBRIS, ROCKS LARGER THAN 1-1/2" IN DIAMETER AND OTHER FOREIGN MATERIALS. THESE MATERIALS ARE NOT TO BE USED FOR BEDDING, HAUNCHING, OR INITIAL BACKFILL.


## 1 EXCAVATION AND BACKFILL DETAIL
P0.0.1 SCALE:NONE




## 2 TRAP PRIMER DETAIL
P0.0.1 SCALE:NONE




## 3 UNDER SINK MIXING VALVE DETAIL
P0.0.1 SCALE:NONE





WATFORD ENGINEERING
860.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27525
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061



© 2018 All reproduction & intellectual property rights reserved.



FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| | | |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W Bay Pkwy,**
**Panama City, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**PLUMBING LEGEND, SCHEDULE, DETAILS, AND NOTES**

SHEET NUMBER

**P0.0.1**



5/9/2022 9:14:39 AM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Plumbing.rvt

## GENERAL NOTES

1. PRIOR TO BEGINNING DEMOLITION CONTRACTOR SHALL COORDINATE WITH ARCHITECT ANY PHASING AND INSTRUCTIONS FOR TEMPORARY LOSS OF SERVICES TO THE EXISTING BUILDING INCLUDING BUT NOT LIMITED TO EXISTING RESTROOMS, BREAKROOMS, ETC.
2. CONTRACTOR SHALL CORE DRILL EXISTING CONCRETE SLAB AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS.
3. COORDINATE WITH GENERAL CONTRACTOR LIMITS OF ANY CEILING OR SOFFIT AT FIRST AND SECOND FLOORS TO BE REMOVED AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS. REPLACE TO MATCH EXISTING.

## SHEET NOTES


1. REMOVE EXISTING SINK AND INSTANTANEOUS WATER HEATER. CAP SANITARY BELOW SLAB AND CAP WATER ABOVE CEILING.
2. REMOVE ALL EXISTING PLUMBING FIXTURES IN ROOMS TO BE DEMOLISHED. CAP SANITARY, DOMESTIC WATER, AND VENT PIPING BELOW SLAB OR ABOVE CEILING AS NECESSARY.




## PLUMBING DEMOLITION PLAN - LEVEL 2

SCALE: 1/8" = 1'-0"

TRUE NORTH / PROJECT NORTH





WATFORD ENGINEERING
850.526.3447
4402 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27925
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061



© 2018 All reproduction & intellectual property rights reserved.



FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/22 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W Bay Pkwy,**
**Panama City, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**PLUMBING DEMOLITION PLAN - LEVEL 2**

SHEET NUMBER

**P1.0.1**


5/9/2022 9:14:42 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Plumbing.rvt





TRUE NORTH / PROJECT NORTH

1 / P2.0.1 PLUMBING NEW WORK PLAN - LEVEL 1

SCALE: 1/8" = 1'-0"

## GENERAL NOTES

1. PRIOR TO BEGINNING DEMOLITION CONTRACTOR SHALL COORDINATE WITH ARCHITECT ANY PHASING AND INSTRUCTIONS FOR TEMPORARY LOSS OF SERVICES TO THE EXISTING BUILDING INCLUDING BUT NOT LIMITED TO EXISTING RESTROOMS, BREAKROOMS, ETC.
2. CONTRACTOR SHALL CORE DRILL EXISTING SECOND FLOOR SLAB AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS.
3. CONTRACTOR SHALL SAW CUT EXISTING FIRST FLOOR CONCRETE SLAB AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS. PATCH TO MATCH EXISTING.
4. COORDINATE WITH GENERAL CONTRACTOR LIMITS OF ANY CEILING OR SOFFIT AT FIRST AND SECOND FLOORS TO BE REMOVED AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS. REPLACE TO MATCH EXISTING.




WATFORD ENGINEERING
850.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/22 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W Bay Pkwy,**
**Panama City, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

## PLUMBING NEW WORK PLAN - LEVEL 1


SHEET NUMBER

# P2.0.1

5/9/2022 9:14:44 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Plumbing.rvt

## GENERAL NOTES

1. PRIOR TO BEGINNING DEMOLITION CONTRACTOR SHALL COORDINATE WITH ARCHITECT ANY PHASING AND INSTRUCTIONS FOR TEMPORARY LOSS OF SERVICES TO THE EXISTING BUILDING INCLUDING BUT NOT LIMITED TO EXISTING RESTROOMS, BREAKROOMS, ETC.
2. CONTRACTOR SHALL CORE DRILL EXISTING CONCRETE SLAB AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS.
3. COORDINATE WITH GENERAL CONTRACTOR LIMITS OF ANY CEILING OR SOFFIT AT FIRST AND SECOND FLOORS TO BE REMOVED AS REQUIRED TO INSTALL NEW PLUMBING SYSTEMS. REPLACE TO MATCH EXISTING.




1 PLUMBING NEW WORK PLAN - LEVEL 2
P2.0.2 SCALE: 1/8" = 1'-0"

TRUE PROJECT

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 05/10/22 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W Bay Pkwy,**
**Panama City, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

## PLUMBING NEW WORK PLAN - LEVEL 2


SHEET NUMBER

# P2.0.2





WATFORD ENGINEERING
850.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27925
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061

5/9/2022 9:14:51 AM BIM 360://21021 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Plumbing.rvt




1 P3.0.1 **SOIL WASTE AND VENT RISER DIAGRAM**
SCALE:NONE




2 P3.0.1 **DOMESTIC WATER RISER DIAGRAM**
SCALE:NONE

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W Bay Pkwy,**
**Panama City, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

## PLUMBING RISER DIAGRAMS

SHEET NUMBER

# P3.0.1




WATFORD ENGINEERING
850.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061

5/9/2022 9:14:51 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Plumbing.rvt

## CONTROLS

| | |
|---|---|
| S | WALL SWITCH ; 120/277V; 20A; 1 POLE; A.C. ONLY; MT 48" AFF TO C/L |
| $S_3$ | WALL SWITCH; 120/277V; 20A; 3 WAY; A.C. ONLY; MT 48" AFF TO C/L; HUBBELL SERIES HBL1223 |
| $S_4$ | WALL SWITCH; 120/277V; 20A; 4 WAY; A.C. ONLY; MT 48" AFF TO C/L; HUBBELL SERIES HBL1224 |
| $S_M$ | WALL SWITCH; 120/277V; 20A; OCCUPANCY SENSOR DUAL TECHNOLOGY MULTI-WAY TYPE; MT 48" AFF TO C/L; REFER TO SPECS |
| $S_{LV}$ | LOW VOLTAGE WALL SWITCH; MT 48" AFF TO C/L; REFER TO SPECS; SEE LIGHTING CONTROL DETAILS |
| MS | MOTOR CONTROL SWITCH; 120V; 30A; 2 POLE; A.C. ONLY; NEAR OR ON EQUIPMENT BEING SERVED; HUBBELL SERIES HBL7832D. |
| WP MS | NEMA 3R MOTOR CONTROL SWITCH; 120V; 30A; 2 POLE; A.C. ONLY; NEAR OR ON EQUIPMENT BEING SERVED; HUBBELL SERIES HBL13R22D. |
| | RED MUSHROOM PUSH-BUTTON WITH KEY RELEASE; MT. 60" AFF TO C/L. LABEL 'EMERGENCY STOP', EQUAL TO SQUARE D MODEL X86AS9345B |
| P | OCCUPANCY SENSOR POWER PACK; MOUNT ABOVE CEILING |
| RP | OCCUPANCY SENSOR RECEPTACLE POWER PACK; MOUNT ABOVE CEILING |
| | LOW VOLTAGE VACANCY SENSOR; 360° DUAL-TECHNOLOGY TYPE; CEILING MOUNTED |
| | LOW VOLTAGE DAYLIGHT SENSOR; 360° DUAL-TECHNOLOGY TYPE; CEILING MOUNTED |

## LIGHTING

| | |
|---|---|
| | CEILING FIXTURE |
| | WALL BRACKET FIXTURE |
| | POLE MOUNTED FIXTURE |
| | 2' X 2' TROFFER FIXTURE; ARROW INDICATES LAMP DIRECTION; SEE SCHEDULE FOR MOUNT TYPE |
| | 2' X 2' TROFFER FIXTURE WITH SELF CONTAINED EMERGENCY BALLAST; ARROW INDICATES LAMP DIRECTION; SEE SCHEDULE FOR MOUNT TYPE |
| | TROFFER FIXTURE; SEE SCHEDULE FOR MOUNT TYPE |
| | TROFFER FIXTURE WITH SELF CONTAINED EMERGENCY BALLAST; SEE SCHEDULE FOR MOUNT TYPE |
| | STRIP FIXTURE; SHADING INDICATES EMERGENCY BALLAST |
| | TWIN HEAD EMERGENCY BATTERY UNIT |
| | EXIT SIGN; CEILING MOUNTED; ARROWS AS NOTED; SHADED SECTION INDICATES LIGHTED FACE OF EXIT SIGN |
| | EXIT SIGN; BACK MOUNTED; ARROWS AS NOTED; SHADED SECTION INDICATES LIGHTED FACE OF EXIT SIGN |

## MISCELLANEOUS SYSTEMS

| | |
|---|---|
| | TELEPHONE WALL OUTLET WITH MODULAR JACK AND COVERPLATE; MT 18" AFF TO C/L UNLESS NOTED OTHERWISE - INSTALL 3/4"C WITH PULLRIBBON UP INTO CEILING SPACE. |
| | DATA SYSTEM WALL OUTLET WITH TWO(2) RJ-45 JACKS AND COVERPLATE; MT 18" AFF TO C/L UNLESS NOTED OTHERWISE - INSTALL 3/4"C WITH PULLRIBBON UP INTO CABLE TRAY RACEWAY OR ATTIC WHERE APPLICABLE. ALL CONDUIT SHALL BE CONCEALED. |
| | DATA SYSTEM FLOOR OUTLET WITH TWO(2) RJ-45 JACKS AND COVERPLATE; HUBBELL SERIES B-2536; AND S-3925 COVER WITH CARPET FLANGE - INSTALL 3/4"C WITH PULLRIBBON UP INTO CABLE TRAY RACEWAY OR ATTIC WHERE APPLICABLE. ALL CONDUIT SHALL BE CONCEALED. |
| | DATA SYSTEM CEILING OUTLET WITH TWO RJ-45 JACKS AND COVERPLATE. |
| F | FIRE ALARM SYSTEM MANUAL PULL STATION; MT 48" AFF TO C/L |
| | FIRE ALARM SYSTEM SIGNAL SPEAKER/STROBE; MT 80" AFF TO BOTTOM, '110' INDICATES CANDELA RATING, NO NUMBER INDICATES 75 CANDELA MINIMUM |
| WP | FIRE ALARM SYSTEM EXTERIOR, WEATHERPROOF SIGNAL SPEAKER; MT 90" AFF TO BOTTOM |
| | FIRE ALARM SYSTEM STROBE; MT 80" AFF TO BOTTOM, '110' INDICATES CANDELA RATING, NO NUMBER INDICATES 75 CANDELA MINIMUM |
| H | FIRE ALARM SYSTEM AUTOMATIC HEAT DETECTOR; 135 DEGREE/RATE OF RISE TYPE; CEILING MOUNTED |
| | FIRE ALARM SYSTEM AUTOMATIC SMOKE DETECTOR; CEILING MOUNTED |
| | FIRE ALARM SYSTEM AUTOMATIC AIR DUCT SMOKE DETECTOR |
| P | PHOTOCELL; TORK MODEL 2101 (120V) OR 2104 (277V) |
| | DIGITAL TIMESWITCH WITH RESERVE POWER; REFER TO LIGHTING CONTROL DIAGRAM FOR TYPE |
| | SECURITY CAMERA; PROVIDE JUNCTION BOX AND 3/4" CONDUIT WITH PULL RIBBON TO ATTIC SPACE FOR SECURITY CAMERA. COORDINATE WITH SECURITY CONTRACTOR. |

## NOTE DESIGNATIONS

| | |
|---|---|
| ? | KEY NOTE REFERENCE |
| ⚠ | DEMO NOTE REFERENCE |
| ? | FEEDER OR PARTS REFERENCE. SEE SCHEDULE |

## POWER DISTRIBUTION

| | |
|---|---|
| | SURFACE MOUNTED PANELBOARD; 120/208V; MT 72" AFF TO TOP |
| | FLUSH MOUNTED PANELBOARD; 120/208V; MT 72" AFF TO TOP |
| T | DRY TYPE TRANSFORMER; SIZE AND RATING AS NOTED |
| | DISCONNECT SWITCH; AMP SIZE AS NOTED; |
| | FUSED DISCONNECT SWITCH; AMP SIZE AS NOTED; FUSE SIZE PER EQUIPMENT NAMEPLATE DATA |
| M | MOTOR; FURNISHED BY OTHERS |
| J | JUNCTION BOX; MOUNTED ABOVE CEILING |
| J | JUNCTION BOX; MOUNTED FLUSH IN WALL WITH BLANK COVER |

## RACEWAYS

| | |
|---|---|
| | CONDUIT CAP |
| UP | CONDUIT TURNED UP |
| DN | CONDUIT TURNED DOWN |
| | RACEWAY INSTALLED CONCEALED IN WALLS AND/OR ABOVE CEILING |
| | RACEWAY INSTALLED CONCEALED IN FLOOR SLAB AND/OR BELOW GRADE |
| | RACEWAY INSTALLED EXPOSED |
| | FLEXIBLE CONDUIT CONNECTION |
| | CONDUIT STUB UP WITH FLEXIBLE CONDUIT CONNECTION TO EQUIPMENT |


## WIRE DESIGNATIONS

| | |
|---|---|
| A-1 'B' | A-1 ADJACENT TO ARROW INDICATES HOMERUN OF CIRCUIT NO. 1 TO PANEL A; "B" INDICATES FIXTURE TYPE; MARKS ACCROSS RACEWAY RUN INDICATES THE NUMBER OF NO. 12 CONDUCTORS; UNLESS NOTED OTHERWISE NO MARKS INDICATES TWO NO.12 CONDUCTORS AND ONE NO. 12 GREEN GROUND CONDUCTOR IN 1/2" CONDUIT (2#12 & 1#12 GND-1/2"C) |
| | TICK MARKS REPRESENT WIRE COUNT AS INDICATED. EACH TICK MARK REPRESENTS 1 PHASE CONDUCTOR AND/OR GROUNDED (NEUTRAL) CONDUCTOR. DOTTED TICK MARK REPRESENTS EQUIPMENT GROUNDING CONDUCTOR. UNLESS NOTED OTHERWISE, NO MARKS INDICATES TWO NO. 12 CONDUCTORS AND ONE NO. 12 GREEN GROUND CONDUCTOR IN 1/2" CONDUIT (2 #12 & 1#12 GND-1/2"C) |

## RECEPTACLES

| CLG | FLOOR | WALL | |
|---|---|---|---|
| | | | DUPLEX RECEPTACLE, 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES HBL5352 |
| | | | QUAD - 2 DUPLEX RECEPTACLE, 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES HBL5352 |
| | | | DUPLEX GFCI RECEPTACLE, 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES GF5362 |
| | | | TAMPER-RESISTANT DUPLEX RECEPTACLE, 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES BR20TxxTR |
| | | | TAMPER-RESISTANT DUPLEX GFCI RECEPTACLE, 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES GFTR20 |
| | | | SPD DUPLEX RECEPTACLE, 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES HBL5362SA |
| | | | HALF-CONTROLLED RECEPTACLE; 125V, 20A; NEMA 5-20R; HUBBELL SERIES BR20C1 |
| | | | HALF-CONTROLLED QUAD - 2 DUPLEX RECEPTACLE; 125 V, 20 A; NEMA 5-20R; HUBBELL SERIES HBL5352 |
| | | | SPECIAL TYPE RECEPTACLE 'X' DENOTES NEMA TYPE A = 250V, 30A, 2P, 2W, NEMA L6-30R; HUBBELL SERIES HBL2620 |

| DESIGNATIONS | |
|---|---|
| WP | LETTERS "WP" ADJACENT TO SYMBOL INDICATES RECEPTACLE WITH WEATHERPROOF COVER; PASS AND SEYMOUR WIUFC10S COVER/BOX. |
| +XX | LETTERS +XX" ADJACENT TO SYMBOL INDICATES RECEPTACLE MOUNTING HEIGHT. WHEN NO HEIGHT IS INDICATED, MOUNT 18" AFF.<br>•AC" = ABOVE COUNTER.<br>•DF" = VERIFY HEIGHT FOR DRINKING FOUNTAIN WITH CONTRACTOR<br>•TV" = VERIFY HEIGHT OF TV WITH OWNER. |




DISCONNECT SWITCH NOMENCLATURE

NTS

## GENERAL NOTES

A. CONTRACTOR SHALL COORDINATE ALL WORK WITH OTHER TRADES PRIOR TO INSTALLATION. REFER TO MECHANICAL AND PLUMBING DRAWINGS FOR EXACT SIZE AND LOCATION OF EQUIPMENT WHICH IS FURNISHED BY OTHERS AND CONNECTED BY ELECTRICAL.
B. RECEPTACLES, SWITCHES AND COVERPLATES COLOR SHALL BE SELECTED BY THE ARCHITECT FROM STANDARD COLORS.
C. VERIFY ALL DOOR SWINGS WITH ARCHITECTURAL DRAWINGS PRIOR TO ROUGHING-IN WALL FOR SWITCHES.
D. LOCATION OF LIGHTING FIXTURES, DISCONNECT SWITCHES, ETC. FOR MECHANICAL EQUIPMENT/ROOM SHALL BE COORDINATED WITH FINAL MECHANICAL EQUIPMENT LOCATION TO PROVIDE NATIONAL ELECTRIC CODE REQUIRED ACCESS SPACE.
E. FINAL CONNECTION TO ALL MOTORS SHALL BE WITH FLEXIBLE CONDUIT CONNECTION.
F. ALL EXIT AND EMERGENCY FIXTURES SHALL BE CONNECTED TO LIGHT CIRCUIT AHEAD OF LOCAL SWITCH.
G. ALL PANELBOARDS, BACKBOARDS, TERMINAL CABINETS, ETC SHALL HAVE CUSTOM ENGRAVED MICARTA NAMEPLATE MECHANICALLY AFFIXED IDENTIFYING SYSTEM.
H. PROVIDE GREEN GROUND CONDUCTOR IN ALL CIRCUITS - SIZE PER N.E.C.
I. ALL EXPOSED CONDUITS, BOXES, STRAPS AND HANGERS IN THE CONTRACT AREA WHETHER NEW OR EXISTING THAT ARE PART OF THE ELECTRICAL SYSTEM SHALL BE PAINTED TO MATCH ADJACENT FINISH.
J. PROVIDE CONCRETE MARKER AT END OF ALL CONDUITS STUBBED OUT OF BUILDING FOR FUTURE USE. MARKER SHALL BE 6" DIA X 18" HIGH WITH 2" ABOVE FINISHED GRADE. INSCRIBE IN TOP OF MARKER "E" FOR ELECTRICAL,"T" FOR TELEPHONE,"V" FOR TV CABLE,"F" FOR FIRE ALARM, AND "IC" FOR INTERCOM.
K. GENERAL CONTRACTOR SHALL FIELD-VERIFY ALL EXISTING CONDITIONS PRIOR TO BEGINNING ANY WORK, AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT OF ANY DISCREPANCIES. FAILURE TO DO SO INDICATES THAT THE CONTRACTOR ACCEPTS THE CONDITIONS AS THEY EXIST, AND SHALL PERFORM THE WORK REQUIRED AS SHOWN AND SPECIFIED.
L. THE ELECTRICAL CONTRACTOR SHALL OBTAIN AND REVIEW THE MECHANICAL AND SPECIAL EQUIPMENT SUBMITTALS PRIOR TO SUBMITTING THE ELECTRICAL SUBMITTALS. ANY ELECTRICAL EQUIPMENT, CONDUIT, AND WIRE SIZE CHANGES RESULTING FROM THIS REVIEW SHALL ALSO BE SUBMITTED FOR APPROVAL.
M. FIRE ALARM LOW VOLTAGE SOURCE AND BATTERY STANDBY SHALL ENERGIZE ALL ITEMS IN FIRE ALARM SYSTEM THAT REQUIRE POWER.
N. VERIFY EXACT LOCATION OF ALL FLOOR OUTLETS WITH THE ARCHITECT PRIOR TO ROUGHING-IN.
O. FINAL CONNECTION TO ALL DRY TYPE TRANSFORMERS SHALL BE WITH FLEXIBLE CONDUIT CONNECTION
P. THE ELECTRICAL CONTRACTOR SHALL PROVIDE FAULT CURRENT CALCULATIONS FOR THE SERVICE EQUIPMENT AND SHALL MARK THE EQUIPMENT WITH THE AVAILABLE FAULT CURRENT AND DATE OF THE CALCULATION PER NEC 110.24. REFER TO TYPICAL SERVICE EQUIPMENT FAULT CURRENT LABEL DETAIL.
Q. THE ELECTRICAL CONTRACTOR SHALL PROVIDE ARC FAULT LABELS PER NFPA 70E ARTICLE 110.16 FOR NEW EQUIPMENT. THE OWNER SHALL PROVIDE AVAILABLE CALCULATION DATA FOR THE EXISTING EQUIPMENT IN THE ELECTRICAL SYSTEM. REFER TO TYPICAL ARC FLASH HAZARD LABEL DETAIL.
R. PROVIDE NEUTRAL AT ALL LINE VOLTAGE SWITCH LOCATIONS PER N.E.C. 404.2(C).

## ABBREVIATIONS

| | | |
|---|---|---|
| 1P | - | ONE POLE |
| 2P | - | TWO POLE |
| 3P | - | THREE POLE |
| 4P | - | FOUR POLE |
| A | - | AMPERE |
| AC | - | ALTERNATING CURRENT |
| AFF | - | ABOVE FINISHED FLOOR |
| AFG | - | ABOVE FINISHED FLOOR |
| AHU | - | AIR HANDLING UNIT |
| AIC | - | AMPERE INTERRUPTING CAPACITY |
| AL | - | ALUMINUM |
| ARCH | - | ARCHITECT |
| AWG | - | AMERICAN WIRE GAUGE |
| BLDG | - | BUILDING |
| C | - | CONDUIT |
| CB | - | CIRCUIT BREAKER |
| CKT | - | CIRCUIT |
| C.T. | - | CURRENT TRANSFORMER |
| CU | - | COPPER |
| DC | - | DIRECT CURRENT |
| DISC | - | DISCONNECT |
| DN | - | DOWN |
| DWG | - | DRAWING |
| EC | - | ELECTRICAL CONTRACTOR |
| EF | - | EXHAUST FAN |
| ELEC | - | ELECTRICAL |
| EWC | - | ELECTRIC WATER COOLER |
| FA | - | FIRE ALARM |
| FLA | - | FULL LOAD AMPS |
| FLEX | - | FLEXIBLE |
| FURN | - | FURNITURE |
| GC | - | GENERAL CONTRACTOR |
| GFCI | - | GROUND FAULT CIRCUIT INTERRUPTER |
| GND | - | GROUNDED |
| HP | - | HORSEPOWER |
| HVAC | - | HEATING, VENTILATION AND AIR CONDITIONING |
| HZ | - | HERTZ (CYCLE) PER SECOND |
| JB | - | JUNCTION BOX |
| KCMIL | - | THOUSAND CIRCULAR MILS |
| KVA | - | KILOVOLT AMPERE |
| KW | - | KILOWATT |
| LTG | - | LIGHTING |
| LV | - | LOW VOLTAGE |
| MCB | - | MAIN CIRCUIT BREAKER |
| MLO | - | MAIN LUGS ONLY |
| MTD | - | MOUNTED |
| MTG | - | MOUNTING |
| NEC | - | NATIONAL ELECTRICAL CODE |
| ϕ | - | PHASE |
| PNL | - | PANELBOARD |
| PRI | - | PRIMARY |
| RTU | - | ROOFTOP UNIT |
| SEC | - | SECONDARY |
| U | | USB RECEPTACLE |
| SW | - | SWITCH |
| UG | - | UNDERGROUND |
| V | - | VOLT |
| W | - | WATT |
| XFMR | - | TRANSFORMER |
| +72 | - | MOUNTING HEIGHT IN INCHES TO CENTERLINE ABOVE FINISHED FLOOR OR GRADE |

SHEET INDEX



| SHEET NUMBER | SHEET NAME |
|---|---|
| E-001 | LEGEND AND NOTES |
| E-101 | DEMOLITION ELECTRICAL PLAN - FIRST FLOOR |
| E-102 | DEMOLITION ELECTRICAL PLAN - SECOND FLOOR |
| E-201 | NEW LIGHTING PLAN - FIRST FLOOR |
| E-202 | NEW POWER PLAN - SECOND FLOOR |
| E-203 | NEW LIGHTING PLAN- SECOND FLOOR |
| E-204 | NEW HVAC POWER PLAN - SECOND FLOOR |
| E-205 | NEW FIRE ALARM PLAN - SECOND FLOOR |
| E-301 | LIGHTING FIXTURE SCHEDULE AND CONTROLS |
| E-401 | ELECTRICAL DETAILS |
| E-501 | PANEL SCHEDULES |




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782



© 2018 All reproduction & intellectual property rights reserved.



FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

**LEGEND AND NOTES**


SHEET NUMBER

# E-001


2022-05-09 4:30:10 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\210186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

## KEYNOTES

| KEY VALUE | KEYNOTE TEXT |
|---|---|
| 1 | TEMPORARILY REMOVE AND REPLACE POWER TO DOORS. RECONNECT TO PROVIDE FULLY OPERATIONAL SYSTEM. |
| 2 | REFER TO 'SECOND FLOOR DEMO PLAN - ELECTRICAL' FOR DEMO WORK IN THIS AREA. |
| 3 | COORDINATE EXTENTS OF DEMOLITION WORK TO BE DONE IN THIS AREA WITH GENERAL CONTRACTOR. TEMPORARILY REMOVE AND REPLACE ELECTRICAL DEVICES AND PROVISIONS AS NEEDED UNLESS OTHERWISE NOTED. |
| 4 | TEMPORARILY REMOVE AND REPLACE EXISTING LIGHTING IN EXIT LANE. COORDINATE REMOVAL AND RECONNECTION WITH GENERAL CONTRACTOR. |
| 5 | TEMPORARILY REMOVE AND REPLACE EXISTING ALL ELECTRICAL DEVICES, FIRE ALARM DEVICES AND LIGHTING CONTROLS DEVICES. COORDINATE REMOVAL AND RECONNECTION WITH GENERAL CONTRACTOR. |




DEMO ELECTRICAL PLAN - FIRST FLOOR

1/8" = 1'-0"

HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

***DEMOLITION ELECTRICAL PLAN - FIRST FLOOR***


SHEET NUMBER

**E-101**

2022-05-09 4:30:12 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt


## KEYNOTES

| KEY VALUE | KEYNOTE TEXT |
|---|---|
| 1 | ALL ELECTRICAL PANELBOARDS AND EQUIPMENT IN THIS ROOM ARE EXISTING TO REMAIN UNLESS NOTED OTHERWISE. |
| 2 | DEMO AND REMOVE EXISTING FIRE ALARM DEVICE IN IT'S ENTIRETY. EXTEND EXISTING CONDUIT AND CONDUCTORS AS NEEDED TO MAINTAIN CIRCUIT CONTINUITY. |
| 3 | DEMO AND REMOVE EXISTING ELECTRICAL DEVICE IN IT'S ENTIRETY. EXTEND EXISTING CONDUIT AND CONDUCTORS AS NEEDED TO MAINTAIN CIRCUIT CONTINUITY. |
| 4 | EXISTING FIRE ALARM DEVICE TO REAMIN. |
| 5 | DEMO AND REMOVE EXISTING LIGHT FIXTURE AND ASSOCIATED CIRCUIT AND CONTROLS IN THEIR ENTIRETY. |
| 6 | EXISTING ELECTRICAL DEVICE TO REMAIN. |
| 7 | RELOCATE EXISTING FIRE ALARM DEVICE |
| 8 | COORDINATE EXTENTS OF DEMOLITION/REMOVAL OF FIXTURES AND ELECTRICAL DEVICES WITH GENERAL CONTRACTOR IN THIS AREA. RELOCATE AND RECONNECT FIXTURES AS NEEDED. |




DEMO ELECTRICAL PLAN - SECOND FLOOR

1/8" = 1'-0"




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

***DEMOLITION ELECTRICAL PLAN - SECOND FLOOR***


SHEET NUMBER

# E-102

2022-05-09 4:30:16 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt


## KEYNOTES

| KEY VALUE | KEYNOTE TEXT |
|---|---|
| 1 | RECONNECT TO EXISTING NORMAL LIGHTING RELAY PANEL SERVING THIS AREA. |
| 2 | RECONNECT TO EXISTING LIFE SAFETY RELAY PANEL SERVING THIS AREA. |
| 3 | CONNECT TO EXISTING NON-SWITCHED PORTION OF NEAREST LIGHTING CIRCUIT. |
| 4 | TEMPORARILY REMOVE AND REINSTALL ALL EXISTING LIGHTING FIXTURES SERVING EXIT LANE. FIELD VERIFY LOCATIONS OF EXISTING EMERGENCY LIGHT FIXTURE AND REINSTALL IN SAME LOCATION. |




NEW LIGHTING PLAN - FIRST FLOOR

1/8" = 1'-0"




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garlick; FL. PE No.53924;
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

***NEW LIGHTING PLAN - FIRST FLOOR***


SHEET NUMBER

# E-201


2022-05-09 4:30:19 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

## KEYNOTES

| KEY VALUE | KEYNOTE TEXT |
|---|---|
| 1 | JUNCTION BOX FOR ELECTRIC HAND DRYER. |
| 2 | INSTALL TWO (2) 2" CONDUIT WITH PULL STRING BACK TO ELEC RM 2100 FOR FUTURE CONCESSION EXPANSION. STUB UP CONDUIT AND CAP. |
| 3 | JUNCTION BOX FOR DOOR ACCESS CONTROL. PROVIDE 120V POWER AND AN ADDITIONAL 1" CONDUIT WITH PULLSTRING UP INTO ACCESSIBLE CEILING SPACE FOR CONTROLS. COORDINATE REQUIREMENTS, INCLUDING CONDUIT ROUGH-IN WITH ACCESS CONTROL CONTRACTOR. |
| 4 | ALL ELECTRICAL PANELBOARDS AND EQUIPMENT IN THIS ROOM ARE EXISTING TO REMAIN UNLESS NOTED OTHERWISE. |
| 5 | EXISTING ELECTRICAL DEVICE TO REMAIN. |
| 6 | FOR POKE-THRU DEVICES, ROUTE CONDUITS ABOVE FIRST FLOOR CEILING SPACE BACK TO ELECTRIC ROOM. COORDINATE TEMPORARY REMOVAL AND REPLACEMENT OF SUSPENDED CEILING AS REQUIRED. |




ENLARGED COMM ROOM
1/4" = 1'-0"





PARTIAL POWER LINE RISER
NTS

FLOOR BOX NOTES:
1. POWER ONLY FLOOR BOX SHALL BE FIRE RATED POKE-THRU EQUAL TO HUBBELL #S1PTAL WITH ALUMINUM COVER PLATE. PROVIDE TWO HUBBELL DUPLEX DECORA RECEPTACLES.
2. POWER/DATA FLOOR BOX SHALL BE FIRE RATED POKE-THRU EQUAL TO HUBBELL #S1R6PTACEHALU WITH ALUMINUM COVER AND 4-20A PRE-WIRED RECEPTACLES.
3. COORDINATE AND PROVIDE CORE DRILLING FOR POKE-THRU DEVICES AS REQUIRED.




NEW POWER PLAN - SECOND FLOOR
1/8" = 1'-0"




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO. 2186
Christopher A. Garick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

PANAMA CITY AIRPORT NWFBIA:

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 W BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE


**NEW POWER PLAN - SECOND FLOOR**

SHEET NUMBER

# E-202


2022-05-09 4:30:41 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

| KEYNOTES | |
|---|---|
| KEY VALUE | KEYNOTE TEXT |
| 1 | ALL ELECTRICAL PANELBOARDS AND EQUIPMENT IN THIS ROOM ARE EXISTING TO REMAIN UNLESS NOTED OTHERWISE. |
| 2 | COORDINATE EXTENTS OF DEMOLITION/REMOVAL OF FIXTURES AND ELECTRICAL DEVICES WITH GENERAL CONTRACTOR IN THIS AREA. RELOCATE AND RECONNECT FIXTURES AS NEEDED. |
| 3 | CONNECT TO EXISTING EMERGENCY EMERGENCY LIFE SAFETY LIGHTING CIRCUIT SERVING THIS ROOM. |
| 4 | CONNECT TO EXISTING NORMAL LIGHTING CIRCUIT SERVING THIS AREA. |
| 5 | CONNECT VIA EMERGENCY LIFE SAFETY LIGHTING CONTROL PANEL LCP-2AE. REFER TO EMERGENCY LIFE SAFETY LIGHTING CONTROL PANEL SCHEDULES FOR SPECIFIC RELAY #. |
| 6 | CONNECT VIA NORMAL LIGHTING CONTROL PANEL LCP-2A. REFER TO LIGHTING CONTROL PANEL SCHEDULES FOR SPECIFIC RELAY #. |




NEW LIGHTING PLAN - SECOND FLOOR

1/8" = 1'-0"




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garlick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

**NEW LIGHTING PLAN- SECOND FLOOR**

SHEET NUMBER

# E-203

2022-05-09 4:30:44 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt


# MECHANICAL EQUIPMENT SCHEDULE

(VERIFY ALL EQUIPMENT CIRCUIT REQUIREMENTS WITH MANUFACTURERS SHOP DRAWINGS PRIOR TO ROUGH-IN)

| EQUIPMENT DESIGNAITON | DESCRIPTION | CFM | VOLT | Φ | ELECTRICAL LOAD | | | | | | PROTECTION | | | | CONDUCTOR / CONDUIT SIZE | | | | | DISC. | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | MOTOR(S) FLA | | | | | | | | SPECIFIED | | SETS | CONDUCTORS | | | | | |
| | | | | | QTY | LARGEST | SUM OF REMAINING | ELECTRIC HEAT KW | OTHER VA | TOTAL CONNECTED VA | MCA | MOCP | TRIP | POLE | | QTY. | SIZE | GND | CONDUIT | | |
| EF-1 | EXHAUST FAN | 790 | 120 | 1 | 1 | 4.75 | | | | 570 | 5.9 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | INTERLOCK WITH AHU-2-2(E) OA DAMPER |
| MHP-1 | MINI-SPLIT OUTDOOR UNIT | | 208 | 1 | 1 | 10 | | | | 2080 | 14 | 15 | 15 | 2 | 1 | 3 | #12 | #12 | 3/4" | 30/2/3R | |
| VAV-2-2-10 | VARIABLE VOLUME UNIT | 340 | 277 | 1 | | | | 1 | | 1000 | 4.5 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-11 | VARIABLE VOLUME UNIT | 360 | 277 | 1 | | | | 1 | | 1000 | 4.5 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-12 | VARIABLE VOLUME UNIT | 340 | 277 | 1 | | | | 1 | | 1000 | 4.5 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-2 | VARIABLE VOLUME UNIT | 1250 | 480 | 3 | | | | 4 | | 4000 | 6 | 15 | 15 | 3 | 1 | 4 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-6 | VARIABLE VOLUME UNIT | 1730 | 480 | 3 | | | | 5 | | 5000 | 7.5 | 15 | 15 | 3 | 1 | 4 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-7 | VARIABLE VOLUME UNIT | 1725 | 480 | 3 | | | | 5 | | 5000 | 7.5 | 15 | 15 | 3 | 1 | 4 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-8 | VARIABLE VOLUME UNIT | 355 | 277 | 1 | | | | 1 | | 1000 | 4.5 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| VAV-2-2-9 | VARIABLE VOLUME UNIT | 335 | 277 | 1 | | | | 1 | | 1000 | 4.5 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | |
| WM-1 | MINI-SPLIT INDOOR UNIT | 646 | 208 | | 1 | 0.67 | | | | 139 | 1 | 15 | 15 | 2 | 1 | 3 | #12 | #12 | 3/4" | MOTOR SWITCH | INTERLOCK WITH OUTDOOR UNIT MHP-1 |
| | BI-POLAR IONIZATION | | 120 | 1 | 1 | 0.12 | | | | 14 | 0.2 | 15 | 15 | 1 | 1 | 2 | #12 | #12 | 3/4" | MOTOR SWITCH | INTERLOCK WITH AHU-2-2(E) |


## KEYNOTES

| KEY VALUE | KEYNOTE TEXT |
|---|---|
| 1 | LABEL VAV SWITCH AS DISCONNECTING MEANS IN SEQUENTIAL ORDER |




NEW HVAC POWER PLAN - SECOND FLOOR

1/8" = 1'-0"




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garcia; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE


**NEW HVAC POWER PLAN - SECOND FLOOR**

SHEET NUMBER


# E-204

2022-05-09 4:30:49 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

| KEYNOTES | |
|---|---|
| KEY VALUE | KEYNOTE TEXT |
| 1 | ALL ELECTRICAL PANELBOARDS AND EQUIPMENT IN THIS ROOM ARE EXISTING TO REMAIN UNLESS NOTED OTHERWISE. |
| 2 | EXISTING FIRE ALARM DEVICE TO REAMIN. |




NEW FIRE ALARM PLAN - SECOND FLOOR
1/8" = 1'-0"




HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-4723
FL. AUTH NO. 00006860
PROJECT NO: 2186
Christopher A. Garick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

***NEW FIRE ALARM PLAN - SECOND FLOOR***

SHEET NUMBER

# E-205

2022-05-09 4:31:10 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

# Lighting Fixture Schedule

| TYPE | MANUFACTURER | CATALOG NUMBER | CONNECTED VOLTAGE | LUMINAIRE LOAD (VA) | LAMPING SOURCE | COLOR RENDER INDEX (CRI) | KELVIN TEMPERATURE | MOUNTING | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|
| D | HE WILLIAMS | PXF-46-12'-L4/840-G-LCAP/RCAP-DR V | 277 V | 48 VA | LED | 80 | 4000 | SURFACE MOUNT ABOVE VANITY COVE | LINEAR SURFACE MOUNT RAIL VANITY FIXTURE |
| H1 | METALUMEN | S6-1L40K-4-MB-B-L4-1-DF-UNV | 277 V | 48 VA | LED | 80 | 4000 | CEILING SLOT RECESSED | 4' LINEAR RECESSED SLOT FIXTURE |
| H1E | METALUMEN | S6-1L40K-4-MB-B-L4-1-DF-UNV | 277 V | 48 VA | LED | 80 | 4000 | CEILING SLOT RECESSED | 4' LINEAR RECESSED SLOT FIXTURE (EMERGENCY CIRCUIT) |
| L22 | HE WILLIAMS | LT-24-L27/840-AF-DRV-UNV | 277 V | 22 VA | LED | 80 | 4000 | GRID LAY-IN | 2'X2' LED LAY-IN TROFFER |
| L22E | HE WILLIAMS | LT-24-L27/840-AF-DRV-UNV | 277 V | 22 VA | LED | 80 | 4000 | GRID LAY-IN | 2'X2' LED LAY-IN TROFFER (EMERGENCY CIRCUIT) |
| LF | BEGHELLI | BS100LED-4-HT-VLO-WT40-120-277V -JM-WHT | 277 V | 30 VA | LED | 80 | 4000 | SURFACECEILING SURFACE MOUNT | 4' LINEAR SURFACE MOUNT |
| LFE | BEGHELLI | BS100LED-4-SA-VLO-WT40-120-277V -JM-WHT | 277 V | 30 VA | LED | 80 | 4000 | SURFACECEILING SURFACE MOUNT | 4' LINEAR SURFACE MOUNT (EMERGENCY CIRCUIT) |
| P1 | HE WILLIAMS | 6DR-TL-L10/840-DIM-UNV-OW-OF-CS -1 | 277 V | 9 VA | LED | 80 | 4000 | CEILING RECESSED | 6" ROUND RECESSED DOWNLIGHT |
| P1E | HE WILLIAMS | 6DR-TL-L10/840-DIM-UNV-OW-OF-CS -N | 277 V | 9 VA | LED | 80 | 4000 | CEILING RECESSED | 6" ROUND RECESSED DOWNLIGHT (EMERGENCY CIRCUIT) |
| P3 | HE WILLIAMS | 6DR-TL-L15/840-DIM-UNV-OW-OF-CS -N | 277 V | 19 VA | LED | 80 | 4000 | CEILING RECESSED | 6" ROUND RECESSED DOWNLIGHT |
| P3E | HE WILLIAMS | 6DR-TL-L20/840-DIM-UNV-OW-OF-CS -N | 277 V | 19 VA | LED | 80 | 4000 | CEILING RECESSED | 6" ROUND RECESSED DOWNLIGHT (EMERGENCY CIRCUIT) |
| SF | BEGHELLI | BS100LED-4-HT-VLO-WT40-120-277V -JM-WHT | 277 V | 30 VA | LED | 80 | 4000 | SURFACECEILING SURFACE MOUNT | 4' LINEAR SURFACE MOUNT |
| SFE | BEGHELLI | BS100LED-4-HT-VLO-WT40-120-277V -JM-WHT | 277 V | 30 VA | LED | 80 | 4000 | SURFACECEILING SURFACE MOUNT | 4' LINEAR SURFACE MOUNT (EMERGENCY CIRCUIT) |
| X | HE WILLIAMS | EXIT-R-AC-WHT-SDT-D | 277 V | 3 VA | LED | | | WALL MOUNT ABOVE DOOR (UNIVERSAL) | WALL MOUNT EXIT SIGN (EMERGENCY CIRCUIT) |
| XC | HE WILLIAMS | EXIT-R-AC-WHT-SDT-D | 277 V | 3 VA | LED | | | LED CEILING MOUNT EXIT SIGN (UNIVERSAL) | CEILING MOUNT |

## EXISTING LIGHTING CONTROL PANEL - NORMAL POWER

**PANEL RP-2AN**

**VOLTAGE:** 277/480V **SUPPLY PANEL:** PANEL HLS2A **MOUNTING:** SURFACE
**PANEL:** LUTRON SOFTSWITCH128 XPS8-FT
**NEMA RATING** 1 **OPTIONS:** N/A **LOCATION** ELECTRICAL RM 2101


| RELAY | LOAD (VA) | LINE FEED | SERVING | VOLTAGE | VOLTAGE | SERVING | LINE FEED | LOAD (VA) | RELAY |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | | DEPATURE HALL | 277V | 277V | DEPARTURE HALL | | | 2 |
| 3 | | | SKYLIGHT | 277V | 277V | SKYLIGHT | | | 4 |
| 5 | | | USO | 277V | 277V | CONCOURSE, TICKETING, BOARDING, LOUNGE | H2A-4 | 1990 | 6 |
| 7 | 180 | H2A-2 | FUTURE CONCESSION SPACE | 277V | 277V | MENS RR, WOMENS RR | H2A-6 | 414 | 8 |

## EXISTING LIGHTING CONTROL PANEL - EMERGENCY POWER

**PANEL RP-2AE**

**VOLTAGE:** 277/480V **SUPPLY PANEL:** PANEL H2A **MOUNTING:** SURFACE
**PANEL:** LUTRON SOFTSWITCH128 XPS8-FT
**NEMA RATING** 1 **OPTIONS:** N/A **LOCATION** ELECTRICAL RM 2101

| RELAY | LOAD (VA) | LINE FEED | SERVING | VOLTAGE | VOLTAGE | SERVING | LINE FEED | LOAD (VA) | RELAY |
|---|---|---|---|---|---|---|---|---|---|
| 1 | | | DEPARTURE HALL | 277V | 277V | DEPARTURE HALL | | | 2 |
| 3 | | | STAIRWELL, LOBBY 2115 | 277V | 277V | ADD ALT PRIMARY PROCESSING | | | 4 |
| 5 | | | ADD ALT CORRIDOR | 277V | 277V | CONCOURSE, TICKETING, BOARDING, LOUNGE | H2A-4 | 1269 | 6 |
| 7 | 180 | HLS2A-4 | FUTURE CONCESSION SPACE | 277V | 277V | MENS RR, WOMENS RR | HLS2A-3 | 90 | 8 |




## KEYNOTES

- RJ45 DIGITAL BUS CONNECTORS ARE LOCATED ON EVERY DIGITAL DEVICE (DIGITAL DEVICES ARE DEFINED AS: RELAY PANELS, DIGITAL SWITCHES AND ALL DIGITAL ACCESSORIES).
- RJ45 CONNECTORS USE THE SAME COLOR CODING AS ETHERNET AND ARE MADE AS STRAIGHT THROUGH CABLES. CROSS OVER CABLES WILL CAUSE SYSTEM FAILURE. ALL CABLES SUPPLIED BY CONTRACTOR.

## NOTES


1. DAISY-CHAIN CAT. 5 PATCH CABLE WITH RJ45 CONNECTORS FROM DIGITAL DEVICE TO DIGITAL DEVICE.
2. REFER TO MANUFACTURERS INSTRUCTIONS FOR LONG DISTANCE RUNS BETWEEN DIGITAL DEVICES.
3. UP TO 4,000 FT TOTAL BUS LENGTH
4. CRIMP AND TEST EACH CABLE WITH A LAN CIRCUIT TESTER PRIOR TO INSTALLATION.

## TYPICAL LOW VOLTAGE NETWORK HOOK UP

NTS

## GR 2404-DIM

WIRING DETAIL





## KEYNOTES

- MANUAL SWITCH BUTTONS FOR RAISE/LOWER AND THREE SCENES.
- OCCUPANCY SENSOR INPUTS. TYPICAL OF 4. WILL OPERATE WITH ANY LOW VOLTAGE OCCUPANCY SENSOR THAT OUTPUTS DRY CONTACT. POWER SUPPLY OUT FOR 12V OR 24V SENSORS. 3#18 AWAG SHIELDED.
- PHOTOCELL INPUTS. TYPICAL OF 4. SPECIFY LUMEN MAINTENANCE PHOTOCELL (LMPC). DIMMERS MAY BE ENABLE TO FOLLOW PHOTOCELL INPUTS. PROGRAMMING SHALL BE DONE FROM A DTC IN THE MASTER RELAY PANEL OR FROM A DESKTOP COMPUTER. LOCALLY OR REMOTELY 5#18AWG.
- MATRIXABLE CONTACT CLOSURE OR ANALOG INPUTS FOR RAISE LOWER, ON/OFF OR SCENE CONTROL.
- LIGHTING RELAYS: N/C, ZERO CROSS, 20A, 277V (TUNGSTEN, BALLAST, HID) AND INCLUDE 1 DIMMED OUTPUT PER RELAY.

## MICRO PANEL WIRING DETAIL

NTS




## LIGHTING CONTROLS RISER DIAGRAM

NTS

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE


***LIGHTING FIXTURE SCHEDULE AND CONTROLS***

SHEET NUMBER

**E-301**


HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garlick; FL. PE No:53924
Thomas A. Alexander; FL- PE No.73172
Daniel J. White; FL:-PE No.73790
Caleb W. Leonard; FL. PE No.91782

2022-05-09 4:31:16 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt





## Arc Flash Hazard Label

NTS





## Electrical Equipment Nameplate

NTS





## Elect Equip Nameplate - Above Ceiling

NTS





## Panel Clearance

NTS





## Service Equipment Fault Current Label

NTS




## Existing Building Conduit Entry

NTS





TYPICAL POWER OUTLET INSTALLATION

TYPICAL POWER/COMMUNICATIONS OUTLET INSTALLATION

## Outlet Installation

NTS





FIVE SIDED ELECTRICAL BOX

ADJACENT ELECTRICAL BOXES

## Wall Details - Electrical Box Installations

NTS




WITH OUTLET BOX

WITHOUT OUTLET BOX

EXPOSED OR FEEDER CONDUIT

## PVC Stub-Up Details

NTS

1

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

***ELECTRICAL DETAILS***

SHEET NUMBER

**E-401**

HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garick; FL. PE No.53924
Thomas A. Alexander; FL. PE No.73172
Daniel J. White; FL. PE No.73790
Caleb W. Leonard; FL. PE No.91782

2022-05-09 4:31:19 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

EXISTING POWER PANEL

## H2A

**MAIN** 225 A MLO
**SYSTEM** 480Y/277V 3P 4W
**OPTIONS** BOLT ON BREAKERS

**A.I.C. RATING** 22 KVA
**NEMA** NEMA 1

**LOCATION** ELEC. 2101
**MOUNTING** Surface

**LOAD PER PHASE**

| CKT | CIRCUIT DESCRIPTION | TRIP | POLES | A | | B | | C | | POLES | TRIP | CIRCUIT DESCRIPTION | CKT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | LTG | 20 A | 1 | 1300 VA | 180 VA | | | | | 1 | 20 A | LTG - FUTURE CONCESSION SPACE | 2 |
| 3 | LTG | 20 A | 1 | | | 1000 VA | 1860 VA | | | 1 | 20 A | LTG - CONCOURSE, TICKETING, BOARDING, LOUNGE | 4 |
| 5 | LTG | 20 A | 1 | | | | | 1500 VA | 248 VA | 1 | 20 A | LTG-GENERAL MEN 2116 | 6 |
| 7 | LTG | 20 A | 1 | 2100 VA | 2500 VA | | | | | 1 | 20 A | LTG | 8 |
| 9 | LTG | 20 A | 1 | | | 600 VA | 2000 VA | | | 1 | 20 A | LTG | 10 |
| 11 | LTG | 20 A | 1 | | | | | 600 VA | 0 VA | 1 | 20 A | SPARE | 12 |
| 13 | LTG - STORAGE RM 2104 | 20 A | 1 | 30 VA | 0 VA | | | | | 1 | 20 A | SPARE | 14 |
| 15 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 16 |
| 17 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 18 |
| 19 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 20 |
| 21 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 22 |
| 23 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 24 |
| 25 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 26 |
| 27 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 28 |
| 29 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 30 |
| 31 | | | | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 32 |
| 33 | T-L2A | 110 A | 3 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 34 |
| 35 | | | | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 36 |
| 37 | | | | 0 VA | 0 VA | | | | | | | | 38 |
| 39 | TVSS | 30 A | 3 | | | 0 VA | 0 VA | | | 3 | 20 A | SPARE | 40 |
| 41 | | | | | | | | 0 VA | 0 VA | | | | 42 |
| | | POWER/PHASE | | 6110 VA | | 5460 VA | | 2348 VA | | | | | |
| | | AMPS/PHASE | | 24 A | | 21 A | | 8 A | | | | | |

| LOAD CLASS | CONNECTED LOAD | DEMAND FACTOR | DEMAND LOAD | TOTALS |
|---|---|---|---|---|
| Lighting - General | 229 VA | 100.00% | 229 VA | **CONNECTED POWER** 13918 VA |
| Other | 0 VA | 0.00% | 0 VA | **DEMAND POWER** 13918 VA |
| Spare | 11600 VA | 100.00% | 11600 VA | **CONNECTED AMPS** 17 A |
| LTG-GENERAL | 2089 VA | 100.00% | 2089 VA | **DEMAND AMPS** 17 A |

**NOTES:**

EXISTING POWER PANEL

## L2A

**MAIN** 225 A MCB
**SYSTEM** 208Y/120V 3P 4W
**OPTIONS** BOLT ON BREAKERS; TWO EQUAL SECTIONS

**A.I.C. RATING** 10kA
**NEMA** NEMA 1

**LOCATION** ELEC. 2101
**MOUNTING** Surface

**LOAD PER PHASE**

| CKT | CIRCUIT DESCRIPTION | TRIP | POLES | A | | B | | C | | POLES | TRIP | CIRCUIT DESCRIPTION | CKT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | | | | 0 VA | 1500 VA | | | | | 1 | 20 A | HAND DRYER | 2 |
| 3 | TVSS | 30 A | 3 | | | 0 VA | 1500 VA | | | 1 | 20 A | HAND DRYER | 4 |
| 5 | | | | | | | | 0 VA | 1500 VA | 1 | 20 A | HAND DRYER | 6 |
| 7 | HAND DRYER | 20 A | 1 | 1500 VA | 1500 VA | | | | | 1 | 20 A | HAND DRYER | 8 |
| 9 | HAND DRYER | 20 A | 1 | | | 1500 VA | 1500 VA | | | 1 | 20 A | HAND DRYER | 10 |
| 11 | HAND DRYER | 20 A | 1 | | | | | 1500 VA | 1500 VA | 1 | 20 A | HAND DRYER | 12 |
| 13 | REC-LOUNGE | 20 A | 1 | 720 VA | 720 VA | | | | | 1 | 20 A | REC-LOUNGE | 14 |
| 15 | REC- CONCOURSE WAITING AREA | 20 A | 1 | | | 1080 VA | 1080 VA | | | 1 | 20 A | REC- CONCOURSE WAITING AREA | 16 |
| 17 | REC-DRINKING FOUNTAIN | 20 A | 1 | | | | | 180 VA | 720 VA | 1 | 20 A | REC- TOILET 2115, FAMILY 2114 | 18 |
| 19 | REC- LOUNGE | 20 A | 1 | 1080 VA | 1080 VA | | | | | 1 | 20 A | REC-CONCOURSE WAITING | 20 |
| 21 | INST. WATER HEATER | 20 A | 2 | | | 3100 VA | 180 VA | | | 1 | 20 A | REC-VESTIBULE | 22 |
| 23 | | | | | | | | 3100 VA | 720 VA | 1 | 20 A | REC- LOUNGE | 24 |
| 25 | REC | 20 A | 1 | 1400 VA | 900 VA | | | | | 1 | 20 A | REC | 26 |
| 27 | REC | 20 A | 1 | | | 1200 VA | 1000 VA | | | 1 | 20 A | REC | 28 |
| 29 | REC CEILING PROJECTOR | 20 A | 1 | | | | | 1100 VA | 200 VA | 1 | 20 A | ELECTRONIC TRAP PRIMER | 30 |
| 31 | REC | 20 A | 1 | 1200 VA | 1000 VA | | | | | 1 | 20 A | REC | 32 |
| 33 | REC | 20 A | 1 | | | 200 VA | 1500 VA | | | 1 | 20 A | REC HAND DRYER | 34 |
| 35 | REC | 20 A | 1 | | | | | 200 VA | 1500 VA | 1 | 20 A | REC HAND DRYER | 36 |
| 37 | REC | 20 A | 1 | 1400 VA | 800 VA | | | | | 1 | 20 A | REC | 38 |
| 39 | REC | 20 A | 1 | | | 1000 VA | 1200 VA | | | 1 | 20 A | REC | 40 |
| 41 | REC | 20 A | 1 | | | | | 1200 VA | 1200 VA | 1 | 20 A | F-TX-1 | 42 |
| 43 | REC HAND DRYER | 20 A | 1 | 1500 VA | 0 VA | | | | | 1 | 20 A | F-TX-5 | 44 |
| 45 | REC HAND DRYER | 20 A | 1 | | | 1500 VA | 0 VA | | | 1 | 20 A | GARBAGE DISPOSAL | 46 |
| 47 | FUTURE USO SPACE | 20 A | 1 | | | | | 1200 VA | 720 VA | 1 | 20 A | REC-CONCOURSE WAITING AREA | 48 |
| 49 | FUTURE USO SPACE | 20 A | 1 | 1200 VA | 180 VA | | | | | 1 | 20 A | REC- CONCOURSE WAITING AREA | 50 |
| 51 | FUTURE USO SPACE | 20 A | 1 | | | 1200 VA | 720 VA | | | 1 | 20 A | REC- CONCOURSE WAITING AREA | 52 |
| 53 | FUTURE USO SPACE | 20 A | 1 | | | | | 1200 VA | 1260 VA | 1 | 20 A | REC- CONCOURSE WAITING AREA | 54 |
| 55 | FUTURE USO SPACE | 20 A | 1 | 1200 VA | 720 VA | | | | | 1 | 20 A | REC- TOILET 2116, JAN CLOSET 2113 | 56 |
| 57 | SPAREFUTURE USO SPACE | 20 A | 1 | | | 1200 VA | 180 VA | | | 1 | 20 A | REC-DRINKING FOUNTAIN | 58 |
| 59 | REC REFRIGERATOR | 20 A | 1 | | | | | 800 VA | 540 VA | 1 | 20 A | REC-CONCOURSE WAITING AREA | 60 |
| 61 | REC COUNTER | 20 A | 1 | 1000 VA | 720 VA | | | | | 1 | 20 A | REC-CONCOURSE WAITING AREA | 62 |
| 63 | REC MICROWAVE | 20 A | 1 | | | 1000 VA | 0 VA | | | 1 | 20 A | SPARE | 64 |
| 65 | REC-CONCOURSE | 20 A | 1 | | | | | 720 VA | 0 VA | 1 | 20 A | SPARE | 66 |
| 67 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 68 |
| 69 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 70 |
| 71 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 72 |
| 73 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 74 |
| 75 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 76 |
| 77 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 78 |
| 79 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 80 |
| 81 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 82 |
| 83 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 84 |
| | | POWER/PHASE | | 21320 VA | | 21840 VA | | 21060 VA | | | | | |
| | | AMPS/PHASE | | 178 A | | 182 A | | 176 A | | | | | |

| LOAD CLASS | CONNECTED LOAD | DEMAND FACTOR | DEMAND LOAD | TOTALS |
|---|---|---|---|---|
| Spare | 37400 VA | 100.00% | 37400 VA | **CONNECTED POWER** 64220 VA |
| Equipment | 13500 VA | 100.00% | 13500 VA | **DEMAND POWER** 62560 VA |
| REC-GEN | 13320 VA | 87.54% | 11660 VA | **CONNECTED AMPS** 178 A |
| | | | | **DEMAND AMPS** 174 A |

**NOTES:**

REPLACE EXISTING POWER PANEL

## LNE2A

**MAIN** 100 A MCB
**SYSTEM** 208Y/120V 3P 4W
**OPTIONS** BOLT ON BREAKERS

**A.I.C. RATING** 10kA
**NEMA** NEMA 1

**LOCATION** ELEC. 2101
**MOUNTING** Surface

**LOAD PER PHASE**

| CKT | CIRCUIT DESCRIPTION | TRIP | POLES | A | | B | | C | | POLES | TRIP | CIRCUIT DESCRIPTION | CKT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | | | | 0 VA | 0 VA | | | | | 2 | 20 A | SPARE | 2 |
| 3 | TVSS | 30 A | 3 | | | 0 VA | 0 VA | | | | | | 4 |
| 5 | | | | | | | | 0 VA | 2150 VA | 2 | 20 A | MINI SPLIT WM-1; MHP-1 | 6 |
| 7 | DOC REC DDC | 20 A | 1 | 700 VA | 2150 VA | | | | | | | | 8 |
| 9 | REC | 20 A | 1 | | | 200 VA | 1000 VA | | | 1 | 20 A | SECURITY DOOR POWER | 10 |
| 11 | REC | 20 A | 1 | | | | | 200 VA | 360 VA | 1 | 20 A | REC- TICKETING BOOTH | 12 |
| 13 | REC | 20 A | 1 | 200 VA | 360 VA | | | | | 1 | 20 A | REC- TICKETING BOOTH | 14 |
| 15 | REC- TV TICKETING | 20 A | 1 | | | 360 VA | 360 VA | | | 1 | 20 A | REC- TV TICKETING | 16 |
| 17 | DOOR LOCKS | 20 A | 1 | | | | | 0 VA | 720 VA | 1 | 20 A | REC-COMM 2101B | 18 |
| 19 | REC-COMM 2101 | 20 A | 1 | 360 VA | 360 VA | | | | | 1 | 20 A | REC-COMM 2101B | 20 |
| 21 | JUNCTION BOX SECURITY | 20 A | 1 | | | 0 VA | 0 VA | | | 2 | 30 A | REC- COMM 2101B | 22 |
| 23 | JUNCTION BOX SECURITY | 20 A | 1 | | | | | 0 VA | 0 VA | | | | 24 |
| 25 | DOOR LOCKS | 20 A | 1 | 720 VA | 360 VA | | | | | 1 | 20 A | DOOR LOCKS | 26 |
| 27 | REC-LCD MONITOR LOUNGE | 20 A | 1 | | | 720 VA | 360 VA | | | 1 | 20 A | REC-LCD MONITOR CONCOURSE | 28 |
| 29 | REC-LCD MONITOR CONCOURSE | 20 A | 1 | | | | | 360 VA | 180 VA | 1 | 20 A | REC-LCD MONITOR CONCOURSE | 30 |
| 31 | REC-LCD MONITOR LOUNGE | 20 A | 1 | 180 VA | 360 VA | | | | | 1 | 20 A | REC-LCD MONITOR CONCOURSE | 32 |
| 33 | REC- FUTURE TELECOM CABINET | 20 A | 1 | | | 360 VA | 360 VA | | | 1 | 20 A | REC-FUTURE TELECOM CABINET | 34 |
| 35 | REC-FUTURE TELECOM CABINET | 20 A | 1 | | | | | 360 VA | 360 VA | 1 | 20 A | DOOR LOCKS | 36 |
| 37 | REC-FUTURE TELECOM CABINET | 20 A | 1 | 360 VA | 0 VA | | | | | 1 | 20 A | SPARE | 38 |
| 39 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 40 |
| 41 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 42 |
| | | POWER/PHASE | | 6110 VA | | 3720 VA | | 4690 VA | | | | | |
| | | AMPS/PHASE | | 52 A | | 31 A | | 40 A | | | | | |

| LOAD CLASS | CONNECTED LOAD | DEMAND FACTOR | DEMAND LOAD | TOTALS |
|---|---|---|---|---|
| Other | 4160 VA | 100.00% | 4160 VA | **CONNECTED POWER** 14519 VA |
| Spare | 2300 VA | 100.00% | 2300 VA | **DEMAND POWER** 14519 VA |
| Receptacle | 720 VA | 100.00% | 720 VA | **CONNECTED AMPS** 40 A |
| Equipment | 1579 VA | 100.00% | 1579 VA | **DEMAND AMPS** 40 A |
| REC-GEN | 5220 VA | 100.00% | 5220 VA | |
| REC-APP | 540 VA | 100.00% | 540 VA | |

**NOTES:**

EXISTING POWER PANEL

## HLS2A

**MAIN** 100 A MLO
**SYSTEM** 480Y/277V 3P 4W
**OPTIONS** BOLT ON BREAKERS

**A.I.C. RATING** 22 KVA
**NEMA** NEMA 1

**LOCATION** ELEC. 2101
**MOUNTING** Surface

**LOAD PER PHASE**

| CKT | CIRCUIT DESCRIPTION | TRIP | POLES | A | | B | | C | | POLES | TRIP | CIRCUIT DESCRIPTION | CKT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | LTG | 20 A | 1 | 1900 VA | 1328 VA | | | | | 1 | 20 A | LTG-GENERAL Room 258, 255, 143, 246, 245 | 2 |
| 3 | LIGHTING - GENERAL MEN 2116 | 20 A | 1 | | | 90 VA | 180 VA | | | 1 | 20 A | LIGHTING - GENERAL FUTURE CONCESSIONS-2 2108-2 | 4 |
| 5 | LIGHTING - GENERAL STOR. 2104 | 20 A | 1 | | | | | 90 VA | 0 VA | 1 | 20 A | SPARE | 6 |
| 7 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 8 |
| 9 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 10 |
| 11 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 12 |
| 13 | LTG | 20 A | 1 | 2900 VA | 0 VA | | | | | 1 | 20 A | SPARE | 14 |
| 15 | LTG | 20 A | 1 | | | 1400 VA | 0 VA | | | 1 | 20 A | SPARE | 16 |
| 17 | LTG | 20 A | 1 | | | | | 900 VA | 0 VA | 1 | 20 A | SPARE | 18 |
| 19 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 20 |
| 21 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 22 |
| 23 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 24 |
| 25 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 26 |
| 27 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 28 |
| 29 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 30 |
| 31 | | | | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 32 |
| 33 | T-LLS2A | 30 A | 3 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 34 |
| 35 | | | | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 36 |
| 37 | | | | 0 VA | 0 VA | | | | | | | | 38 |
| 39 | TVSS | 30 A | 3 | | | 0 VA | 0 VA | | | 3 | 20 A | SPARE | 40 |
| 41 | | | | | | | | 0 VA | 0 VA | | | | 42 |
| | | POWER/PHASE | | 6128 VA | | 1670 VA | | 990 VA | | | | | |
| | | AMPS/PHASE | | 23 A | | 6 A | | 4 A | | | | | |

| LOAD CLASS | CONNECTED LOAD | DEMAND FACTOR | DEMAND LOAD | TOTALS |
|---|---|---|---|---|
| Lighting - General | 534 VA | 100.00% | 534 VA | **CONNECTED POWER** 8788 VA |
| Other | 0 VA | 0.00% | 0 VA | **DEMAND POWER** 8788 VA |
| Spare | 7100 VA | 100.00% | 7100 VA | **CONNECTED AMPS** 11 A |
| LTG-GENERAL | 1154 VA | 100.00% | 1154 VA | **DEMAND AMPS** 11 A |

**NOTES:**

EXISTING POWER PANEL

## HEQ2A

**MAIN** 225 A MLO
**SYSTEM** 480Y/277V 3P 4W
**OPTIONS** BOLT ON BREAKERS; TWO EQUAL SECTIONS

**A.I.C. RATING** 22 kA
**NEMA** NEMA 1

**LOCATION** ELEC. 2101
**MOUNTING** Surface

**LOAD PER PHASE**

| CKT | CIRCUIT DESCRIPTION | TRIP | POLES | A | | B | | C | | POLES | TRIP | CIRCUIT DESCRIPTION | CKT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | | | | 1333 VA | 7500 VA | | | | | | | | 2 |
| 3 | VAV-2-2-2 | 15 A | 3 | | | 1333 VA | 7500 VA | | | 3 | 50 A | AHU 2-2 | 4 |
| 5 | | | | | | | | 1333 VA | 7500 VA | | | | 6 |
| 7 | | | | 1667 VA | 2500 VA | | | | | | | | 8 |
| 9 | VAV-2-2-6 | 15 A | 3 | | | 1667 VA | 2500 VA | | | 3 | 20 A | VAV 2-1-8 | 10 |
| 11 | | | | | | | | 1667 VA | 2500 VA | | | | 12 |
| 13 | | | | 1667 VA | 2500 VA | | | | | | | | 14 |
| 15 | VAV-2-2-7 | 15 A | 3 | | | 1667 VA | 2500 VA | | | 3 | 20 A | VAV 2-1-9 | 16 |
| 17 | | | | | | | | 1667 VA | 2500 VA | | | | 18 |
| 19 | VAV-2-2-8 | 15 A | 1 | 1000 VA | 1000 VA | | | | | 1 | 20 A | VAV 2-1-13 | 20 |
| 21 | VAV-2-2-9 | 15 A | 1 | | | 1000 VA | 0 VA | | | 1 | 20 A | SPARE | 22 |
| 23 | VAV-2-2-10 | 15 A | 1 | | | | | 1000 VA | 0 VA | 1 | 20 A | SPARE | 24 |
| 25 | VAV-2-2-11 | 15 A | 1 | 1000 VA | 0 VA | | | | | 1 | 20 A | SPARE | 26 |
| 27 | VAV-2-2-5 | 15 A | 1 | | | 1000 VA | 0 VA | | | 1 | 20 A | SPARE | 28 |
| 29 | VAV-2-2-12 | 15 A | 1 | | | | | 1000 VA | 0 VA | 1 | 20 A | SPARE | 30 |
| 31 | | | | 2500 VA | 2500 VA | | | | | | | | 32 |
| 33 | VAV 2-1-10 | 20 A | 3 | | | 2500 VA | 2500 VA | | | 3 | 20 A | VAV 2-1-11 | 34 |
| 35 | | | | | | | | 2500 VA | 2500 VA | | | | 36 |
| 37 | | | | 2500 VA | 2500 VA | | | | | | | | 38 |
| 39 | VAV 2-1-12 | 20 A | 3 | | | 2500 VA | 2500 VA | | | 3 | 20 A | VAV 2-1-7 | 40 |
| 41 | | | | | | | | 2500 VA | 2500 VA | | | | 42 |
| 43 | | | | 3300 VA | 1700 VA | | | | | | | | 44 |
| 45 | VAV 2-2-5 | 20 A | 3 | | | 3300 VA | 1700 VA | | | 3 | 20 A | VAV 2-2-2 | 46 |
| 47 | | | | | | | | 3300 VA | 1700 VA | | | | 48 |
| 49 | | | | 4000 VA | 3300 VA | | | | | | | | 50 |
| 51 | VAV 2-2-6 | 20 A | 3 | | | 4000 VA | 3300 VA | | | 3 | 20 A | VAV 2-2-8 | 52 |
| 53 | | | | | | | | 4000 VA | 3300 VA | | | | 54 |
| 55 | VAV 2-2-1 | 20 A | 1 | 1000 VA | 1667 VA | | | | | | | | 56 |
| 57 | SPARE | 20 A | 1 | | | 0 VA | 1667 VA | | | 3 | 20 A | EQUIPMENT SPACE 258 | 58 |
| 59 | SPARE | 20 A | 1 | | | | | 0 VA | 1667 VA | | | | 60 |
| 61 | VAV 2-2-7 | 20 A | 1 | 1000 VA | 0 VA | | | | | 1 | 20 A | SPARE | 62 |
| 63 | VAV 2-2-9 | 20 A | 1 | | | 1500 VA | 0 VA | | | 1 | 20 A | SPARE | 64 |
| 65 | VAV 2-2-10 | 20 A | 1 | | | | | 2500 VA | 0 VA | 1 | 20 A | SPARE | 66 |
| 67 | VAV 2-2-11 | 20 A | 1 | 2000 VA | 0 VA | | | | | 1 | 20 A | SPARE | 68 |
| 69 | VAV 2-2-12 | 20 A | 1 | | | 2500 VA | 0 VA | | | 1 | 20 A | SPARE | 70 |
| 71 | VAV 2-2-13 | 20 A | 1 | | | | | 1000 VA | 0 VA | 1 | 20 A | SPARE | 72 |
| 73 | VAV 2-2-14 | 20 A | 1 | 1000 VA | 2200 VA | | | | | | | | 74 |
| 75 | VAV 2-2-15 | 20 A | 1 | | | 3000 VA | 2200 VA | | | 3 | 20 A | VAV 2-2-16 | 76 |
| 77 | SPARE | 20 A | 1 | | | | | 0 VA | 2200 VA | | | | 78 |
| 79 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | | | | 80 |
| 81 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 3 | 30 A | TVSS | 82 |
| 83 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | | | | 84 |
| | | POWER/PHASE | | 51333 VA | | 52333 VA | | 48833 VA | | | | | |
| | | AMPS/PHASE | | 187 A | | 190 A | | 176 A | | | | | |

| LOAD CLASS | CONNECTED LOAD | DEMAND FACTOR | DEMAND LOAD | TOTALS |
|---|---|---|---|---|
| Spare | 127500 VA | 100.00% | 127500 VA | **CONNECTED POWER** 152500 VA |
| Equipment | 25000 VA | 100.00% | 25000 VA | **DEMAND POWER** 152500 VA |
| | | | | **CONNECTED AMPS** 183 A |
| | | | | **DEMAND AMPS** 183 A |

**NOTES:**

EXISTING POWER PANEL

## HNE2A

**MAIN** 100 A MLO
**SYSTEM** 480Y/277V 3P 4W
**OPTIONS** BOLT ON BREAKERS

**A.I.C. RATING** 22000
**NEMA** NEMA 1

**LOCATION** ELEC. 2101
**MOUNTING** Surface

**LOAD PER PHASE**

| CKT | CIRCUIT DESCRIPTION | TRIP | POLES | A | | B | | C | | POLES | TRIP | CIRCUIT DESCRIPTION | CKT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | | | | 9400 VA | 0 VA | | | | | 1 | 20 A | SPARE | 2 |
| 3 | AHU 2-1 | 70 A | 3 | | | 9400 VA | 0 VA | | | 1 | 20 A | SPARE | 4 |
| 5 | | | | | | | | 9400 VA | 0 VA | 1 | 20 A | SPARE | 6 |
| 7 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 8 |
| 9 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 10 |
| 11 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 12 |
| 13 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 14 |
| 15 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 16 |
| 17 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 18 |
| 19 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 20 |
| 21 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 22 |
| 23 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 24 |
| 25 | SPARE | 20 A | 1 | 0 VA | 0 VA | | | | | 1 | 20 A | SPARE | 26 |
| 27 | SPARE | 20 A | 1 | | | 0 VA | 0 VA | | | 1 | 20 A | SPARE | 28 |
| 29 | SPARE | 20 A | 1 | | | | | 0 VA | 0 VA | 1 | 20 A | SPARE | 30 |
| 31 | | | | 0 VA | 0 VA | | | | | | | | 32 |
| 33 | T-LNE2A | 45 A | 3 | | | 0 VA | 0 VA | | | 3 | 30 A | SPARE | 34 |
| 35 | | | | | | | | 0 VA | 0 VA | | | | 36 |
| 37 | | | | 0 VA | 0 VA | | | | | | | | 38 |
| 39 | TVSS | 30 A | 3 | | | 0 VA | 0 VA | | | 3 | 20 A | SPARE | 40 |
| 41 | | | | | | | | 0 VA | 0 VA | | | | 42 |
| | | POWER/PHASE | | 9400 VA | | 9400 VA | | 9400 VA | | | | | |
| | | AMPS/PHASE | | 34 A | | 34 A | | 34 A | | | | | |

| LOAD CLASS | CONNECTED LOAD | DEMAND FACTOR | DEMAND LOAD | TOTALS |
|---|---|---|---|---|
| Spare | 28200 VA | 100.00% | 28200 VA | **CONNECTED POWER** 28200 VA |
| | | | | **DEMAND POWER** 28200 VA |
| | | | | **CONNECTED AMPS** 34 A |
| | | | | **DEMAND AMPS** 34 A |

**NOTES:**

NEW WORK LEGEND
- EXISTING TO REMAIN - LIGHT
- NEW WORK - BOLD

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | BID DOCUMENT REVISIONS | 5/10/2022 |

***PERMIT DOCUMENTS***

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 W BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

03.25.2022

DRAWING TITLE

***PANEL SCHEDULES***

HG ENGINEERS
621 N TYNDALL PARKWAY, SUITE C
PANAMA CITY, FL 32404
PHONE: (850) 243-6723
FL. AUTH NO. 00006680
PROJECT NO: 2186
Christopher A. Garlick; FL PE No.53924
Thomas A. Alexander; FL PE No.73172
Daniel J. White; FL PE No.73790
Caleb W. Leonard; FL PE No.91762

SHEET NUMBER

**E-501**

2022-05-09 4:31:24 PM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)\2186 - ECP North Terminal Renovations Task 2-ELECTRICAL.rvt

# LEGEND

| | | |
|---|---|---|
| ——— | FW | FIRE WATER SUPPLY |
| ———W——— | PW | POTABLE WATER SUPPLY |
| ◎ | | CEILING MOUNTED PENDANT HEAD |
| ◎ | | UPRIGHT HEAD |
| ▽ | | SIDEWALL HEAD |
| ▽$^{F}$ | | FREEZE PROOF SIDEWALL HEAD (EXTENDED COVERAGE) |

# DESIGN CRITERIA

EACH BULIDING SYSTEM SHALL BE HYDRAULICALLY DESIGNED WITH NO INSIDE HOSE STREAM ALLOWANCE AND FIRE PROTECTION SPRINKLER DENSITY VALUES AS FOLLOWS:

LIGHT HAZARD = 0.10 GPM/SF WITH A MAXIMUM OF 225 SF COVERAGE PER SPRINKLER

ORDINARY HAZARD GROUP 1 = 0.15 GPM/SF WITH A MAXIMUM OF 130 SF COVERAGE PER SPRINKLER

ORDINARY HAZARD GROUP II = 0.20 GPM/SF WITH A MAXIMUM OF 130 SF COVERAGE PER SPRINKLER

THE SPRINKLER DESIGN SHALL BE BASED ON THE MOST HYDRAULICALLY DEMANDING 1500 SF. THE CONTRACTOR IS ALLOWED TO REDUCE THE DESIGN AREA BASED ON THE USE OF QUICK RESPONSE SPRINKLERS AND CEILING HEIGHT IN ACCORDANCE WITH NFPA 13.

THE DESIGN OF THE SPRINKLER SYSTEM SHALL BE BASED UPON WATER SUPPLY INFORMATION OBTAINED BY THE SPRINKLER CONTRACTOR AND WITNESSED BY THE AUTHORITY HAVING JURISDICTION. WATER SUPPLY SHALL BE PRESUMED AVAILABLE AT THE POINT OF CONNECTION OF THE FIRE MAIN TO THE WATER SUPPLY SYSTEM.

# WATER BASED SPRINKLER SYSTEM REQUIREMENTS


1. THE POINT OF SERVICE, BACKFLOW PREVENTER, & FDC ARE EXISTING. REFER TO THE CIVIL SITE UTILITY PLAN FOR
2. THE BUILDING SHALL BE FULLY SPRINKLED IN ACCORDANCE WITH NFPA 13-2016 AND 2020 FLORIDA FIRE PREVENTION CODE (7TH EDITION).
3. REFER TO PLAN SHEETS AND HAZARD CLASSIFICATION LEGEND FOR HAZARD CLASSIFICATION OF EACH ROOM OR AREA.
4. THE NEW SYSTEMS SHALL SHALL BE HYDRAULICALLY CALCULATED IN ACCORDANCE WITH NFPA 13-2016.

   LIGHT HAZARD: 0.10 GPM/SF, MAX 225 SF PER HEAD, 15 FT MAX NOMINAL SPACING; ORDINARY TEMPERATURE RATING HEADS.
   ORDINARY HAZARD GROUP 1: 0.15 GPM/SF, MAX 130 SF PER HEAD, 15 FT MAX NOMINAL SPACING; INTERMEDIATE TEMPERATURE RATING HEADS.
   ORDINARY HAZARD GROUP 2: 0.20 GPM/SF, MAX 130 SF PER HEAD, 15 FT MAX NOMINAL SPACING; INTERMEDIATE TEMPERATURE RATING HEADS.

   FOR ADDITIONAL REQUIREMENTS, REFER TO DESIGN CRITERIA NOTES ON THIS SHEET.
5. THE POINT OF SERVICE CONNECTION IS EXISTING.
6. REFER TO DESIGN CRITERIA NOTES ON THIS SHEET FOR FLOW TEST DATA.
7. RISER IS EXISTING AND WILL NOT BE MODIFIED.
8. MICROBIAL INDUCED CORROSION IS NOT ANTICIPATED IN THIS PROJECT.
9. BACKFLOW PREVENTER IS EXISTING. MAXIMUM DESIGN PRESSURE DROP SHALL NOT EXCEED 3.5 PSI.
10. REFER TO DIVISION 21 SPECIFICATIONS FOR QUALITY AND PERFORMANCE SPECIFICATIONS OF ALL FIRE PROTECTION COMPONENTS.
11. NO FIRE PUMP IS REQUIRED.
12. NO ON SITE FIREWATER STORAGE TANK IS REQUIRED.

# GENERAL NOTES

1. IT IS NOTED THAT SOME AREAS WILL BE REQUIRED TO BE PROTECTED AS ORDINARY HAZARD (MECHANICAL ROOMS, ETC.) THESE AREAS HAVE BEEN IDENTIFIED BY A DIFFERENT HATCHING PATTERN THEN THE LIGHT HAZARD AREAS ON THE PLANS.
2. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN CURRENT WATER FLOW DATA AND DESIGN SPRINKLER SYSTEMS ACCORDINGLY.
3. MAINTAIN THE INTEGRITY OF ALL FIRE RATED ASSEMBLIES AND ACOUSTICAL ASSEMBLIES.
4. CONTRACTOR SHALL COORDINATE SYSTEM DESIGN WITH ALL OTHER TRADES.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING INSPECTOR'S TEST LOCATIONS IN ACCORDANCE WITH NFPA 13 AND THE AUTHORITY HAVING JURISDICTION.
6. ALL PIPING SHALL OBSERVE PROPER PITCH. PROVIDE DRAINS FOR LOW POINTS.
7. THE SPRINKLER SYSTEM SHALL BE ARRANGED FOR FLUSHING. READILY REMOVABLE FITTINGS SHALL BE PROVIDED AT THE END OF ALL CROSSMAINS.
8. PIPE HANGERS SHALL BE INSTALLED AS REQUIRED BY NFPA 13 FOR SUPPORTING SPRINKLER PIPING. NO OTHER PIPING OR DEVICE SHALL BE ATTACHED TO THE SPRINKLER HANGER SYSTEM UNLESS THE HANGER HAS BEEN DESIGNED TO CARRY THE ADDITIONAL LOAD.
9. THIS CONTRACT DOES NOT INCLUDE ANY MATERIAL OR DEVICE TO IMPROVE THE STRUCTURAL STRENGTH OF THE BUILDING TO ENABLE IT TO CARRY THE LOAD OF THE FIRE PROTECTION SYSTEM.
10. ALL UNDERGROUND PIPING SHALL BE DUCTILE IRON WITH FITTINGS AND JOINTS PER NFPA 13. TEFLON TAPE SHALL BE ADDED TO ALL MALE THREADS OF PIPE AS A JOINING COMPOUND.
11. ALL ABOVE GROUND WET SPRINKLER PIPE THAT IS THREADED SHALL BE SCHEDULE 40 BLACK WITH BLACK CAST/MALEABLE IRON FITTINGS WITH JOINTS PER NFPA 13. TEFLON TAPE SHALL BE ADDED TO ALL MALE THREADS OF PIPE AS A JOINING COMPOUND. CPVC PIPING IS NOT ACCEPTABLE.
12. ALL ABOVE GROUND WET SYSTEM SPRINKLER PIPE THAT IS WELDED OR ROLL-GROOVED SHALL BE SCHEDULE 10 BLACK WITH BLACK CAST/MALEABLE IRON FITTINGS WITH JOINTS PER NFPA 13. CPVC PIPING IS NOT ACCEPTABLE.
13. TRENCHING SHALL BE PERFORMED BY HAND WHERE THERE IS THE POSSIBILITY OF ENCOUNTERING OBSTACLES OR EXISTING UTILITY LINES. WHERE CLEAR AND UNOBSTRUCTED AREAS ARE TO BE EXCAVATED, APPROPRIATE MACHINE EXCAVATION METHODS MAY BE EMPLOYED. PROVIDE PROPER BACKFILL AS REQUIRED PER SPECIFICATIONS.
14. INSTALL SPRINKLER HEADS IN CENTER OF TILE IN ACCOUSTICAL CEILINGS. HEAD LOCATIONS SHALL BE GUIDED B ARCHITECTURAL ELEMENTS FOR OTHER CEILING TYPES.
15. DO NOT LOCATE INSPECTOR'S TEST LOCATIONS OR DRAINS IN FINISHED SPACES. INDICATE ALL LOCATIONS OF EXPOSED PIPING ON SHOP DRAWINGS.
16. SITE PIPING BEYOND 5'-0" OUTSIDE OF BUILDING SHOWN FOR REFERENCE ONLY. REFER TO CIVIL SITE UTILITY PLANS FOR BACK FLOW PREVENTER WITH FIRE DEPARTMENT CONNECTION AND HYDRANT LOCATIONS.
17. FLEXIBLE CONNECTIONS TO SPRINKLER HEADS ARE NOT ALLOWED.




WATFORD ENGINEERING
800.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

# FIRE PROTECTION LEGEND AND NOTES


SHEET NUMBER

# FP0.0.1

5/9/2022 8:37:13 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Fire Protection.rvt

## SHEET NOTES

1. REMOVE EXISTING UPRIGHT SPRINKLER HEADS CURRENTLY INSTALLED IN SHELL SPACE. HEADS SHALL BE TURNED DOWN AND RELOCATED AS NECESSARY. REFER TO FP2.0.1.
2. REMOVE EXISTING FDV AND PREPARE FOR RELOCATION. REFER TO FP2.0.1 FOR NEW LOCATION.
3. REMOVE EXISTING WINDOW SPRINKLERS IN AREAS WHERE NEW TWO HOUR WALL WILL BE ADDED, CONTINUOUS FROM FLOOR TO CEILING.
4. REMOVE EXISTING FIRE SPRINKLER CONTROL ASSEMBLY FROM WALL TO BE DEMOLISHED. RELOCATE TO NEW LOCATION SHOWN ON FP2.0.1.




1 FIRE PROTECTION DEMOLITION PLAN
FP1.0.1 SCALE: 1/8" = 1'-0"

TRUE PROJECT

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

**FIRE PROTECTION DEMOLITION PLAN**

SHEET NUMBER

**FP1.0.1**




WATFORD ENGINEERING
850.526.3447
4452 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27825
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061


5/9/2022 8:37:20 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Fire Protection.rvt

## HAZARD CLASSIFICATION

| | |
|---|---|
| | LIGHT HAZARD |
| | ORDINARY HAZARD GROUP 1 |
| | ORDINARY HAZARD GROUP 2 |

## SHEET NOTES


1. HEADS SHALL BE TURNED DOWN AND/OR RELOCATED AS NECESSARY TO PROVIDE FULL COVERAGE. HEADS SHALL BE COORDINATED WITH ARCHITECTURAL CEILING SYSTEM AND ALL HEAD LOCATIONS SHALL BE APPROVED BY ARCHITECT.
2. NEW STOREFRONT WINDOW WALL SHALL BE PROTECTED IN ACCORDANCE WITH NFPA 101.8.6.7(1)(C). ATRIUM SIDE IS NOT REQUIRED TO HAVE SPRINKLERS PER 101.8.6.7(1)(C)iv.
3. PROVIDE NEW FDV IN LOCATION SHOWN.
4. RELOCATE EXISTING SPRINKLER CONTROL ASSEMBLY TO LOCATION SHOWN.




## FIRE PROTECTION NEW WORK PLAN

FP2.0.1 SCALE: 1/8" = 1'-0"

TRUE PROJECT





WATFORD ENGINEERING
850.526.3447
4402 Clinton Street
Marianna, Florida 32446
Florida CA Number: 27525
David N. Watford, PE
Florida License Number: 58208
Project Number: 2021-061



© 2018 All reproduction & intellectual property rights reserved.



FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA


REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|

**PERMIT DOCUMENTS**

NOT RELEASED FOR CONSTRUCTION

CLIENT

***NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)***

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**FIRE PROTECTION NEW WORK PLAN**

SHEET NUMBER

# FP2.0.1


5/9/2022 8:37:28 AM BIM 360://210211 - NFBIA North Terminal Renovations - Task #2 (2021)/2021-061_ECP Terminal Expansion Fire Protection.rvt

## TELECOM / SECURITY / AUDIO VISUAL SYSTEM LEGEND

| DEVICE SYMBOL | SYMBOL SUBSCRIPT - TYPE 'x' | DESCRIPTION |
|---|---|---|
| | | BUILDING SUPPORT SYSTEM DEVICES |
| | DDC | DIRECT DIGITAL CONTROLS NETWORK OUTLET |
| | FA | FIRE ALARM SYSTEM OUTLET |
| | | NETWORK DEVICES |
| | - | DATA/VOICE OUTLET |
| | WAP | WIRELESS ACCESS POINT DATA OUTLET |
| | - | POKE-THRU - DATA/VOICE OUTLET |
| | | AUDIO VISUAL SYSTEM - ROUGH-IN ONLY |
| FID | - | FLIGHT INFORMATION DISPLAY |
| GID | - | GATE INFORMATION DISPLAY |
| FP | - | LIVE STREAMING CONTENT DISPLAY |
| DS | - | DIGITAL SIGNAGE DISPLAY |
| | | PAGING SYSTEM |
| S | - | WALL MOUNTED SPEAKER - INTERIOR |
| S | - | CEILING MOUNTED SPEAKER - INTERIOR |
| PA | - | PAGING INTERFACE WITH DESKTOP PHONE |
| PAS | - | LOCAL PAGING SYSTEM "SIDEKICK" MICROPHONE |
| | | CAMERA SURVEILLANCE SYSTEM (CCTV) - ROUGH-IN ONLY |
| CAM | - | WALL MOUNTED CAMERA - INTERIOR |
| CAM | - | CEILING MOUNTED CAMERA - INTERIOR |
| CAM | - | CORNER MOUNTED CAMERA - INTERIOR |
| | | ACCESS CONTROL SYSTEM (ACS) - ROUGH-IN ONLY |
| CR | - | CARD READER |
| CRK | - | CARD READER W/KEYPAD |
| D | - | DOOR POSITION SENSOR / CONTACT |
| | | |

## SYSTEMS ANNOTATION LEGEND

1 SHEET NOTE

LEADER

1 DIAGRAM NOTE


DIAGRAM LEADER

CONDUIT TURNING DOWN

CONDUIT TURNING UP

CONDUIT STUB


### TYPICAL ENLARGED PLAN REFERENCE




### TYPICAL DETAIL TITLE




### TYPICAL VIEW TITLE




### TYPICAL ELEVATION SYMBOL




### TYPICAL SECTION SYMBOL




## SYSTEMS ABBREVIATIONS:

| | |
|---|---|
| AW | ABOVE WORK-SURFACE |
| AFF | ABOVE FINISH FLOOR |
| ACS | ACCESS CONTROL SYSTEM |
| ADA | AMERICANS WITH DISABILITIES ACT |
| ANSI | AMERICAN NATIONAL STANDARDS INSTITUTE |
| AWG | AMERICAN WIRE GAUGE |
| AA | APPROVING AUTHORITY |
| ARCH | ARCHITECTURAL |
| AV | AUDIO / VISUAL |
| AHJ | AUTHORITY HAVING JURISDICTION |
| BBC | BONDING BACKBONE CONDUCTOR |
| BAS | BUILDING AUTOMATION SYSTEM |
| CT | CABLE TRAY |
| CAT 3 | CATEGORY 3 |
| CAT 5E | CATEGORY 5 ENHANCED |
| CAT 6 | CATEGORY 6 |
| CAT 6A | CATEGORY 6 AUGMENTED |
| CO | COMMUNICATIONS OUTLET |
| CATV | COMMUNITY ANTENNA TELEVISION |
| C | CONDUIT |
| CP | CONSOLIDATION POINT |
| CFCI | CONTRACTOR FURNISHED, CONTRACTOR INSTALLED |
| CFOI | CONTRACTOR FURNISHED, OWNER INSTALLED |
| OTR | OWNER'S TECHNICAL REPRESENTATIVE |
| DDC | DIRECT DIGITAL CONTROLS |
| DEMARC | DEMARCATION |
| DS | DIGITAL SIGNAGE |
| EBS | EMERGENCY BROADCAST SYSTEM |
| ELEC | ELECTRICAL |
| EMI | ELECTROMAGNETIC INTERFERENCE |
| EMCS | ENERGY MANAGEMENT CONTROL SYSTEM |
| EMT | ELECTRICAL METALLIC TUBING |
| ESS | ELECTRONIC SECURITY SYSTEM |
| EX | EXISTING |
| EXT | EXTERIOR |
| FCC | FEDERAL COMMUNICATIONS COMMISSION |
| FO | FIBER OPTIC |
| FP | FLAT PANEL |
| HH | HANDHOLE |
| IAW | IN ACCORDANCE WITH |
| LAN | LOCAL AREA NETWORK |
| MTR | MAIN TELECOMMUNICATIONS ROOM |
| MH | MAINTENANCE HOLE |
| MAX | MAXIMUM |
| um | MICRON / MICROMETER |
| MIN | MINIMUM |
| MUTOA | MULTI-USER TELECOMMUNICATIONS OUTLET ASSEMBLY |
| MM | MULTIMODE |
| NEMA | NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION |
| NEC | NATIONAL ELECTRICAL CODE |
| NESC | NATIONAL ELECTRICAL SAFETY CODE |
| NFPA | NATIONAL FIRE PROTECTION ASSOCIATION |
| NVR | NETWORK VIDEO RECORDER |
| N/A | NOT APPLICABLE |
| NIC | NOT IN CONTRACT |
| OFCI | OWNER FURNISHED, CONTRACTOR INSTALLED |
| OFOI | OWNER FURNISHED, OWNER INSTALLED |
| OSP | OUTSIDE PLANT |
| PR | PAIR |
| PP | PATCH PANEL |
| PVC | POLYVINYL CHLORIDE |
| PB | PULL BOX |
| PBB | PRIMARY BONDING BUSBAR |
| PBX | PRIVATE BRANCH EXCHANGE |
| RMU | RACK MOUNTED UNIT |
| RM | ROOM |
| RI | ROUGH-IN |
| ScTP | SCREENED TWISTED-PAIR |
| SBB | SECONDARY BONDING BUSBAR |
| SVTC | SECURED VIDEO TELECONFERENCE |
| SEC | SECURITY |
| STP | SHIELDED TWISTED-PAIR |
| SM | SINGLEMODE |
| SF | SURFACE MOUNT |
| STR | STRANDS |
| TBB | TELECOMMUNICATIONS BONDING BACKBONE |
| TEBC | TELECOMMUNICATIONS EQUIPMENT BONDING CONDUCTOR |
| TBC | TELECOMMUNICATIONS BONDING CONDUCTOR |
| TER | TELECOMMUNICATIONS EQUIPMENT ROOM |
| TR | TELECOMMUNICATIONS ROOM |
| TIA | TELECOMMUNICATIONS INDUSTRY ASSOCIATION |
| TYP | TYPICAL |
| UG | UNDERGROUND |
| UL | UNDERWRITERS LABORATORIES INC |
| UPS | UNINTERRUPTIBLE POWER SUPPLY |
| UTP | UNSHIELDED TWISTED-PAIR |
| UNO | UNLESS NOTED OTHERWISE |
| VTC | VIDEO TELECONFERENCE |
| VoIP | VOICE OVER INTERNET PROTOCOL |

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**SYSTEMS LEGEND AND NOTES**

LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM

SHEET NUMBER

**T-0.0.1**

## TELECOMMUNICATIONS GENERAL NOTES - FACILITY INFRASTRUCTURE:

THE TELECOMMUNICATIONS DRAWINGS PROVIDED ARE DIAGRAMMATIC AND SHOW THE GENERAL LOCATION OF ALL REQUIRED DEVICES; SUCH AS OUTLETS, RACEWAYS, EQUIPMENT, AND APPURTENANCES. THEY DO NOT SHOW ALL NECESSARY OFFSETS, JUNCTION BOXES, CABLE/LADDER TRAY TRANSITIONS, CONDUIT SLEEVES/PENETRATIONS, AND ADJUSTMENTS NECESSARY BY COORDINATION WITH OTHER TRADES IN THE FIELD.

TELECOMMUNICATION CONTRACTOR'S SCOPE OF WORK: TELECOMMUNICATION'S CONTRACTOR SHALL BE RESPONSIBLE FOR ENTIRE STRUCTURED CABLING SYSTEM ELEMENTS DEFINED IN THIS SCOPE OF WORK. THIS INCLUDES A COMPLETE INSTALLATION OF ALL PASSIVE INFRASTRUCTURE ELEMENTS SUCH AS OUTLETS, JACKS, CABLING, CABINETS, RACKS. BACKBOARDS, LADDER TRAY (LIMITED TO TELECOM ROOMS), TELECOM EQUIPMENT ROOM/CABINET BONDING, TERMINATIONS, TESTING, LABELING, WARRANTIES, AND ALL REQUIRED CLOSE-OUT DOCUMENTS. THE TELECOMMUNICATIONS CONTRACTOR SHALL UNDERSTAND THE FULL INTENT OF THE DRAWINGS AND SPECIFICATIONS PRIOR TO BID, AND WILL INCLUDE IN SCOPE OF WORK ALL REQUIREMENTS NECESSARY TO ENSURE A FULLY FUNCTIONAL SYSTEM.

COORDINATION: WITH OTHER TRADES EXAMINE AND REVIEW THE DOCUMENTS OF ALL DIVISIONS IN ORDER TO COORDINATE THE INSTALLATION OF WORK. USE DIMENSIONED DRAWINGS TO VERIFY THE SPACE NECESSARY FOR LOCATING OUTLETS, RACEWAYS, AND EQUIPMENT. USE FIELD MEASUREMENTS TO VERIFY DIMENSIONS WHERE AREAS ARE CONGESTED, AND EXACT LOCATION IS CRITICAL TO ENSURE PROPER INSTALLATION. COORDINATION SHALL INCLUDE, BUT NOT BE LIMITED TO; VERIFYING THE LOCATION AND SIZE OF OPENINGS/PENETRATIONS IN FLOORS, WALLS, PARTITIONS, CEILINGS, AND ROOFS WITH THE INSTALLING TRADES; ALLOCATION OF SPACE WITH OTHER TRADES, INSTALLING WORK IN CHASES, SHAFTS, CEILING INTERSTITIAL SPACES, AND EQUIPMENT SPACES; AND THE PHASING OF INSTALLATION WORK WITH THAT OF OTHER TRADES.

INSTALLATION SHALL CONFORM WITH NFPA 70 "NATIONAL ELECTRICAL CODE," ANSI/TIA, AND ELECTRICAL SPECIFICATIONS (UNO).

CABLING INSTALLATION: ALL CABLING ROUTED IN SLAB, BELOW VAPOR BARRIER OR BELOW GRADE, SHALL BE U.L. LISTED FOR WET LOCATIONS THAT COMPLIES WITH NFPA 70 (NEC): PART V, 725.3(L), 110.11, 300.5(B), 300.6, AND 310.10(G). DO NOT USE PLENUM OR RISER RATED CABLE, AND UNLISTED CABLES IN SUCH AN ENVIRONMENT. FOR IN-FLOOR CONDUIT SYSTEMS, PROVIDE HOME RUNS BACK TO THE TR SERVING THAT AREA.

USE A FILL RATIO OF 40 PERCENT FOR CONDUIT SIZING. DO NOT INSTALL MORE THAN FOUR, FOUR-PAIR CABLES IN A 1 INCH (27 MM) CONDUIT.

PROVIDE PULL STRING IN ALL EMPTY CONDUITS AND INNERDUCT. PULL STRING TO BE RATED FOR 200LBS IN ALL CONDUITS.

TELECOMMUNICATIONS FACEPLATES SHALL MATCH ELECTRICAL SWITCH AND RECEPTACLE PLATE FINISHES. PROVIDE COVER PLATES FOR ALL UNUSED J-BOX LOCATIONS.

LABEL ALL CABLES WITHIN 4 INCHES OF EACH TERMINATION. PROVIDE 12 INCHES SERVICE LOOP AT THE WORK AREA END OF EACH HORIZONTAL CABLE.

INSTALL VELCRO CABLE TIES TO ALL CABLE BUNDLES IN CABLE TRAY, NON-CONTINUOUS SUPPORTS, RACK WIRE MANAGEMENT, D-RINGS AND OTHER SUPPORT MEANS. BUNDLE ALL DIFFERENTIATING NETWORK CABLING SEPARATELY.

BALANCED TWISTED-PAIR CABLING SHALL BE SEPARATED FROM FLUORESCENT LAMPS AND ASSOCIATED FIXTURES BY A MINIMUM OF 5 IN.

NON-CONTINUOUS CABLE SUPPORTS (WHEN SPECIFIED): SUPPORTS MUST NOT EXCEED 20 CABLES OR 50 PERCENT OF THE FILL CAPACITY, WHICHEVER IS LESS; INTERVALS NOT TO EXCEED 5 FT.

CABLING INSTALLATION IN CABLE TRAYS:
A MINIMUM OF 12 IN ACCESS HEADROOM SHALL BE PROVIDED AND MAINTAINED ABOVE A CABLE TRAY SYSTEM OR CABLE RUNWAY.

A MINIMUM OF 3 IN CLEAR VERTICAL SPACE SHALL BE AVAILABLE ABOVE ACCESSIBLE CEILING, BELOW THE CABLE TRAY.

THE MAXIMUM FILL OF ANY CABLE TRAY SHALL NOT EXCEED 25% (UNO), ALLOWING FACILITY USERS AN ADDITIONAL 25% SPARE CAPACITY. THE MAXIMUM FILL DEPTH OF ANY CABLE TRAY SHALL NOT EXCEED 6 IN.

MAIN TELECOM ROOM (MTR) / TELECOM ROOMS (TRs):
CONTRACTOR SHALL COORDINATE WITH GENERAL CONTRACTOR TO ENSURE TELECOM ROOMS ARE DIMENSIONALLY CONSTRUCTED AS DESIGNED. THIS INCLUDES USING FIELD MEASUREMENTS TO VERIFY ROOM DIMENSIONS, CONDUIT LOCATIONS (PRIOR TO CONCRETE POUR), WALL PENETRATIONS, AND DEVICE PLACEMENT.

INSTALL BACKBOARDS IN ACCORDANCE WITH TIA-569-D. BACKBOARDS MUST BE FIRE-RETARDANT TREATED WOOD, BEARING THE MANUFACTURER'S STAMP. IF PAINTED, THE MANUFACTURER'S FIRE RATED STAMP MUST REMAIN VISIBLE.

INSTALL FLOOR MOUNTED EQUIPMENT RACKS / CABINETS LOCATED AT OR NEAR THE CENTER OF THE TELECOMMUNICATION ROOM. MAINTAIN A MINIMUM OF 36 INCHES SPACE BOTH IN FRONT AND IN BACK OF THE RACK, MEASURED FROM THE EQUIPMENT, AND A MINIMUM SIDE CLEARANCE OF 24 INCHES ON AT LEAST ONE END OF THE RACK OR ROW OF ADJACENT RACKS IS REQUIRED. PROVIDE 25% SPARE CAPACITY WITHIN EACH UTILIZED RACK.

FURNITURE/MILLWORK:
ENSURE THAT THE CABLE IS PROTECTED AT ALL TRANSITION POINTS, AND THAT METALLIC SEPARATION IS PROVIDED BETWEEN TELECOMMUNICATION AND POWER WIRING IN THE UTILITY COLUMNS AND SYSTEMS FURNITURE TRACK IN ACCORDANCE WITH TIA-569-D AND NFPA 70.

## ELECTRICAL GENERAL NOTES - FACILITY INFRASTRUCTURE:

ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE ENTIRE INTERIOR ROUGH-IN AND SUPPORT SYSTEM NECESSARY FOR THE COMPLETE STRUCTURED CABLING SYSTEM DEFINED IN THIS SCOPE OF WORK. THIS INCLUDES A COMPLETE INSTALLATION OF ALL REQUIRED PATHWAYS INCLUDING: CABLE TRAY (EXCLUDES TRAY IN MTR/TR), CONDUIT, BACK BOXES, JUNCTION BOXES, FLOOR BOXES, BLOCKING, GROUNDING CONDUCTORS AND BUSBARS, FIRESTOPPING, POWER, AND ANY OTHER NECESSARY APPURTENANCES.

THE ELECTRICAL CONTRACTOR SHALL UNDERSTAND THE FULL INTENT OF THE DRAWINGS AND SPECIFICATIONS PRIOR TO BID, AND WILL INCLUDE IN SCOPE OF WORK ALL REQUIREMENTS NECESSARY TO SUPPORT THE TELECOMMUNICATIONS SYSTEM TO COORDINATE AND ENSURE A FULLY FUNCTIONAL SYSTEM.

COORDINATION WITH OTHER TRADES:
EXAMINE AND REVIEW THE DOCUMENTS OF ALL DIVISIONS IN ORDER TO COORDINATE THE INSTALLATION OF WORK. USE DIMENSIONED DRAWINGS TO VERIFY THE SPACE NECESSARY FOR LOCATING OUTLETS, RACEWAYS, AND EQUIPMENT. USE FIELD MEASUREMENTS TO VERIFY DIMENSIONS WHERE AREAS ARE CONGESTED, AND EXACT LOCATION IS CRITICAL TO ENSURE PROPER INSTALLATION. COORDINATION SHALL INCLUDE, BUT NOT BE LIMITED TO, VERIFYING THE LOCATION AND SIZE OF OPENINGS/PENETRATIONS IN FLOORS, WALLS, PARTITIONS, CEILINGS, AND ROOFS WITH THE INSTALLING TRADES; ALLOCATION OF SPACE WITH OTHER TRADES, INSTALLING WORK IN CHASES, SHAFTS, CEILING INTERSTITIAL SPACES, AND EQUIPMENT SPACES; AND THE PHASING OF INSTALLATION WORK WITH THAT OF OTHER TRADES.

INSTALLATION SHALL CONFORM WITH NFPA 70 "NATIONAL ELECTRICAL CODE," ANSI/TIA, AND ELECTRICAL SPECIFICATIONS (UNO).

CONDUIT:
INSTALL ELECTRICAL METALLIC TUBING (EMT) CONDUIT FROM THE CABLE BACKBONE DISTRIBUTION SYSTEM, WHETHER CABLE TRAY OR ENCLOSED DUCT, TO EACH OUTLET (UNO).

PROVIDE A MINIMUM OF 1 INCH EMT CONDUIT FOR STANDARD OUTLETS. WHEN CABLE TRAY OR ENCLOSED DUCT IS NOT USED, INSTALL INDIVIDUAL CONDUITS FROM THE MTR/TR TO EACH OUTLET.

CONDUITS HAVE BEEN SIZED BASED ON THE NFPA, AS WELL AS ANSI/TIA 569. WHERE INSTALLATIONS VARY, INCREASE CONDUITS SIZES ACCORDING TO MAXIMUM NUMBER OF CABLES BASED ON ALLOWABLE FILL RATIO OF 40%.

FOR IN-SLAB, BELOW VAPOR BARRIER OR BELOW GRADE CONDUIT SYSTEMS, PROVIDE HOME RUNS BACK TO THE MTR/TR SERVING THAT AREA.

METALLIC PATHWAYS 3 FT OR GREATER IN LENGTH SHALL COMPLY WITH THE BONDING REQUIREMENTS OF ANSI/TIA-607.

FOR CONDUITS WITH AN INTERNAL DIAMETER OF 2 IN OR LESS, THE INSIDE RADIUS OF A BEND IN CONDUIT SHALL BE AT LEAST 6 TIMES THE INTERNAL DIAMETER. FOR CONDUITS WITH AN INTERNAL DIAMETER OF MORE THAN 2 IN, THE INSIDE RADIUS OF A BEND IN CONDUIT SHALL BE AT LEAST 10 TIMES THE INTERNAL DIAMETER. BENDS IN THE CONDUIT SHALL NOT CONTAIN ANY KINKS OR OTHER DISCONTINUITIES THAT MAY HAVE A DETRIMENTAL EFFECT ON THE CABLE SHEATH DURING CABLE PULLING OPERATIONS.

CONDUITS SHALL BE REAMED TO ELIMINATE SHARP EDGES. METALLIC CONDUIT SHALL BE TERMINATED WITH AN INSULATED BUSHING.

DO NOT USE FLEXIBLE METAL CONDUIT FOR TELECOMMUNICATIONS WIRING EXCEPT WHEN INSTALLING ACCESS FLOOR BOXES IN AN ACCESS FLOOR, WHERE THE ACCESS FLOOR BOX MAY BE RELOCATED WITHIN A SPECIFIED SERVICE AREA. IN THIS CASE THE LENGTH OF THE FLEXIBLE METAL CONDUIT MUST NOT EXCEED A LENGTH OF 20 FEET (6 M) FOR EACH RUN PER TIA-569-D.

ALL PENETRATIONS SHALL BE SEALED WITH AN APPROVED SEALANT OR U.L. LISTED PENETRATION DEVICE THAT WILL MAINTAIN THE FIRE, SMOKE AND WATERPROOF OR OTHER APPLICABLE RATINGS OF THE TYPE OF CONSTRUCTION BEING PENETRATED. SEE ARCHITECTURAL DRAWINGS FOR PENETRATION REQUIREMENTS.

UNLESS NOTED OTHERWISE, ALL CONDUITS SHALL BE INSTALLED CONCEALED UNDER FLOOR SLABS, ABOVE THE CEILING AND WITHIN THE FINISHED WALLS. ALL OUTLET BOXES SHALL BE INSTALLED FLUSH MOUNTED WITHIN FINISHED WALLS, CEILINGS OR FLOORS. SURFACE MOUNTED RACEWAY AND OUTLET BOXES SHALL NOT BE PERMITTED ON FINISHED WALLS, CEILINGS OR FLOORS EXCEPT AS INDICATED ON THE DRAWINGS.

WHEN SURFACE MOUNT RACEWAYS ARE INDICATED, PROVIDE RACEWAY TO EMT TRANSITIONAL ADAPTER AT ALL ACCESSIBLE CEILINGS. ABOVE ACCESSIBLE CEILING, ROUTE EMT TO SERVING CABLE TRAY OR SERVING MTR/TR.

PULL ROPE SHALL BE INSTALLED IN ALL CONDUITS. PULL ROPE SHALL HAVE A MINIMUM 200LB TENSILE STRENGTH FOR ALL TELECOMMUNICATIONS CONDUITS.

WORK AREA OUTLETS:
INSTALL DOUBLE GANG ELECTRICAL BOXES, MINIMUM STANDARD SIZE 4-11/16 INCHES SQUARE AND 2-1/8 INCHES DEEP WITH APPROPRIATELY SIZED PLASTER RING FOR CONNECTION OF SINGLE GANG OR DOUBLE GANG FACEPLATE.

INSTALL OUTLET BOX FOR RECESS MOUNTING WITH THE FACEPLATE FLUSH WITH THE WALL SURFACE, AT THE SAME HEIGHT AS THE ELECTRICAL OUTLETS.

DO NOT PUT OUTLET BOXES IN SAME STUD CAVITY WHERE BOXES ARE ON EACH SIDE OF STC RATED WALLS.

POWER:
INSTALL A QUADRUPLEX ELECTRICAL OUTLET WITHIN 6 INCHES OF ALL WORK AREA OUTLETS TO SERVE TELECOMMUNICATIONS LOADS ASSOCIATED WITH THAT OUTLET.

TELECOM GROUNDING / BONDING:
INSTALL ALL REQUIRED TELECOM GROUNDING / BONDING PER ANSI/TIA 607, ELECTRICAL SPECIFICATIONS, TELECOM GROUNDING DETAILS / NOTES (UNO).

BLOCKING AND SUPPORT HARDWARE:
INSTALL ALL MOUNTS AND SUPPORT HARDWARE FOR TELECOM SYSTEMS; INCLUDING, UNISTRUT, ALL- THREAD OR THREADED RODS, BLOCKING, SUPPORT CABLES, ETC.

CABLE TRAYS:
THE MAXIMUM FILL OF ANY CABLE TRAY SHALL NOT EXCEED 50%. THE MAXIMUM FILL DEPTH OF ANY CABLE TRAY SHALL NOT EXCEED 6 IN.

THE SPAN FOR CABLE SUPPORT SYSTEMS SHALL BE DETERMINED IN ACCORDANCE WITH THE MANUFACTURER'S MAXIMUM RECOMMENDED LOAD CAPACITY FOR A GIVEN SPAN. THESE SYSTEMS MAY BE SUPPORTED BY THREE BASIC METHODS:
1. CANTILEVER BRACKETS FROM A WALL;
2. TRAPEZE OR INDIVIDUAL ROD SUPPORTS FROM ABOVE;
3. OR FROM BELOW.

CABLE TRAY SUPPORTS SHALL BE LOCATED WHERE PRACTICAL SO THAT CONNECTIONS BETWEEN SECTIONS OF THE TRAY FALL BETWEEN THE SUPPORT POINT AND ONE-QUARTER THE DISTANCE OF THE SPAN. A SUPPORT SHALL BE PLACED WITHIN 24 IN ON EACH SIDE OF ANY CONNECTION TO A BEND, TEE, OR CROSS.

A MINIMUM OF 12 IN ACCESS HEADROOM SHALL BE PROVIDED AND MAINTAINED ABOVE A CABLE TRAY SYSTEM OR CABLE RUNWAY.

INSTALL CABLE TRAY WITH SWEEPING RADIAL TURNS. DO NOT INSTALL WITH HARD 90° TURNS.

BOND CABLE TRAY PER ANSI/TIA 607, AND GROUNDING DETAILS / NOTES.

PULL BOXES:
PULL BOXES SHALL BE READILY ACCESSIBLE. PULL BOXES SHALL NOT BE PLACED IN A FIXED FALSE CEILING SPACE UNLESS IMMEDIATELY ABOVE A SUITABLY MARKED ACCESS PANEL.

A PULL BOX SHALL BE PLACED IN A CONDUIT RUN WHERE:
- THE LENGTH IS OVER 100 FT;
- THERE ARE MORE THAN TWO 90° BENDS, OR EQUIVALENT;
- OR THERE IS A REVERSE (U-SHAPED) BEND IN THE RUN.

PULL BOXES SHALL BE PLACED IN A STRAIGHT SECTION OF CONDUIT. THEY SHALL NOT BE USED IN LIEU OF A BEND. THE CORRESPONDING CONDUIT ENDS SHALL BE ALIGNED WITH EACH OTHER.

WHERE A PULL BOX IS REQUIRED WITH CONDUITS SMALLER THAN 1-1/4", AN OUTLET BOX MAY BE USED AS A PULL BOX.

IF THE PULL BOX IS COMPRISED OF METALLIC COMPONENTS, IT SHALL BE BONDED TO GROUND.

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**SYSTEMS NOTES**

SHEET NUMBER

**T-0.0.2**


LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM




ENLARGED DEMOLITION SYSTEMS FLOOR PLAN - FIRST FLOOR EXIT LANE

2 / T-1.0.1


SCALE: 1/4"=1'-0"




ENLARGED SYSTEMS FLOOR PLAN - BOARDING VESTIBULE 2103 (SECOND FLOOR)

3 / T-1.0.1

SCALE: 1/4"=1'-0"




ENLARGED SYSTEMS FLOOR PLAN - SECOND FLOOR

1 / T-1.0.1

SCALE: 1/8"=1'-0"

GENERAL NOTES:

1. REFER TO LEGEND AND NOTES, SHEETS T-0.0.1 AND T-0.0.2 FOR ADDITIONAL INFORMATION.
2. FOR DETAILS, REFER TO SHEETS T-2.0.1 - T-2.0.2.
3. FOR SINGLE LINE DIAGRAM, REFER TO SHEET T-3.0.1.
4. FOR ALL DEVICES SHOWN ON THIS SHEET, HOMERUN CONDUIT TO NEW TELECOM RM 1309 (TR.1309). SEE SHEET T-4.0.1 FOR ADDITIONAL DETAILS.

SHEET NOTES:

1. PROVIDE ROUGH-IN FOR ELEVATOR ACCESS CONTROL ON BOTH 1ST AND 2ND FLOORS.
2. REMOVE AND REINSTALL EXISTING SECURITY DEVICES IN THE EXIT LANE AND AT SECURE EXIT DOORS.

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

PANAMA CITY AIRPORT NWFBIA:

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE


05.10.2022

DRAWING TITLE

**ENLARGED SYSTEMS FLOOR PLAN**

SHEET NUMBER

**T-1.0.1**





4' 0' 4' 8'
SCALE: 1/4"=1'-0"

8' 0' 8' 16'
SCALE: 1/8"=1'-0"


LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM

## ANSI/TIA 606C IDENTIFICATION NOMENCLATURE




### 1 TIA-606C OUTLET TO PATCH PANEL LABELING NOMENCLATURE (TYPICAL)


NOT TO SCALE




NOTE:
PER ANSI/TIA-568, THE HORIZONTAL CABLING EXTENDS FROM THE TERMINATION OF THE MEDIA AT THE PATCH PANEL IN THE MTR/TR TO THE TELECOMMUNICATIONS OUTLET/CONNECTOR OR MULTI-USER TELECOMMUNICATIONS OUTLET ASSEMBLY. THE MAXIMUM HORIZONTAL CABLING LENGTH IN ANY DEVICE IS NOT TO EXCEED 90M (295FT), INDEPENDENT OF MEDIA TYPE. WHERE A MUTOA IS DEPLOYED, THE MAXIMUM HORIZONTAL BALANCED TWISTED-PAIR COPPER CABLE LENGTH SHALL BE REDUCED IN ACCORDANCE WITH ANSI/TIA-568. IN ESTABLISHING THE MAXIMUM DISTANCE FOR EACH HORIZONTAL CHANNEL, AN ALLOWANCE WAS MADE FOR 5M (16FT) FROM THE TELECOMMUNICATIONS OUTLET/CONNECTOR TO THE WORK AREA EQUIPMENT.

### 2 HORIZONTAL TELECOM CHANNEL LINK - ANSI / TIA 568.1-D

NOT TO SCALE





NOTES:

1. TELECOM OUTLET MOUNTING HEIGHT MAY VARY AT LOCATIONS OF FIXED CABINETS OR CASEWORK. LOCATE AND MOUNT OUTLETS AS DIRECTED BY THE TECHNICAL REPRESENTATIVE.
2. DO NOT INSTALL MORE THAN FOUR 4-PAIR CABLES IN A 1" CONDUIT.

### 3 TELECOM OUTLET MOUNTING DETAIL - HOMERUN DEVICE CONDUIT

NOT TO SCALE





KEY NOTES

1. POWER/DATA RECESSED POKE THRU, EQUAL TO LEGRAND EVOLUTION SERIES 8AT2. PROVIDE FLUSH MOUNT COVER, ALL FITTINGS, COUPLERS, SHIMS, ADAPTERS, DIVIDERS, AND BLANKS REQUIRED FOR A COMPLETE INSTALLATION. ADHERE TO MANUFACTURER'S INSTRUCTIONS TO MAINTAIN DEVICE'S U.L. 2-HOUR FIRE CLASSIFICATION. COVER FINISH SHALL BE BLACK, UNO.
2. INSTALL TWO STANDARD 120 VAC DUPLEX RECEPTACLES PROVIDED WITH POKE THRU. SEE ELECTRICAL PLANS FOR CIRCUITING REQUIREMENTS.
3. INSTALL SINGLE GANG DEVICE PLATE CAPABLE OF ACCEPTING SIX COMMUNICATIONS PORTS, EQUAL TO LEGRAND 8ACT6A. REFER TO PLANS FOR JACK TYPES / QUANTITY. TELECOM CONTRACTOR WILL INSTALL JACKS AND CABLING.
4. INSTALL TELECOM SINGLE GANG HOUSING W/CONDUIT COUPLER FOR 1"C. COORDINATE 1" CONDUIT ROUTING WITH STRUCTURED CABLING CONTRACTOR.
5. INSTALL POWER HOUSING ASSEMBLY; CONNECT TO ELECTRICAL CONDUIT / CIRCUIT WITH REQUIRED COUPLER. SEE ELECTRICAL DRAWINGS FOR CIRCUITING REQUIREMENTS.
6. INSTALL BLANK PLATES FOR CABLING/ CONNECTIONS BY OTHERS, EQUAL TO LEGRAND 8BAS.
7. INSTALL TWO SINGLE GANG HOUSINGS W/CONDUIT COUPLERS FOR 1"C.; CABLING CONNECTIONS BY OTHERS. COORDINATE FINAL CONDUIT ROUTING WITH DESIGNATED TECHNICAL REPRESENTATIVE.
8. HOMERUN CONDUIT(S) TO SERVING EQUIPMENT LOCATION. COORDINATE CONDUIT ROUTING IN FIELD.

### 4 MULTIMEDIA POKE-THRU DETAIL

NOT TO SCALE





KEY NOTES:

1. COMMUNICATIONS OUTLET FACEPLATE
2. SNAP-IN COUPLER; 8P8C, UNSHIELDED TWISTED PAIR (UTP), RJ-45 MODULAR JACK WITH COLORED NETWORK AS INDICATED IN LEGEND.
3. COMMUNICATIONS OUTLET IDENTIFIER ON LASER PRINTED INSERT UNDER FACTORY PLASTIC COVER.

TYPICAL FOR:


### 5 DATA/VOICE NETWORK FACEPLATE DETAIL

NOT TO SCALE




### 6 WIRELESS ACCESS (WAP) WALL MOUNTING DETAIL

NOT TO SCALE




KEY NOTES

1. COMMUNICATIONS SURFACE MOUNT OUTLET BOX.
2. SNAP-IN COUPLER; 8P8C, CATEGORY 6 RJ-45 MODULAR JACK.
3. NETWORK OUTLET IDENTIFIER ON LASER PRINTED INSERT UNDER FACTORY PLASTIC COVER.
4. PROVIDE SNAP-IN BLANK COUPLER; COLOR TO MATCH SURFACE BOX COLOR.

TYPICAL FOR:
DDC

### 7 SURFACE MOUNT 'BISCUIT' OUTLET

NOT TO SCALE

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT
**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE
**PANAMA CITY AIRPORT NWFBIA:**
# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**


PROJECT NUMBER
NO. 210211

ISSUE DATE
05.10.2022

DRAWING TITLE
**TELECOM DETAILS**


SHEET NUMBER
**T-2.0.1**

LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM





## 1 TYPICAL SECURITY DEVICE MOUNTING HEIGHTS

NOT TO SCALE





## 2 EXTERIOR (INTERIOR SIMILAR) CAMERA MOUNTING DETAIL - CORNER MOUNT

NOT TO SCALE





## 3 INTERIOR CAMERA MOUNTING DETAIL - WALL MOUNT

NOT TO SCALE





## 4 EXTERIOR CAMERA MOUNTING DETAIL - WALL MOUNT

NOT TO SCALE




## 5 INTERIOR CAMERA MOUNTING DETAIL - CEILING MOUNT


NOT TO SCALE




NOTES:
1. ACS DOOR/CONTACT POSITION SWITCH (NOT SHOWN ON PLANS FOR CLARITY)
2. ALL NOTED CONDUIT IS CONCEALED (WHERE ALLOWABLE BY SECURITY OFFICER).
3. AS A MINIMUM, PROVIDE PULLBOX EVERY 100' OF INTERIOR CONDUIT RUNS.

## 6 SECURITY DOOR ROUGH-IN DETAIL SINGLE DOOR - "CR", "CRK", "D"


NOT TO SCALE




NOTES:
1. ACS DOOR/CONTACT POSITION SWITCH (NOT SHOWN ON PLANS FOR CLARITY).
2. ALL NOTED CONDUIT IS CONCEALED (WHERE ALLOWABLE BY SECURITY OFFICER).
3. AS A MINIMUM, PROVIDE PULLBOX EVERY 100' OF INTERIOR CONDUIT RUNS.

## 7 SECURITY DOOR ROUGH-IN DETAIL SINGLE DOOR - "CR", "CRK", "D"


NOT TO SCALE




NOTES:
1. ACS DOOR/CONTACT POSITION SWITCH (NOT SHOWN ON PLANS FOR CLARITY)
2. ALL NOTED CONDUIT IS CONCEALED (WHERE ALLOWABLE BY SECURITY OFFICER).
3. ALL NOTED ACCESSIBLE PULL BOXES AND BACK BOXES ARE LOCATED ON SECURE SIDE OF DOOR, UNO.
4. AS A MINIMUM, PROVIDE PULLBOX EVERY 100' OF INTERIOR CONDUIT RUNS.

## 8 SECURITY ROUGH-IN DETAIL DOUBLE DOOR - "CR" / "CRK", "D",

NOT TO SCALE




NOTES:
1. ACS DOOR/CONTACT POSITION SWITCH (NOT SHOWN ON PLANS FOR CLARITY).
2. ALL NOTED CONDUIT IS CONCEALED (WHERE ALLOWABLE BY SECURITY OFFICER).
3. AS A MINIMUM, PROVIDE PULLBOX EVERY 100' OF INTERIOR CONDUIT RUNS.

## 9 SECURITY ROUGH-IN DETAIL SINGLE DOOR W/SWIPE OUT - "CR", "CRK", "D"

NOT TO SCALE

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**SECURITY DETAILS**

SHEET NUMBER


**T-2.0.2**

LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM





1 PAGING SPEAKER ROUGH-IN DETAIL - WALL MOUNT

NOT TO SCALE




2 PAGING SPEAKER DETAIL - CEILING MOUNT

NOT TO SCALE




NOTES:

1. MAXIMUM COMBINED WEIGHT OF WALL MOUNT DISPLAY AND DISPLAY MOUNT SHALL NOT EXCEED 250 LBS.

TYPICAL FOR: FP DS FID GID

3 ELECTRONIC DISPLAY ROUGH-IN DETAIL - WALL MOUNT

NOT TO SCALE

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

**AUDIO / VISUAL DETAILS**


LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM

SHEET NUMBER


**T-2.0.3**

## TELECOM GROUNDING LEGEND:


| | |
|---|---|
| CTBC | CABLE TRAY BONDING CONDUCTOR |
| IBC | INDIVIDUAL BONDING CONDUCTOR |
| MTR | MAIN TELECOMMUNICATIONS ROOM |
| PBB | PRIMARY BONDING BUSBAR |
| SBB | SECONDARY BONDING BUSBAR |
| RBB | RACK BUSBAR |
| TBB | TELECOMMUNICATIONS BONDING BACKBONE |
| TEBC | TELECOMMUNICATIONS EQUIPMENT BONDING CONDUCTOR |
| TBC | TELECOMMUNICATIONS BONDING CONDUCTOR |
| TR | TELECOMMUNICATIONS ROOM |




| BONDING CONDUCTOR SIZING CRITERIA | |
|---|---|
| TBB LINEAR LENGTH (FEET) | TBB CONDUCTOR SIZE (AWG) |
| LESS THAN 13 | 6 |
| 14 - 20 | 4 |
| 21 - 26 | 3 |
| 27 - 33 | 2 |
| 34 - 41 | 1 |
| 42 - 52 | 1/0 |
| 53 - 66 | 2/0 |
| 67 - 84 | 3/0 |
| 85 - 105 | 4/0 |
| 106 - 125 | 250 kcmil |
| 126 - 150 | 300 kcmil |
| 151 - 175 | 350 kcmil |
| 176 - 250 | 500 kcmil |
| 251 - 300 | 600 kcmil |
| GREATER THAN 301 | 750 kcmil |
| INFO BASED ON ANSI/TIA-607-C | |




2 LADDER TRAY GROUNDING / BONDING CONNECTION DETAIL
NOT TO SCALE




3 IRREVERSIBLE COMPRESSION CONNECTION DETAIL
NOT TO SCALE

## TELECOM GROUNDING NOTES:

1. PROVIDE TELECOMMUNICATIONS COPPER GROUNDING BUSBARS SUITABLE FOR INDOOR INSTALLATION IN ACCORDANCE WITH TIA-607. BUSBARS MUST BE MADE OF COPPER, OR COPPER ALLOYS HAVING A MINIMUM OF 95% CONDUCTIVITY WHEN ANNEALED AS SPECIFIED BY THE INTERNATIONAL ANNEALED COPPER STANDARD (IACS) AND LISTED BY A NATIONALLY RECOGNIZED TESTING LABORATORY.
2. ALL BUSBARS MUST BE PREDRILLED PROVIDED WITH HOLES FOR USE WITH STANDARD SIZED LUGS; BUSBARS MUST BE CLEANED, WITH AN ANTI-OXIDANT APPLIED PRIOR TO FASTENING CONNECTORS.
3. FROM SBB BUSBAR LOCATION, RUN CONDUCTOR TO PBB BUSBAR LOCATION IN EMT CONDUIT. IF PBB DOES NOT MEET TIA-607 OR DOES NOT EXIST, RUN TO BUILDING SERVICE GROUND IN EMT CONDUIT.
4. ALL BONDING CONDUCTORS SHALL HAVE A GREEN JACKET. WHERE BARE CONDUCTORS ARE SPECIFIED, THEY SHALL BE SUPPORTED BY STANDOFF INSULATORS AT INTERVALS NO GREATER THAN 2 FT OR BE CONTAINED IN ELECTRICAL NONMETALLIC TUBING (ENT). BARE BONDING CONDUCTORS SHALL NOT BE IN CONTACT WITH METALLIC SURFACES OR OTHER CONDUCTORS THAT ARE NOT PART OF THE TELECOMMUNICATIONS BONDING SYSTEM.
5. BOND EACH CONDUIT AND CONDUIT SUPPORT STRUTS IN ALL TRs, AND DESIGNATED SPACES WITH 6 AWG BONDING CONDUCTOR. METALLIC CABLE SHIELD(S), METAL PATHWAY FOR CABLE (E.G., CONDUIT), OR WATER PIPING SYSTEMS ARE NOT TO BE USED AS A TBB.
6. CONNECTIONS TO THE PBB: THE CONNECTIONS OF THE TBC AND THE TELECOMMUNICATIONS BONDING BACKBONE (TBB) TO THE PBB SHALL UTILIZE EXOTHERMIC WELDING, LISTED COMPRESSION TWO-HOLE LUGS, OR LISTED EXOTHERMIC TWO-HOLE LUGS. THE CONNECTION OF CONDUCTORS FOR BONDING TELECOMMUNICATIONS EQUIPMENT AND TELECOMMUNICATIONS PATHWAYS TO THE PBB SHALL UTILIZE EXOTHERMIC WELDING, LISTED COMPRESSION TWO-HOLE LUGS, OR LISTED EXOTHERMIC TWO-HOLE LUGS.
7. SECONDARY BUSBAR - SBB (AKA TGB): HAVE DIMENSIONS OF 6.35 MM (0.25 IN) THICK X 50 MM (2 IN) WIDE AND SIZED IN ACCORDANCE WITH THE IMMEDIATE APPLICATION REQUIREMENTS AND WITH CONSIDERATION OF FUTURE GROWTH.
8. BONDS TO THE SBB: THE TBBS AND OTHER SBBS WITHIN THE SAME SPACE SHALL BE BONDED TO THE SBB WITH A CONDUCTOR THE SAME SIZE AS THE TBB. IN ALL CASES, MULTIPLE SBBS WITHIN A ROOM SHALL BE BONDED TOGETHER WITH A CONDUCTOR THE SAME SIZE AS THE TBB.
9. CONNECTIONS TO THE SBB: THE CONNECTION OF THE TBB TO THE SBB SHALL UTILIZE EXOTHERMIC WELDING, LISTED COMPRESSION TWO-HOLE LUGS, OR LISTED EXOTHERMIC TWO-HOLE LUGS. THE CONNECTION OF CONDUCTORS FOR BONDING TELECOMMUNICATIONS EQUIPMENT AND TELECOMMUNICATIONS PATHWAYS TO THE SBB SHALL UTILIZE EXOTHERMIC WELDING, LISTED COMPRESSION TWO-HOLE LUGS, OR LISTED EXOTHERMIC TWO-HOLE LUGS.
10. RACK BONDING BUSBAR (RBB): SHALL HAVE A MINIMUM CROSS-SECTIONAL AREA EQUAL TO A 6 AWG WIRE, AND BE LISTED. EQUIPMENT CONTAINING METALLIC PARTS AND PATCH PANELS FOR SHIELDED CABLING IN CABINETS AND RACKS SHALL BE BONDED TO THE TELECOMMUNICATIONS BONDING SYSTEM IN ACCORDANCE WITH THE MANUFACTURER INSTRUCTIONS. WHERE INSTRUCTIONS ARE NOT GIVEN, ALL BONDING CONDUCTORS THAT CONNECT THESE INSTALLED PRODUCTS SHALL BE A MINIMUM SIZED CONDUCTOR OF 12 AWG. BOND ALL RACKS WITH 4 AWG CONDUCTOR; ROUTE CONDUCTOR ALONG RACK REAR AND IN CABLE RUNWAY TO GROUNDING BUSBAR.
11. CABLE TRAY / METALLIC PATHWAYS: ALL METALLIC TELECOMMUNICATIONS PATHWAYS SHALL BE BONDED TO THE PBB OR SBB. ADDITIONALLY, CABLE TRAY SECTIONS SHALL BE BONDED TOGETHER, AND TO THE PBB OR SBB. BOND TRAYS TOGETHER BY CONNECTOR PLATES OF AN IDENTICAL TYPE AS THE CABLE TRAY SECTIONS. PROVIDE NO. 2 AWG BARE COPPER WIRE THROUGHOUT CABLE TRAY SYSTEM, AND BOND TO EACH SECTION, EXCEPT USE NO. 1/0 ALUMINUM WIRE IF CABLE TRAY IS ALUMINUM. TERMINATE CABLE TRAYS 10 INCHES FROM BOTH SIDES OF SMOKE AND FIRE PARTITIONS. INSTALL CONDUCTORS RUN THROUGH SMOKE AND FIRE PARTITIONS IN 4 INCH RIGID STEEL CONDUITS WITH GROUNDING BUSHINGS, EXTENDING 12 INCHES BEYOND EACH SIDE OF PARTITIONS. SEAL CONDUIT ON BOTH ENDS TO MAINTAIN SMOKE AND FIRE RATINGS OF PARTITIONS.
12. BUILDING STRUCTURAL METAL: WHERE STRUCTURAL METAL IS ACCESSIBLE AND IN THE SAME ROOM AS THE SBB, THE SBB SHALL BE BONDED TO STRUCTURAL METAL USING A MINIMUM SIZED CONDUCTOR OF 6 AWG.
13. RUN CONDUCTOR FROM BUSBAR LOCATION TO BUILDING SERVICE GROUND IN EMT CONDUIT. PROVIDE INSULATED GROUNDING BUSHING - AT CONDUIT ENDS AND GROUND PER NEC. GROUNDING TO BUILDING STRUCTURE, CONDUITS, UTILITY PIPING, OR ELECTRICAL SUBPANELS IN LIEU OF BONDING TO BUILDING MAIN ELECTRICAL SERVICE GROUND IS NOT ACCEPTABLE.

1 TELECOM GROUNDING / BONDING DETAIL
NOT TO SCALE

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**GROUNDING DETAILS**

LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM

SHEET NUMBER

**T-2.0.4**




LAN BACKBONE LAYOUT

TYPICAL HORIZONTAL CABLING LAYOUT

## 1 DATA / VOICE SINGLE LINE DIAGRAM


NOT TO SCALE

TELECOM SINGLE LINE DIAGRAM NOTES:

1. FIBER OPTIC BACKBONE INTERCONNECT UNIT, PROVIDE INDICATED MODULE TYPE / QUANTITY; PROVIDE LABELING ON FRONT COVER TO INDICATE SERVING ROOM SOURCE, EACH ROOM'S DESTINATION, AND EACH CABLING QUANTITY / TYPE. CONFIRM TERMINATION MODULE WITH OWNER'S TECHNICAL REPRESENTATIVE (UNO).
2. FIBER OPTIC BACKBONE CABLE, CABLING TYPE INDICATED, DIELECTRIC, INDOOR/OUTDOOR, PLENUM RATED (IF REQUIRED) PER NFPA, (UNO). RUN CONTINUOUS FROM SOURCE TO DESTINATION WITH NO SPLICES OR TERMINATIONS. ADHERE TO TIA-598 JACKET COLOR CODING SCHEME FOR BACKBONE FIBER ONLY. CONFIRM TERMINATION MODULES WITH OWNER'S TECHNICAL REPRESENTATIVE (UNO). PROVIDE INDICATED STRAND QUANTITY.
3. FIBER OPTIC PATCH CORD; DUAL STRAND, DIELECTRIC, PRE-MANUFACTURED, FACTORY TERMINATED AND TESTED. PROVIDE QUANTITY AS REQUIRED, PLUS 10% SPARE. PATCH CORD TYPE, MODULE, AND COLOR TO MATCH SERVING DEVICES. CONFIRM ALL PATCH CORD REQUIREMENTS WITH TECHNICAL REPRESENTATIVE (UNO).
4. CATEGORY 6 HORIZONTAL PATCH PANEL WITH 8P8C UTP (UNSHIELDED TWISTED PAIR) MODULAR JACKS, COLOR TO MATCH FACEPLATE JACK; PROVIDE WITH REAR CABLE MANAGERS. LABEL JACKS ACCORDING TO OWNER'S TECHNICAL REPRESENTATIVE'S REQUIREMENTS OR ADHERE TO TIA 606 LABELING STANDARDS. PROVIDE INDICATED PORT QUANTITY.
5. CATEGORY 6 HORIZONTAL WIRING; UTP (UNSHIELDED TWISTED PAIR), 4-PAIR, 23 AWG, PLENUM RATED (IF REQUIRED) PER NFPA, MAXIMUM INSTALLED LENGTH 90 METERS (295'), TERMINATED TO T568A PINOUT ARRANGEMENT.
6. DATA / VOICE OUTLET WITH CATEGORY 6 8P8C UTP (UNSHIELDED TWISTED PAIR) MODULAR JACKS FOR DATA/VOICE CONNECTIONS, TERMINATED TO T568A PINOUT ARRANGEMENT.
7. CATEGORY 6 PATCH CORDS WITH UTP (UNSHIELDED TWISTED PAIR) 8P8C MODULAR PLUG, PRE-MANUFACTURED WITH NO BOOT, FACTORY TERMINATED AND TESTED TO T568A PINOUT ARRANGEMENT. COLOR TO MATCH SYSTEM JACK. PROVIDE QUANTITY OF PATCH CORDS AS REQUIRED PLUS 10% SPARE.
8. DEVICE DESTINATION CABLE LABELING, PER ANSI/TIA LABELING STANDARDS.

TV SYSTEM GENERAL NOTES:

1. CABLE SHALL BE CONTINUOUS BETWEEN DEVICES. INTERMEDIATE SPLICES OR COUPLINGS ARE NOT ALLOWABLE.
2. ALL COAXIAL CONNECTORS SHALL BE 'F' COMPRESSION TYPE, FOR RG-6 AND RG-11, SPECIFICALLY SIZED FOR EACH CONNECTOR TYPE.
3. PROVIDE EQUALIZERS AS REQUIRED TO COMPENSATE FOR CABLE SLOPE ADJUSTMENT FOR BACKBONE CABLE FEEDS.
4. TERMINATE ALL UNUSED SPLITTER PORTS WITH 75 OHM TERMINATING RESISTORS.
5. MOUNT ALL DISTRIBUTION AMPLIFIERS WITH LONG SIDE (HEAT SINKS) IN THE DIRECTION OF VERTICAL, NOT HORIZONTAL, FOR PROPER HEAT DISPLACEMENT.
6. PROVIDE SPLITTERS/TAPS WITH RESISTIVE NETWORK CIRCUIT BOARDS IN LIEU OF FERRITE BEADS.
7. PROVIDE PROFESSIONAL GRADE FACTORY JUMPERS, RG-6 COAX WITH SCREW-ON ENDS, QUANTITY EQUAL TO NUMBERS OF TV OUTLETS SHOWN ON PLANS, PLUS 25% SPARE, LENGTH AS REQUIRED.
8. ALL INPUT CABLES SHALL NOT BE BUNDLED WITH OUTPUT CABLES. PHYSICAL SEPARATION BETWEEN INPUT AND OUTPUT CABLES SHALL BE MAINTAINED.
9. PROVIDE PLENUM RATED CABLING PER NFPA.
10. REFER TO FLOOR PLANS FOR ACTUAL DEVICE COUNTS.




## 2 CATV SINGLE LINE DIAGRAM

NOT TO SCALE

KEY NOTES:

1. RG-11 COAX TV CABLE, RUN CONTINUOUS WITH NO SPLICES OR COUPLERS.
2. PROFESSIONAL GRADE TAP, 8 OUTPUT, BLONDER-TONGUE SRT-8A OR EQUAL. MOUNT ON BACKBOARD. INSTALL TERMINATORS ON ALL UNUSED PORTS.
3. CATV DISTRIBUTION AMPLIFIER, VARIABLE GAIN AND SLOPE. MOUNT IN BACKBOARD, HOOK-UP, AND TUNE TO SYSTEM SETTINGS/VERIFY PROPER OPERATION.
4. SURGE PROTECTOR. MOUNT ON BACKBOARD AND ROUTE #6 GROUND TO GROUNDING BUSBAR.
5. RG-6 COAX TV CABLE, RUN CONTINUOUS WITH NO SPLICES OR COUPLERS.

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

6300 WEST BAY PKWY,
PANAMA CITY, FL 32409

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**SYSTEMS SINGLE LINE DIAGRAMS**

SHEET NUMBER

# T-3.0.1


LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM




1 T-4.0.1

## ENLARGED TELECOM ROOM 2101 - EQUIPMENT FLOOR PLAN

SCALE: 1/2"=1'-0"





2 T-4.0.1

## ENLARGED TELECOM ROOM 2101 - OVERHEAD TRAY PLAN

SCALE: 1/2"=1'-0"

KEY NOTES:

1. PLYWOOD BACKBOARD, 8'-0" WIDE X LENGTH AS SHOWN, MOUNTED ON WALLS INDICATED; MOUNT WITH BOTTOM AT 6" ABOVE FINISH FLOOR, COUNTERSINK ALL SCREWS. ROUGH ALL ELECTRICAL OUTLETS IN BACKBOARD FOR FLUSH MOUNT INSTALLATION OF FACEPLATES. BACKBOARDS SHALL BE 5/8" THICK A-C GRADE FIRE-RATED PLYWOOD, WITH "A" SIDE OUT, BEARING THE MANUFACTURER'S STAMP, WITH FIRE-RETARDANT BATTLESHIP GRAY PAINT.
2. SECONDARY BONDING BUSBAR (SBB), REFER TO TELECOM GROUNDING / BONDING DETAILS.
3. 2-POST EQUIPMENT RACK.
4. CABLE RUNWAY (WIDTH INDICATED). PROVIDE BUTT-SPLICE KIT TO BUTT-SPLICE SECTIONS, WALL ANGLE SUPPORT KITS, CEILING SUPPORT BRACKETS, AND JUNCTION SPLICE KITS OF CABLE RUNWAY. INSTALL ALL CABLE RUNWAY, FITTINGS, AND ACCESSORIES IN ACCORDANCE WITH MANUFACTURER'S PRINTED INSTRUCTIONS.
5. COMMUNICATIONS SERVICE/BACKBONE CABLING CONDUIT.




CABLE RUNWAY MOUNTING HEIGHT NOTE
BOTTOM OF CABLE RUNWAY MUST BE MOUNTED AT EXACTLY 7'-0" ABOVE THE FINISHED FLOOR TO ALLOW INSTALLATION OF 7'-0" HIGH RACKS (UNLESS NOTED OTHERWISE).

GENERAL CABLE RUNWAY NOTE
PROVIDE ALL FACTORY COMPONENTS MATCHING CABLE RUNWAY SPECIFIED FOR THE FOLLOWING:


BUTT-SPLICE KITS
TRIANGULAR WALL SUPPORTS
RADIUS BENDS
CABLE RUNWAY RADIUS DROPS
JUNCTION SPLICE KITS
ALL-THREAD SUPPORT BRACKETS
FOOT-MOUNTS
WALL-ANGLE SUPPORTS

INSTALL ALL CABLE RUNWAY AND RELATED FITTING AND ACCESSORIES ACCORDING TO THE MANUFACTURERS PRINTED INSRUCTIONS, UNLESS OTHERWISE NOTED.

3 T-4.0.1

## TYPICAL RUNWAY TO RACK SUPPORT DETAIL


NOT TO SCALE




4 T-4.0.1

## TYPICAL VERTICAL CABLE RUNWAY DETAIL

NOT TO SCALE




2' 0' 2' 4'
SCALE: 1/2"=1'-0"

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

ATLANTA
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

TALLAHASSEE
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY, PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022


DRAWING TITLE

**ENLARGED TELECOM ROOM FLOOR PLAN**

SHEET NUMBER

**T-4.0.1**

LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM




2 RACK ELEVATION
NOT TO SCALE

GENERAL NOTES:

1. QUANTITY OF PATCH PANELS SHOW IS ARBITRARY, CONFIRM OUTLET QUANTITIES WITH FLOOR PLANS.
2. FOR SINGLE LINE DIAGRAMS, REFER TO SHEET T3.0.1.
3. FOR ADDITIONAL REQUIREMENTS, REFER TO ENLARGED TELECOM, SHEET T4.0.1.

KEY NOTES:

1. STANDARD 7'-0"H x 19"W FLOOR MOUNT 2-POST RACK, COLOR BLACK. REFER TO SPECIFICATIONS.
2. FIBER OPTIC BACKBONE INTERCONNECT UNIT, RACK MOUNT.
3. CATEGORY 6 HORIZONTAL PATCH PANEL
4. VERTICAL RACK CABLING MANAGEMENT WITH FRONT & REAR SOLID DOORS, SIZE 3"W X 6"D X 7'H, COLOR BLACK.
5. HORIZONTAL CABLE MANAGER, 2RU, ON FRONT SIDE OF RACK WITH SOLID COVER TO CONCEAL CABLES.
6. 2200VA 120V INPUT RACK MOUNTED UPS.

CAUTION:
FIBER OPTIC CABLE
MDF.A/IDF.B F1-F24

PROVIDE SELF-LAMINATING WRITE-ON FIBER OPTIC CABLE MARKER RIGID (NON-ADHESIVE) TAG, PANDUIT PST-FO, WITH SELF-ADHESIVE LAMINATING LABLES (LASER PRINTED).

TYPICAL FIBER OPTIC CABLING TAG DETAIL
NOT TO SCALE


FIBER OPTIC BACKBONE NOMENCLATURE

MDF.A/IDF.B MMF1-F12
- TELCOM ROOM DESIGNATOR
- TELCOM ROOM DESIGNATOR
- BACKBONE CABLE AND STRAND ID

BACKBONE CABLE LABELING

LABEL ALL BACKBONE CABLES WITHIN 12" OF CABLE BREAKOUT POINT WITH PERMANENT MYLAR WRAP WRITE-ON MARKERS.

NAME FORMULA = ROOM NUMBER/ ROOM NUMBER, CABLE TYPE (F = FIBER) AND STRAND COUNT (STRANDS 1-12). EACH PANEL WILL CONTAIN A SPREADSHEET DETAILING WHAT STRAND OF CABLE CONNECTS TO WHAT PORT NUMBER.




TYPICAL FIBER BACKBONE CABLE CODING
FOR PATCH PANEL SERVING EACH TELECOMMUNICATIONS ROOM

© 2018 All reproduction & intellectual property rights reserved.

FITZGERALD COLLABORATIVE

**ATLANTA**
1201 W. PEACHTREE ST, SUITE 630
ATLANTA, GA 30309

**TALLAHASSEE**
850 S. GADSDEN ST, SUITE 140
TALLAHASSEE, FL 32301

FITZGERALD COLLABORATIVE GROUP, LLC.
AA26001957

DAG ARCHITECTS

ZHA

REVISION

| NO. | DESCRIPTION | DATE |
|---|---|---|
| 1 | ADDENDUM 3 | 05/10/2022 |

**PERMIT DOCUMENTS**

CLIENT

**NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT (ECP)**

NORTHWEST FLORIDA BEACHES INTERNATIONAL AIRPORT

PROJECT TITLE

**PANAMA CITY AIRPORT NWFBIA:**

# NORTH TERMINAL EXPANSION / IMPROVEMENTS

**6300 WEST BAY PKWY,**
**PANAMA CITY, FL 32409**

PROJECT NUMBER

NO. 210211

ISSUE DATE

05.10.2022

DRAWING TITLE

## RACK ELEVATION

SHEET NUMBER

# T-5.0.1

LOGAN TECHNOLOGY GROUP
918 HIGHWAY 98 EAST
DESTIN, FL 32541
O: 850.427.2140
F: 850.427.2141
WWW.LOGANTECHGROUP-LLC.COM