


Addendum No. 2 Date: March 11, 2024

Project:

NEW FIELD HOUSE FOR THE JUNIOR VARSITY AT CENTRAL HIGH SCHOOL FOR THE CLAY COUNTY BOARD OF EDUCATION LINEVILLE, ALABAMA



MCKEE PROJECT NO. 22.304 ALABAMA DIVISION OF CONSTRUCTION MANAGEMENT NO. 2024009

The following changes and/or substitutions to the plans and specifications are hereby made a part of same and are incorporated in full force as part of the contract.

Bidders shall acknowledge receipt of this Addendum in writing on the Proposal Form.

A2.1 GENERAL MODIFICATIONS:

- A. Refer to the **Advertisement for Bid** and **Change** as follows:
 - 1. A <u>Non-Mandatory Pre-Bid Conference</u> shall be held on <u>Friday, March 15, 2024, at 9:00</u> AM Central Time at the school.

A2.2 SPECIFICATION MODIFICATIONS:

A. Refer to Section 15700, HVAC, letter dated 03.11.24 from Zougvas, Eiring & Associates, herein

A2.3 DRAWING MODIFICATIONS:

- A. See the attached Revised Drawings as follows:
 - 1. Sheet(s) G1.1, A1.1, A1.10, A5.1, A6.1 and A6.2 (Revised 03.08.24), here.
 - 2. Sheet(s) C1, C2, C3, and C4 (revised 03.08.24), herein.

A2.4 CLARIFICATIONS & RESPONSES:

A. See the following responses to RFI questions received from Contractors.

Question: NONE.

Answer:

- B. See the following clarifications as follows:
 - 1. NONE.

END OF ADDENDUM



New Fieldhouse for the Junior Varsity at Central High School

March 11, 2024



- 1) Refer to the Plans Sheet P2 and note the revised plumbing plan requirements.
- 2) Refer to the Plans Sheet M1 and note the deletion of sheet metal ductwork in the Training Room 101. Provide DuctSox as specified below.

PART 17. FABRIC AIR DISPERSION (DUCTSOX)

- 17.1. General: Non-metal ductwork, as shown on the plans, consisting of a noncondensing, fabric air dispersion product assembly. Product shall be classified by Underwriter's Laboratories and shall have a fire hazard rating not to exceed 25 for flame spread and 50 for fuel contributed and smoke developed as determined by ASTM E84. NFPA 90-A and are also classified in accordance with ICC Evaluation Service AC167 and UL 2518. All product sections must be labeled with the logo and classification marking of Underwriter's Laboratories. Manufacturer shall have and submit documented design support information including duct sizing, vent and orifice location, vent and orifice sizing, length, and suspension. Parameters for design, including maximum air temperature, velocity, pressure and fabric permeability, shall be considered and documented. Tensioning system shall be an IHS internal hoop system consisting of internal 360-degree hoop system spaced on 5'-0" centers for 95% full round tension in any airflow mode. System shall be installed with a one row suspension system located 1.5" above top-dead-center of the textile system. System attachment to cable or U-Track shall be made using Gliders spaced 12 inches. Provide 316 Stainless Steel components including coupler assembly. vertical cable support and Gripple quick cable connector. System shall be designed by the fabric air dispersion system Manufacturer to provide a maximum NC 35 sound rating at 6 feet above the floor. Provide all items necessary and required for a complete, finished and properly functioning installation. Duct Sox shall be provided with custom color, custom logo and custom wording. The Architect shall select color, wording and logo. Basis of design is DuctSox Verona. Equivalents by Durkee Sox Nano Model NSL with IRR support system, Prihoda or Fabric Air will be considered.
- **17.2.** <u>Textile Air Dispersion System:</u> Air diffusers shall be constructed with a metallic internal tensioning and skeletal system and of a woven fire retardant fabric that shall

be 100% flame retardant and treated with a machine wash-able anti-microbial agent from the Manufacturer. Fabric shall be a minimum of 6.8 oz. /sq. vd. per ASTM D3776 with custom color as selected by the Architect. The fabric shall operate within a temperature range of 0 degrees F to 180 degrees F. Fabric shall be coated with an antimicrobial agent shall be proven 99% effective after 10 laundry cycles per AATCC Test Method 100. Air dispersion shall be accomplished by vent nozzles as shown on the plans. Linear vent is to consist of an array of open orifices rather than a mesh style vent. Inlet connection to metal duct shall be via zip screw fastener. Inlet connection shall include zipper for easy removal and maintenance. System shall include adjustable flow devices to balance turbulence, airflow and distribution as needed. Flow restriction device shall include ability to adjust the airflow resistance from 0.06 – 0.60 in W.G. static pressure. End cap shall include zipper. Fabric system shall include connectors to accommodate suspension system listed. Each section of the textile shall include identification labels documenting order number, section diameter, section length, piece number, code certifications and other pertinent information. Any deviation from a straight run shall be made using a gored elbow or a high efficiency tee. Normal 90-degree elbows are five gores, and the radius of the elbow is 1.5 times the diameter of the DuctSox. Fabric diffusers shall be designed from 0.25" water gauge minimum to 3.0" maximum, with 0.5" as the standard. System overall design: diameter, length, airflow, operating static pressure and dispersion shall be designed and approved by the Manufacturer. Textile shall be warranted for 10 years.

- 17.3. Shop Drawings: Manufacturer shall submit for review, shop drawings indicating all sizing, fittings, attachments, dispersion pattern, etc. to achieve proper airflow at the design cfm and mounting height required for comfort and NC criteria specified. Provide sound analysis with submittal verifying NC ratings specified. Provide drawings indicating system design and certified performance rating. Additionally, supplier of the fabric sox material shall submit factory drawings, for review, showing the vent hole configuration with number and size of air outlet holes and spacing angles to adequately supply air to the floor based on the mounting height and locations of the fabric sox within each space.
- **17.4.** <u>Warranty:</u> Manufacturer must provide a 15-Year Product Warranty for products supplied for the fabric portion of this system as well as a Design and Performance Warranty

END OF ADDENDUM

NOTICE

FOR YOUR SAFETY

EDUCATIONAL

MAXIMUM

OCCUPANCY OF:

68

PERSONS


THIS IS NOT AN ASSEMBLY OCCUPANCY AND CANNOT ALLOW

SPECTATORS TO OCCUPY THIS FACILITY BY ORDER OF

THE CODE OFFICIAL

Keep Posted Under Penalty Of Law

THIS IS AN



SYMBOL

DESCRIPTION

PRIMARY BUILDING EXIT

TD

TD

TRAVEL DISTANCE NEAREST TO EXIT

HANDICAP ACCESSIBLE

FE

FIRE EXTINGUISHER LOCATION (SEE DETAIL AX.X)

ACTUAL OCCUPANT LOAD SERVED TOTAL EGRESS CAPACITY

3/4

HOUR

RATED DOOR ASSEMBLY

VARSIT

HOUSE

DUCATION

CODE REVIEW CODE: 2021 INTERNATIONAL BUILDING CODE OCCUPANCY TYPE: GROUP 'E' SPRINKLERED: NO NUMBER OF STORIES: 1 CONSTRUCTION TYPE: TYPE VB TYPE VB, REQUIRES THE FOLLOWING FIRE RESISTANCE (TABLE 601): STRUCTURAL FRAME: 0 HOUR EXTERIOR BEARING WALLS: 0 HOUR INTERIOR BEARING WALLS: 0 HOUR EXTERIOR NONBEARING WALLS: 0 HOUR INTERIOR NONBEARING WALLS: 0 HOUR FLOOR CONSTRUCTION: 0 HOUR ROOF CONSTRUCTION: 0 HOUR OTHER REQUIREMENTS: FIRE WALL RATING (TABLE 706.4): NA OCCUPANCY SEPARATION (TABLE 508.4): NA INCIDENTAL USE AREAS (TABLE 509): NA CORRIDORS (TABLE 1020.1): CORRIDORS SERVING MORE THAN 30 OCCUPANTS IN UNSPRINKLERED 'E' OCCUPANCY SHALL HAVE A 1-HOUR WALL. **NA** STAIRS & SHAFT ENCLOSURES (707 & TABLE 707.3.10 NOT LEES THAN 508.4 IF APPLICABLE): **NA** SINGLE OCCUPANCY FIRE BARRIERS (TABLE 707.3.10): **NA** EXIT ACCESS TRAVEL DISTANCE IS **200** FEET FOR **E** NON SPRINKLERFED (TABLE 1017.2)

_	
	EXIT CALCULATIONS
	TOTAL BUILDING AREA
	OCCUPANCY TYPE - GROUP 'E' BUILDING TYPE: VB ALLOWABLE SF: 9,500 SQ FT (TABLE 506.2) ACTUAL SF - 4,800 SQ FT 1
	ALLOWABLE HEIGHT (TABLE 504.3) ALLOWABLE # OF STORIES (TABLE 504.4) ALLOWABLE HEIGHT: 40 FT ALLOWABLE NO. OF STORIES: 1 ACTUAL BUILDING HEIGHT: 122 FT ACTUAL NO. OF STORIES: 1
	OCCUPANT LOAD
	OCCUPANT LOAD TOTAL (1004 & TABLE 1004.5) = 68 PERSONS
	EXIT REQUIREMENTS
	EXIT ACCESS (TABLE 1006.2.1 & TABLE 1006.3.3) NO. OF EXITS REQUIRED: 2 NO. OF EXITS FURNISHED: 4
	MEANS OF EGRESS WIDTH (1005.3) SEE PLAN FOR EXIT WIDTHS
	MINIMUM CORRIDOR WIDTH (TABLE 1020.3) NA

PLUMBING CALCULATIONS

021 INTERNATIONAL PLUMBING CODE EQUIREMENTS:
CCUPANT LOAD TOTAL = 68 PERSONS

TOILETS (TABLE 2902.1)

MEN'S (1 PER 50 OCC.) (34 OCC.): 1 REQUIRED 3 PROVIDED

WOMEN'S (1 PER 50 OCC.) (34 OCC.): 1 REQUIRED 3 PROVIDED

LAVATORIES (TABLE 2902.1)

MEN'S (1 PER 50 OCC.) (34 OCC.): 1 REQUIRED 2 PROVIDED

WOMEN'S (1 PER 50 OCC.) (34 OCC.): 1 REQUIRED 2 PROVIDED

DRINKING FOUNTAINS (TABLE 2902.1)

(1 PER 100 OCC.) (68 OCC.): 2 REQUIRED 2 PROVIDED

SERVICE SINK (TABLE 2902.1): 1 REQUIRED 1 PROVIDED

SHEET TITLE : CODE PLAN

MCKEE JOB # : 22-304

.WN BY : GAC

DATE: 02.15.2024

REVISED DATE: 1 03.08.24

REVISED DATE:

REVISED DATE:

CODE PLAN

SCALE: 1/8" = 1'-0"

HEET NO · G1.

MALTER T. MCKEE, JR. S. No. 1082

0

QN SOLVE



New Fieldhouse for the Junior Varsity at Central High School

March 11, 2024



- 1) Refer to the Plans Sheet P2 and note the revised plumbing plan requirements.
- 2) Refer to the Plans Sheet M1 and note the deletion of sheet metal ductwork in the Training Room 101. Provide DuctSox as specified below.


PART 17. FABRIC AIR DISPERSION (DUCTSOX)

- 17.1. General: Non-metal ductwork, as shown on the plans, consisting of a noncondensing, fabric air dispersion product assembly. Product shall be classified by Underwriter's Laboratories and shall have a fire hazard rating not to exceed 25 for flame spread and 50 for fuel contributed and smoke developed as determined by ASTM E84. NFPA 90-A and are also classified in accordance with ICC Evaluation Service AC167 and UL 2518. All product sections must be labeled with the logo and classification marking of Underwriter's Laboratories. Manufacturer shall have and submit documented design support information including duct sizing, vent and orifice location, vent and orifice sizing, length, and suspension. Parameters for design, including maximum air temperature, velocity, pressure and fabric permeability, shall be considered and documented. Tensioning system shall be an IHS internal hoop system consisting of internal 360-degree hoop system spaced on 5'-0" centers for 95% full round tension in any airflow mode. System shall be installed with a one row suspension system located 1.5" above top-dead-center of the textile system. System attachment to cable or U-Track shall be made using Gliders spaced 12 inches. Provide 316 Stainless Steel components including coupler assembly. vertical cable support and Gripple quick cable connector. System shall be designed by the fabric air dispersion system Manufacturer to provide a maximum NC 35 sound rating at 6 feet above the floor. Provide all items necessary and required for a complete, finished and properly functioning installation. Duct Sox shall be provided with custom color, custom logo and custom wording. The Architect shall select color, wording and logo. Basis of design is DuctSox Verona. Equivalents by Durkee Sox Nano Model NSL with IRR support system, Prihoda or Fabric Air will be considered.
- **17.2.** <u>Textile Air Dispersion System:</u> Air diffusers shall be constructed with a metallic internal tensioning and skeletal system and of a woven fire retardant fabric that shall

be 100% flame retardant and treated with a machine wash-able anti-microbial agent from the Manufacturer. Fabric shall be a minimum of 6.8 oz. /sq. vd. per ASTM D3776 with custom color as selected by the Architect. The fabric shall operate within a temperature range of 0 degrees F to 180 degrees F. Fabric shall be coated with an antimicrobial agent shall be proven 99% effective after 10 laundry cycles per AATCC Test Method 100. Air dispersion shall be accomplished by vent nozzles as shown on the plans. Linear vent is to consist of an array of open orifices rather than a mesh style vent. Inlet connection to metal duct shall be via zip screw fastener. Inlet connection shall include zipper for easy removal and maintenance. System shall include adjustable flow devices to balance turbulence, airflow and distribution as needed. Flow restriction device shall include ability to adjust the airflow resistance from 0.06 – 0.60 in W.G. static pressure. End cap shall include zipper. Fabric system shall include connectors to accommodate suspension system listed. Each section of the textile shall include identification labels documenting order number, section diameter, section length, piece number, code certifications and other pertinent information. Any deviation from a straight run shall be made using a gored elbow or a high efficiency tee. Normal 90-degree elbows are five gores, and the radius of the elbow is 1.5 times the diameter of the DuctSox. Fabric diffusers shall be designed from 0.25" water gauge minimum to 3.0" maximum, with 0.5" as the standard. System overall design: diameter, length, airflow, operating static pressure and dispersion shall be designed and approved by the Manufacturer. Textile shall be warranted for 10 years.

- 17.3. Shop Drawings: Manufacturer shall submit for review, shop drawings indicating all sizing, fittings, attachments, dispersion pattern, etc. to achieve proper airflow at the design cfm and mounting height required for comfort and NC criteria specified. Provide sound analysis with submittal verifying NC ratings specified. Provide drawings indicating system design and certified performance rating. Additionally, supplier of the fabric sox material shall submit factory drawings, for review, showing the vent hole configuration with number and size of air outlet holes and spacing angles to adequately supply air to the floor based on the mounting height and locations of the fabric sox within each space.
- **17.4.** <u>Warranty:</u> Manufacturer must provide a 15-Year Product Warranty for products supplied for the fabric portion of this system as well as a Design and Performance Warranty

END OF ADDENDUM



SCREEN WALL

23'-0"

FLOOR PLAN
SCALE: 1/8" = 1'-0"

DOOR SCHEDULE													
DOOR#	WIDTH	HEIGHT	THICKNESS	MATERIALS	DOOR TYPE	DOOR FINISH	FRAME TYPE	FRAME FINISH	LABEL	DET HEAD	AILS JAMB	SIGNAGE	REMARKS
101a	(2)3'-0"	7'-0"	1 3/4"	ALUMINUM STOREFRONT	Α	FACTORY	AS1	FACTORY		5/A2.1	3&4/A2.1		
101b	(2)3'-0"	7'-0"	1 3/4"	ALUMINUM STOREFRONT	А	FACTORY	AS1	FACTORY		5/A2.1	3&4/A2.1		
101c	(2)3'-0"	7'-0"	1 3/4"	ALUMINUM STOREFRONT	Α	FACTORY	AS1	FACTORY		5/A2.1	3&4/A2.1		
102	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	С	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	BOY'S	
103	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	В	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	OFFICE	
104	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	С	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	JANITOR	
105	(2)3'-0"	7'-0"	1 3/4"	ALUMINUM STOREFRONT	Α	FACTORY	AS1	FACTORY		5/A2.1	3&4/A2.1		
106	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	С	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	MECHANICAL	
107	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	С	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	DATA	
108	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	С	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	GIRL'S	
109	3'-0"	7'-0"	1 3/4"	FLUSH WOOD SOLID CORE	С	FACTORY	HM1	PAINT		2/A2.1	1/A2.1	ELECTRICAL	
	101a 101b 101c 102 103 104 105 106 107 108	101a (2)3'-0" 101b (2)3'-0" 101c (2)3'-0" 102 3'-0" 103 3'-0" 104 3'-0" 105 (2)3'-0" 106 3'-0" 107 3'-0" 108 3'-0"	101a (2)3'-0" 7'-0" 101b (2)3'-0" 7'-0" 101c (2)3'-0" 7'-0" 102 3'-0" 7'-0" 103 3'-0" 7'-0" 104 3'-0" 7'-0" 105 (2)3'-0" 7'-0" 106 3'-0" 7'-0" 107 3'-0" 7'-0" 108 3'-0" 7'-0"	101a (2)3'-0" 7'-0" 1 3/4" 101b (2)3'-0" 7'-0" 1 3/4" 101c (2)3'-0" 7'-0" 1 3/4" 102 3'-0" 7'-0" 1 3/4" 103 3'-0" 7'-0" 1 3/4" 104 3'-0" 7'-0" 1 3/4" 105 (2)3'-0" 7'-0" 1 3/4" 106 3'-0" 7'-0" 1 3/4" 107 3'-0" 7'-0" 1 3/4" 108 3'-0" 7'-0" 1 3/4"	101a (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT 101b (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT 101c (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT 102 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE 103 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE 104 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT 106 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE 107 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE 108 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE 109 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE	DOOR # WIDTH HEIGHT THICKNESS MATERIALS TYPE 101a (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 101b (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 101c (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 102 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C 103 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C 104 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 106 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 106 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 107 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A 108	DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE FINISH 101a (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 101b (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 101c (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 102 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C FACTORY 103 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C FACTORY 104 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 106 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 107 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY 106 3'-0" 7'-0" 1 3/4" FLUSH WOOD	DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE DOOR FINISH FINISH TYPE 101a (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 101b (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 101c (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 102 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C FACTORY HM1 103 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C FACTORY HM1 104 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY HM1 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY HM1 106 3'-0" 7'-0" 1 3/4" FLUSH WOOD C FACTORY HM1 107 3'-0" 7'-0" 1 3/4" FLUSH WOOD <th>DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE DOOR FINISH FINISH TYPE FRAME FINISH FINISH FINISH 101a (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 101b (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 101c (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 102 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 103 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE B FACTORY HM1 PAINT 104 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C FACTORY HM1 PAINT 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY HM1 PAINT 106 3'-0" 7'-0" 1 3/4" FLUS</th> <th>DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE DOOR FINISH FACTORY LABEL FINISH FACTORY </th> <th> DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE FINISH TYPE FINISH LABEL HEAD </th> <th> DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE FINISH TYPE FINISH LABEL DETAILS </th> <th> DOOR # WIDTH</th>	DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE DOOR FINISH FINISH TYPE FRAME FINISH FINISH FINISH 101a (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 101b (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 101c (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 102 3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY AS1 FACTORY 103 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE B FACTORY HM1 PAINT 104 3'-0" 7'-0" 1 3/4" FLUSH WOOD SOLID CORE C FACTORY HM1 PAINT 105 (2)3'-0" 7'-0" 1 3/4" ALUMINUM STOREFRONT A FACTORY HM1 PAINT 106 3'-0" 7'-0" 1 3/4" FLUS	DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE DOOR FINISH FACTORY LABEL FINISH FACTORY	DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE FINISH TYPE FINISH LABEL HEAD	DOOR # WIDTH HEIGHT THICKNESS MATERIALS DOOR TYPE FINISH TYPE FINISH LABEL DETAILS	DOOR # WIDTH

SIGN MOUNTING HEIGHT

703.4.1 HEIGHT ABOVE FINISH FLOOR OF GROUND
TACTILE CHARACTERS ON SIGNS SHALL BE LOCATED 48 INCHES (1220 mm) MINIMUM ABOVE THE FINISH FLOOR OR GROUND SURFACE, MEASURED FROM THE BASELINE OF THE LOWEST TACTILE CHARACTER AND 60 INCHES (1525 mm) MAXIMUM ABOVE FINISH FLOOR OR GROUND SURFACE, MEASURED FROM THE BASELINE OF THE HIGHEST TACTILE CHARACTER.

EXCEPTION: BRAILLE PROVIDED ON ELEVATOR CAR CONTROLS SHALL BE SEPARATED ¾6 INCHES (4.8 mm) MINIMUM AND SHALL BE LOCATED EITHER DIRECTLY BELOW OR ADJACENT TO THE CORRESPONDING RAISED CHARACTERS OR SYMBOLS.


703.4.2 LOCATION
WHERE A TACTILE SIGN IS PROVIDED AT A DOOR, THE SIGN SHALL BE LOCATED ALONGSIDE THE DOOR AT THE LATCH SIDE. WHERE A TACTILE SIGN IS PROVIDED AT DOUBLE DOORS WITH ONE ACTIVE LEAF, THE SIGN SHALL BE LOCATED ON THE INACTIVE LEAF. WHERE A TACTILE SIGN IS PROVIDED AT DOUBLE DOORS WITH TWO ACTIVE LEAFS, THE SIGN SHALL BE LOCATED TO THE RIGHT OF THE RIGHT HAND DOOR. WHERE THERE IS NO WALL SPACE AT THE LATCH SIDE OF A SINGLE DOOR OR AT THE RIGHT SIDE OF DOUBLE DOORS, SIGNS SHALL BE LOCATED ON THE NEAREST ADJACENT WALL. SIGNS CONTAINING TACTILE CHARACTERS SHALL BE LOCATED SO THAT THE CLEAR FLOOR SPACE OF 18 INCHES (455 mm) MINIMUM, CENTERED ON THE TACTILE CHARACTERS, IS PROVIDED BEYOND THE ARC OF ANY DOOR SWING BETWEEN THE CLOSEST POSITION AND 45 DEGREE OPEN POSITION. EXCEPTION: SIGNS WITH TACTILE CHARACTERS SHALL BE PERMITTED ON THE PUSH SIDE OF DOORS WITH CLOSERS AND WITHOUT HOLD-OPEN DEVICES.

SIGNAGE NOTES:


FURNISH INDIVIDUAL PLASTIC LAMINATE SIGNAGE SYSTEM WITH ROOM OR OCCUPANT'S NAME AND ROOM NUMBER. FINAL WORDING TO BE FURNISHED WHEN SHOP DRAWINGS FOR SIGNAGE SYSTEM ARE SUBMITTED. FURNISH INDIVIDUAL PLASTIC LAMINATE RESTROOM SIGNS FOR DOOR(S) AND HANDICAPED ACCESS SIGN TO BE PLACED ON WALL BESIDE RESTROOM DOOR(S) -SEE DIAGRAM.

LABELED DOOR AND FRAME NOTE:


HOURLY RATING DESIGNATIONS AND / OR ALPHABETICAL LETTER DESIGNATIONS ARE GIVEN WHERE PROTECTED OPENINGS ARE REQUIRED IN RATED PARTITIONS. THESE OPENING PROTECTIVE ASSEMBLIES SHALL INCLUDE THE FRAME, DOOR, HARDWARE, CLOSING DEVICE, SILL AND ANCHORAGE. CONTRACTOR SHALL SEE THAT NO COMPONENT IS OMITTED OR SUBSTANDARD QUALITY USED SUCH THAT THE EFFECTIVENESS OF THE ENTIRE OPENING AS A FIRE OR SMOKE BARRIER MIGHT BE JEOPARDIZED. DOORS AND FRAMES SHALL BE FURNISHED WITH UNDERWRITER'S LABORATORIES OR WARNOCKHERSEY LABELS WITH APPROPRIATE FIRE RESISTANCE RATINGS FOR THE CLASS OF OPENING SCHEDULED. SUBJECT TO DOOR MANUFACTURER'S PROCEDURAL LIMITATIONS, LABELS SHOULD BEAR THE FOLLOWING NOTATION: "FIRE DOOR, TO BE EQUIPPED WITH FIRE EXIT HARDWARE"




SIGNAGE




Location of Tactile Signs at Doors



TYPICAL DOOR TYPES SCALE: 1/4" - 1'-0"




TYPICAL FRAME TYPES



A		B
HOLLOW METAL	HC	DLLOW METAL
TYPICAL	WINDOW	TYPES
SCALE: 1/4" - 1'-0"		

GLAZING SCHEDULE						
SYMBOL	DESCRIPTION					
CT	CLEAR TEMPERED					
IG	INSULATING GLASS					
TT	TINTED TEMPERED					




EXISTING

BUILDING

- EXISTING

SCREEN WALL



SCREEN WALL DETAIL

SCALE: 3/4" = 1'-0"

FLOOR PLAN - PART "X"

ATION

0

 ω_z

JUNIOR

HOUS

MCKEE JOB #: 22-304

DRAWN BY: DATE: 02.15.2024

REVISED DATE: (1) 03.08.24

REVISED DATE: REVISED DATE:


SHEET NO.: A1.1

BB

A5.1

-(DSB)

SCREEN WALL






FLOOR PLAN LEGEND					
<u>SYMBOL</u>	<u>DESCRIPTION</u>				
CORRIDOR	SCHEDULED ROOM NAME AND NUMBER				
P-	WALL PARTITION TYPES				
X AX.X X	INTERIOR ELEVATION SYMBOL				
(WHR)	WALL MOUNTED METAL HANDRAIL - PAINT				
HGR	METAL HANDRAIL / GUARDRAIL - PAINT				
GR	METAL GUARDRAIL - PAINT				

ACCESSIBLE SHOWER NOTES

- A FOLDING SEAT SHALL BE PROVIDED IN EACH ACCESSIBLE SHOWER STALL AND SHALL BE MOUNTED 17"-19" FROM THE SHOWER FLOOR AND SHALL EXTEND THE FULL DEPTH OF THE SHOWER STALL (SEE SPECS) SEAT SHALL BE MOUNTED SECURELY AND SHALL NOT SLIP DURING USE.
- A SHOWER SPRAY UNIT WITH A HOSE AT LEAST 60" LONG THAT CAN BE USED AS A FIXED SHOWER HEAD OR AS A HAND-HELD SHOWER SHALL BE PROVIDED (SEE SPECS)
- ALL CONTROLS, SHOWER HEADS ETC SHALL BE LOCATED ON OPPOSITE WALL FROM SHOWER SEAT (SEE ELEVATIONS FOR MOUNTING HEIGHTS)
- ONE ACCESSIBLE SHOWER STALL SHALL BE PROVIDED AT EACH TOILET/SHOWER ROOM (SEE PLAN FOR LOCATION). SECOND STALL TO BE A STANDARD SHOWER WITH A FIXED SHOWER HEAD. GRAB BARS AND SHOWER SEAT WILL NOT BE REQUIRED.



ACCESSIBLE SHOWER ELEVATIONS SCALE: 1/4" - 1'-0"

ACCESSIBLE SHOWER PLAN SCALE: 1/2" - 1'-0"

ENLARGED PLANS AND DETAILS

DUCATION

0

QN SO SO SO


MCKEE JOB #: 22-304

DRAWN BY:

DATE: 02.15.2024 1 03.08.24

REVISED DATE: REVISED DATE:

SHEET NO.: **A1.10**



BUILDING SECTION LEGEND

SYMBOL

CMUP

CONCRETE MASONRY UNIT - PAINT

CMU

CONCRETE MASONRY UNIT - NO PAINT

MWP

METAL WALL PANELS

GBP

GYPSUM BOARD - PAINT

GBP

IMPACT RESISTANT GYPSUM BOARD - NO PAINT

IGB

IMPACT RESISTANT GYPSUM BOARD - PAINT

MGBP

MOISTURE RESISTANT GYPSUM BOARD - PAINT

MGB

MOISTURE RESISTANT GYPSUM BOARD - NO PAINT

MFTAL LINER PANELS

PLYP

PLYWOOD - PAINTED

NEW FIELDHOUSE FOR THE JUNIOR VARSITY

CENTRAL HIGH SCHOOL

EDUCATION

S WALTER T. Mc. 1085
No. 1085
No. 1085

0

ET TITLE : BUILDING SECTION

MCKEE JOB # : 22-304

DRAWN BY: GAC

DATE: 02.15.2024

REVISED DATE: 1 03.08.24

REVISED DATE:

^ - -

SHEET NO.: A5.1

- Z:\2022\22-304 New Fieldhouse for the Junior Varsity for the Clay County\CAD Drawings\Architectural\A6.1 Wall Sectic - Tuesday, March 5, 2024 10:52:28 AM

- Z:\2022\22-304 New Fieldhouse for the Junior Varsity for the Clay County\CAD Drawings\Architectural\A6.2 Wall Sections.dwg

SHEET NO. : S1.1

FRAMING PLANS

GAC

02.15.2024

- S:\MCKEE\Central High School Junior Varsity Field House - Lineville Al\S-Central High School JV Fieldhouse - Sections.dwg