



300 CHASE PARK SOUTH • SUITE 200 • HOOVER, ALABAMA 35244
205-988-9112

ADDENDUM NO. 3
ADDITIONS AND ALTERATIONS TO HOMER SMILES STADIUM
Architect Job No. 23-125
September 17, 2024
DCM # 20240208

BIDS DUE:

Tuesday, September 24, 2024, until
2:00 p.m., local time, held at
Leeds City Board of Education
1517 Hurst Ave. NE
Leeds, AL 35094

NON-MANDATORY PRE-BID MEETING:

Thursday, September 19, 2024, at
2:00 p.m., local time, held at
Leeds City Board of Education, Conference Room
1517 Hurst Ave. NE
Leeds, AL 35094

The Plans and Specifications are hereby amended. The following supersedes all contrary and/or conflicting information and is made part of the contract documents.

GENERAL

1. There will be a **NON-MANDATORY PRE-BID MEETING** held on **Thursday, September 19, 2024**. All general contractors who intend to bid on this project are encouraged to attend.

SPECIFICATIONS

1. **ADD Section 105116 – Wood Sport, Athletic Lockers** in its entirety.
2. **Section 01030 – Special Project Requirements** **REVISE** as follows:

TIME FOR COMPLETION

All work under this Contract shall be complete and ready for Owner occupancy by **NOVEMBER 28, 2025**. The work under this contract shall commence within Ten (10) calendar days from date of Notice To Proceed.

CLARIFICATIONS

1. The Synthetic Turf spec. included in the project's specifications is for the plaza area only. The turf on the football field is to remain as is.

SECTION 105116 - WOOD SPORT, ATHLETIC LOCKERS

1.0 - GENERAL

- 1.1 Related Documents
 - A. General Conditions
 - B. Division One
- 1.2 Scope Of Work
 - A. Description: Furnish and install Custom Wood Sports Lockers, complete, as shown and specified per contract documents.
- 1.3 Related Work Specified Elsewhere:
 - A. Concrete: Section 03320
 - B. Rough Carpentry: Section 06100
 - C. Finish Carpentry: Section 06210
- 1.4 Submittals
 - A. Refer to Section 01350 - Submittals
 - B. Shop Drawings: Submit drawings showing locker types, sizes, quantities, layouts, anchoring, trim attachments, and work by others.
 - C. Color Charts: Provide color charts showing manufacturer's available finishes. Provide samples if requested.
 - D. Numbering: If number tags are required, locker numbering sequence will be provided by the approving authority and noted on approved shop drawings returned to the locker contractor.
- 1.5 Quality Assurance
 - A. Manufacturing Standard: Provide wood lockers that are standard products of a single manufacturer, with interchangeable like parts. Include necessary mounting accessories, fittings, and fastenings.
 - B. Fabricator Qualifications: Experience (**minimum 5 years**) in the fabrication of like products for use in similar environments, including project size, with the manufacturing capacity to meet the construction schedule.
 - C. Installer Qualifications: Experienced (minimum 2 years) installer who is authorized and trained by manufacturer to install this type of wood lockers project.
- 1.6 Product Handling
 - A. All work shall be fabricated in ample time to not the delay construction process.
 - B. All materials shall be delivered to the site at such a time as required for proper coordination of the work. Materials are to be received in the manufacturer's original, unopened packages.
 - C. Store all materials in a dry, temperature-controlled space.

1.7 Guarantee

WARRANTY:

- A. Submit upon completion of the work, manufacturer's standard warranty to repair or replace locker components that fail in materials or workmanship for a period of 3 years from the date of substantial completion.
- B. This Warranty excludes damage resulting from abuse or vandalism and does not extend to mechanical or electrical component parts made by others (i.e. fans, lights, locks and other similar items) or consumable components (i.e. bulbs, batteries and other similar items).

2.0 - PRODUCTS

2.1 Manufacturers

- A. Subject to compliance with the design, material, method of fabrication and installation as required in this specification section or modified as shown on drawings. Manufacturers offering products which may be incorporated in the work provided they meet the spec include the following:
H&H Enterprise. (Basis of Design)
List Industries, Inc. "Recruiter II"
Hollman, "Athletic Wood Lockers"
- B. Other Locker manufacturers may submit for preapproval at least 10 days prior to bid. Comply with Section 01360.

2.2 Locker Types

- A. Type 1 – (Varsity 111): Lockers shall be "ENDURANCE PRO OPEN FRONT LOCKERS" as manufactured by H&H Enterprise or approved equal.

Wood Lockers: (Open Front)

- 1. Type: Single Tier
- 2. Size: 24" wide x 18" deep x 72" high
- 3. Upper 12" Security Box with soft close hinges
- 4. Lower seat with padded, vinyl covered seat cushion, soft-close sliding drawer and pull
- 5. Locker Body, Sides, Tops, Bottoms, Upper Shelf, and Backs: Shall be $\frac{3}{4}$ " Domestic furniture grade B plain slice maple hardwood or veneer throughout finished with catalyzed, clear, 3 coat cabinet lacquer. Sides to be bow front style. Cores made of Fiberboard or Particleboard will not be accepted.
- 6. Locker Trim: Face trim and seat front nosing shall be T-style, ABS bumper molding. Personal effects locker doors, seat hinge support blocking, and seat support cleats to be fabricated from maple lumber.
- 7. Hinges: European, soft close hinges.
- 9. Locker Base: 4" concrete curb by others.

10. Type 1 – ADA Locker: to be configured with open, upper shelf with security box positioned on lower seat.

B. Type 2 – (Baseball 107):: Lockers shall be "ENDURANCE PRO OPEN FRONT **LOCKERS**" as manufactured by H&H Enterprise or approved equal.

Wood Lockers: (Open Front)

1. Type: Single Tier

2. Size: 18" wide x 18" deep x 72" high

3. Upper 12" Security Box with soft close hinges

4. Lower seat with soft-close sliding drawer and pull

5. Locker Body, Sides, Tops, Bottoms, Upper Shelf, and Backs: Shall be $\frac{3}{4}$ " Domestic furniture grade B plain slice maple hardwood or veneer throughout finished with catalyzed, clear, 3 coat cabinet lacquer. Sides to be bow front style. Cores made of Fiberboard or Particleboard will not be accepted.

6. Locker Trim: Face trim and seat front nosing shall be T-style, ABS bumper molding. Personal effects locker doors, seat hinge support blocking, and seat support cleats to be fabricated from maple lumber.

7. Hinges: European, soft close hinges.

9. Locker Base: 4" concrete curb by others.

10. Type 2 – ADA Locker: to be configured with open, upper shelf with security box positioned on lower seat/shelf.

C. Type 3 – (Soccer 105; Locker Room 108):: Lockers shall be "ENDURANCE PRO DOORED **LOCKERS**" as manufactured by H&H Enterprise or approved equal.

Wood Lockers:

1. Type: Double Tier

2. Size: 18" wide x 18" deep x 36/72" high

3. Doors: 5 piece Solid Maple Hardwood with 2 stiles, 2 rails, and 1 panel.

4. Locker Body, Sides, Tops, Bottoms, Upper Shelf, and Backs: Shall be $\frac{3}{4}$ " Domestic furniture grade B plain slice maple hardwood or veneer throughout finished with catalyzed, clear, 3 coat cabinet lacquer. Cores made of Fiberboard or Particleboard will not be accepted.

5. Locker Trim: to be 3mm maple edging.

6. Hinges: European, soft close hinges.

7. Locker Base: 4" concrete curb by others.

8. Type 3 – ADA Locker: shelves, hooks, rods, etc to be relocated between 15" – 48" a.f.f.

2.3 Fabrication

A. Materials:

1. Shall be ¾" Domestic furniture grade B plain sliced maple hardwood or veneer throughout finished with catalyzed, clear, 3 coat cabinet lacquer.
2. Fasteners: Cadmium, zinc or nickel plated steel; bolt heads, slotless type; self locking nuts or lock washers.
3. Hardware: Hooks and hang rods of cadmium plated or zinc plated steel or cast aluminum. Clothes hang bar to be of stainless steel or chrome plated steel.
4. Name Plates: To be LED back lit plexiglass with removable, interchangeable acrylic name plates.

2.4 Locker Accessories/Equipment: Type 1

- A. Provide Padlock Hasp: Locker by owner
- B. Equipment: Furnish each locker with one hat shelf, two double prong coat hooks on locker sides or 1" O.D. coat rod, factory attached below upper hat shelf.

3.0 - EXECUTION

3.1 Installation

- A. General: Installation shall be in strict conformance with referenced standards, the manufacturer's written directions, as shown on the drawings and as herein specified.
- B. Conditions: Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside the manufacturer's recommendations.
- C. Placement: Lockers shall be set in place, plumb, level, rigid, flush and securely attached to the wall (or bolted together if back-to-back) and anchored to the floor or base according to manufacturer's specifications.

3.2 Adjustment

Upon completion of installation, inspect lockers and adjust as necessary for proper door operation. Touch-up scratches and abrasions to match original finish.

END OF SECTION