FINISH SCHEDULE - CBOC

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALL FINISH NORTH	WALL FINISH SOUTH	WALL FINISH EAST	WALL FINISH WEST	KEY NOTES
001	ENTRY VESTIBULE	C-2	TL-1	WC-1	WC-1	WC-1	WC-1	
002	CHECK-IN	TL-1		P-1	P-1	P-1	P-1	2
003	WAITING	C-1/TL-1		P-1	P-1	P-1	P-1	2
004	CORR.	C-1	B-1	P-1	P-1	P-1	P-1	
005	FAMILY TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
006	PATIENT TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
007	CORR.	LVT-1/LVT-2	B-1	P-1	P-3	P-1	P-1	11
008	CUST SERVICE	C-1	B-1	P-1	P-1	P-5	P-1	
009	CORR.	LVT-2	B-1	P-1	P-1	P-1	P-1	11
010	STOR.	LVT-1	B-1	P-1	P-1	P-1	P-1	
011	JAN	LVT-1	B-1	P-1	P-1	P-1	P-1	
012	CLERICAL SUPER.	C-1	B-1	P-1	P-1	P-5	P-1	
013	RECEPTION	LVT-1	B-1	P-1	P-1	P-1	P-1	
014	CHECK-OUT	LVT-1	B-1	P-3	P-1	P-1	P-1	
015	CORR.	LVT-2	B-1	P-1	P-1	P-1	P-1	11
016	VSO REP. OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
017	ADMIN OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
018	ADMIN OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
019	WAITING	C-1/TL-1	B-1	P-1	P-1	P-1	P-1	2
020	MULTI-PURPOSE	C-1	B-1	P-1	P-5	P-1	P-1	
021	CORR.	C-1	B-1	P-1	P-1	P-1	P-1	
022	FAMILY TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
023	PATIENT TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
024	CORR.	LVT-1/2/3	B-1	P-1	P-1/P-3	P-1	P-1	11
025	ADMIN OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
026	CORR.	LVT-1/LVT-2	B-1	P-1/P-5	P-1	P-1	P-1	11
027	R.N.	LVT-1	B-1	P-1	P-1	P-1	P-4	
028	SHARED LPN OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
029	MD OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
030	SUP.	LVT-1	B-1	P-1	P-1	P-1	P-1	
031	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-4	P-1	6
032	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-4	6
033	P.C./M.H. OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
034	GROUP CONFERENCE	C-1	B-1	P-1	P-5	P-1	P-1	
035	CORR.	LVT-1/2/3	B-1	P-1	P-1	P-1	P-1/P-3	11
036	PATIENT TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
037	CORR.	LVT-1/LVT-2	B-1	P-1/P-5	P-1	P-1	P-1	11
038	R.N.	LVT-1	B-1	P-1	P-1	P-1	P-4	
039	TELERETINAL EYE	LVT-1/LVT-2	B-1	P-1	P-1	P-4	P-1	6
040	MD OFFICE	LVT-1	B-1	P-1	P-1	P-5	P-1	
041	SUP.	LVT-1	B-1	P-1	P-1	P-1	P-1	
042	SOCIAL WORKER	LVT-1	B-1	P-1	P-1	P-5	P-1	
043	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-4	P-1	6
044	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-4	6
045	CORR.	LVT-1	B-1	P-1	P-3	P-1	P-1	11
046	GROUP ROOM	C-1	B-1	P-1	P-5	P-1	P-1	
047	CORR.	LVT-1/LVT-2	B-1	P-1	P-1/P-5	P-1	P-1	11
048	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-4	6
049	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-4	P-1	6
050	DIETICIAN OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
051	SUP.	LVT-1	B-1	P-1	P-1	P-1	P-1	
052	SOCIAL WORKER	C-1	B-1	P-1	P-1	P-5	P-1	
053	MD OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
054	R.N.	LVT-1	B-1	P-1	P-1	P-1	P-4	
055	CLEAN UTILITY	WSF-1	WSF-1	P-1	P-1	P-1	P-1	10
056	CORR.	LVT-1	B-1	P-1	P-1	P-1	P-1	11
057	SHARED OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
058	STRETCHER ROOM	WSF-1	WSF-1	P-1	P-1	P-4	P-1	
059	ELECTRICAL	LVT-1	B-1	P-1	P-1	P-1	P-1	
060	BIO.	WSF-1	WSF-1	P-1	P-1	P-1	P-1	10
061	SOILED UTILITY	WSF-1	WSF-1	P-1	P-1	P-1	P-1	10
062	C.C.H.T. OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
063	CORR.	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-1	11
064	M.H. OFFICE	LVT-1	B-1	P-1	P-1	P-5	P-1	
065	M.H. OFFICE	LVT-1	B-1	P-1	P-1	P-1	P-5	
066	M.H. OFFICE	LVT-1	B-1	P-1	P-1	P-1	P-5	
067	M.H. OFFICE	LVT-1	B-1	P-1	P-1	P-5	P-1	
068	CORR.	LVT-1/2/3	B-1	P-1	P-1	P-1/P-3	P-1	11
069	LPN	LVT-2	B-1	P-1	P-1	P-1	P-1	11
070	OMNI CELL	LVT-1	B-1	P-1	P-1	P-1	P-1	
071	TELE MED	LVT-1	B-1	P-1	P-4	P-1	P-1	
072	TAP	LVT-1	B-1	P-1	P-1	P-1	P-1	
073	MEDICATION	LVT-1	B-1	P-1	P-1	P-1	P-1	
074	PATIENT TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
075	CORR.	LVT-1/LVT-2	B-1	P-1	P-3	P-1	P-1	11
076	SUPPLY	LVT-1	B-1	P-1	P-1	P-1	P-1	
077	OFFICE	C-1	B-1	P-1	P-1	P-3	P-1	
078	SUBWAIT	LVT-1/LVT-3	B-1	P-1	P-1	P-1	P-1	
079	LAB/RAD. CHECK-IN	LVT-2	B-1	P-1	P-1	P-1	P-1	
080	BLOOD DRAW	LVT-1	B-1	P-4	P-1	P-1	P-1	
081	PATIENT TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
082	LAB	LVT-1	B-1	P-1	P-1	P-1	P-1	
083	RADIOLOGY	LVT-1	B-1	P-1	P-1	P-1	P-1	
084	PATIENT TOILET	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
085	SUP.	LVT-1	B-1	P-1	P-1	P-1	P-1	
086	CORR.	LVT-1	B-1	P-3	P-1	P-1	P-1	11
087	EYE EXAM	LVT-1	B-1	P-1	P-1	P-1	P-1	
088	EYE DISP.	LVT-1	B-1	P-1	P-1	P-4	P-1	
089	EYE EXAM	LVT-1	B-1	P-1	P-1	P-1	P-1	
090	VISUAL FIELD	LVT-1	B-1	P-1	P-1	P-1	P-1	
092	PHYSICAL THERAPY	LVT-1/2	B-1	P-1	P-4	P-1	P-1	
093	SUPPLY	LVT-1	B-1	P-1	P-1	P-1	P-1	
095	OPERATORY	LVT-1	B-1	P-1	P-1	P-3	P-1	
096	OPERATORY	LVT-1	B-1	P-1	P-4	P-1	P-4	
097	CORR.	LVT-1	B-1	P-1	P-4	P-1	P-1	11
098	DENTIST OFFICE	LVT-1	B-1	P-1	P-1	P-1	P-4	
099	LAB	LVT-1	B-1	P-1	P-1	P-1	P-1	
100	CORR.	LVT-1/2/3	B-1	P-1	P-1	P-1	P-1/P-3	11
101	ADMIN OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
102	NURSE WORK	LVT-3	B-1	P-1	P-3	P-1	P-1	
103	CORR.	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-1	11
104	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-4	P-1	6
105	EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-4	6
106	STOR.	LVT-1	B-1	P-1	P-1	P-1	P-1	
107	MD OFFICE	C-1	B-1	P-1	P-1	P-1	P-5	
108	SHARED OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
109	CORR.	LVT-1/LVT-2	B-1	P-1	P-1	P-3	P-1	11
110A	EQUIP.	LVT-1	B-1	P-1	P-1	P-1	P-1	
110B	NITRO.	LVT-1	B-1	P-1	P-1	P-1	P-1	
111	TAP ROOM	LVT-1	B-1	P-1	P-1	P-1	P-1	
112	CORR.	LVT-1	B-1	P-3	P-1	P-1	P-1	11
113	PATIENT TLT.	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
114	PATIENT TLT.	TL-2	B-2	P-1/TL-3	P-1/TL-3	P-1/TL-3	P-1/TL-3	1, 4
115	SUPPLY	LVT-1	B-1	P-1	P-1	P-1	P-1	
116	CORR.	LVT-1/LVT-2	B-1	P-1	P-1	P-1	P-1	11

FINISH SCHEDULE- CBOC

ROOM NUMBER	ROOM NAME	FLOOR	BASE	WALL FINISH NORTH	WALL FINISH SOUTH	WALL FINISH EAST	WALL FINISH WEST	KEY NOTES
117	AUDIO							3
118	CONTROL							3
119	CONTROL							3
120	AUDIO							3
121	AUDIOLOGY EXAM	LVT-1/LVT-2	B-1	P-1	P-1	P-4	P-1	
122	CLINICAL PSY.	C-1	B-1	P-1	P-1	P-1	P-5	
123	HBPC OFFICE	C-1	B-1	P-5	P-1	P-1	P-1	
124	ADMIN OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
125	HBPC DIRECTOR OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
126	SHARED OFFICE	C-1	B-1	P-1	P-1	P-5	P-1	
127	CORR.	LVT-1	B-1	P-1	P-1	P-1	P-1	
128	PROSTHETIC STOR.	LVT-1	B-1	P-1	P-1	P-1	P-1	
129	POD. STER. SUPPLY	LVT-1	B-1	P-1	P-1	P-1	P-1	
130	POD. EXAM	LVT-1/LVT-2	B-1	P-1	P-4	P-1	P-1	6
131	POD. EXAM	LVT-1/LVT-2	B-1	P-4	P-1	P-1	P-1	6
132	CORR.	LVT-1	B-1	P-1	P-5	P-1	P-1	
133	SOILED UTILITY	LVT-1	B-1	P-1	P-1	P-1	P-1	10
134	CLEAN UTILITY	WSF-1	WSF-1	P-1	P-1	P-1	P-1	10
135	STORAGE	LVT-1	B-1	P-1	P-1	P-1	P-1	
136	I.T.	LVT-1	B-1	P-1	P-1	P-1	P-1	
137	HK	WSF-1	WSF-1	P-1	P-1	P-1	P-1	10
138	ARMORY	LVT-1	B-1	P-1	P-1	P-1	P-1	
139	BREAK	LVT-1/LVT-2	B-1	P-1	P-3	P-1	P-1	
140	LOCKERS	LVT-1	B-1	P-1	P-1	P-1	P-1	
141	MECH	LVT-1	B-1	P-1	P-1	P-1	P-1	
142	STAFF TLT.	TL-2	B-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	1, 4
143	STAFF TLT.	TL-2	B-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	1, 4
144	LOCKERS	LVT-1	B-1	P-1	P-1	P-1	P-1	
145	MECH	LVT-1	B-1	P-1	P-1	P-1	P-1	
146	STAFF TLT.	TL-2	B-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	1, 4
147	STAFF TLT.	TL-2	B-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	P-1/TL-2	1, 4
148	WATER/SPRINKLER	LVT-1	B-1	P-1	P-1	P-1	P-1	
149	CORR.	C-1	B-1	P-1	P-1	P-1	P-1	
150	AUD. WORK	C-1	B-1	P-1	P-1	P-1	P-1	
151	SUPPLY	LVT-1	B-1	P-1	P-1	P-1	P-1	
152	STER.	LVT-1	B-1	P-1	P-1	P-1	P-1	
153	SCLURS	LVT-2	B-1	P-1	P-1	P-1	P-1	
154	CORR.	LVT-1/2/3	B-1	P-1	P-1	P-1	P-1	11

FINISH LEGEND

MISCELLANEOUS FINISHES (CONTINUED)

WALL PROTECTION

INPRO CORP. BIOPOLYPETG#(G2-SERIES) ITEM #G2405 - .040" THICK, 4' X 8', G2401 - 8' TOP CAP. COLOR: OATMEAL.

FLOORING

CARPET

C-1 SHAW CONTRACT: 24" X 24" CARPET TILE: REED-59523. COLOR: SWEET CLOVER 23309; 1/4 TURNED. 21.7% PRE-CONSUMER, 12% POST-CONSUMER RECYCLED CONTENT.

C-2 MATS INC. WALK OFF MAT. NUWAY: SEM RECESSED INSTALLATION UPPER STRIPS-CHARCOAL; ALUMINUM SCRAPER BARS.

LUXURY VINYL TILE

LVT-1 CENTIVA RAYS, COLOR: FE-0784-C AMBER, SURFACE: FROST, 31% PRE-CONSUMER, 6% POST CONSUMER RECYCLED CONTENT, 12" X 12" STANDARD EDGE.

LVT-2 CENTIVA SIGMA, COLOR: FE-0718-C PURE, SURFACE: FROST, 31% PRE-CONSUMER, 6% POST-CONSUMER RECYCLED CONTENT, 12" X 12", STANDARD EDGE.

LVT-3 CENTIVA VICTORY-MAGICS, COLOR: MG-8043-V JASPER, SLATE SURFACE, 12" X 12", STANDARD EDGE.

LVT-4 AMTICO, W731 WILD CHERRY.

PORCELAIN & CERAMIC TILE

GROUT LINES SHALL BE 1/8" UNLESS NOTED OTHERWISE. LATICRETE GROUT, COLOR: 516 DESERT KHAKI. GROUT & SEALANT TYPE AS RECOMMENDED BY MANUFACTURER.

TL-1 SPECIALITY TILE PRODUCTS: RAGNO, STYLE: ARTE, COLOR: BG- 12" X 24" TILE (10.8% RECYCLED CONTENT)

TL-2 SPECIALITY TILE PRODUCTS: FLORIM USA, STYLE: WISH, COLOR: IVORY - 12" X 12" TILE (40% PRE CONSUMER RECYCLED CONTENT)

TL-3 SPECIALITY TILE PRODUCTS: FLORIM USA, STYLE: WISH, COLOR: IVORY - 6" X 6" TILE (40% PRE CONSUMER RECYCLED CONTENT)- WALL TILE

TL-4 SPECIALITY TILE PRODUCTS: FLORIM USA, STYLE: ANTELOPE CANYON, COLOR: MESA- 2" X 2" MOSAIC- (40% PRE CONSUMER RECYCLED CONTENT)- WALL TILE AT KITCHEN BACKSPLASH-GLC

NATURAL STONE TILE

NTL-1 DACO STONE 2'-0"X2'-0"X2" HONED FINISH NATURAL STONE PAVER SET IN AT MORTAR BED

NTL-2 DACO STONE 2'-0"X2'-0"X3" HONED FINISH NATURAL STONE PAVER SET IN AT MORTAR BED

HEAT WELDED SHEET FLOORING

WSF-1 MANNINGTON ASSURANCE II- COLOR: WASABI 16321. HEAT WELD SEAMS. USE V-82 ADHESIVE.

COVE BASE

B-1 JOHNSONITE 4" RUBBER BASE. COLOR: 66 EITHER ORE. 14% PRE-CONSUMER RECYCLED CONTENT.

B-2 TILE TO EXTEND TO FLOOR.

B-3 JOHNSONITE REVEAL 4.25" MILLWORK BASE. COLOR: 66 EITHER ORE. 14% PRE-CONSUMER RECYCLED CONTENT.

B-4 WSF-1 FLASH COVE 4" MIN. HEAT WELD SEAMS.

B-5 4" PLASTIC LAMINATE BASE (PL-1) SEE DETAIL 1 ON SHEET A5.13.

TR RESILIENT TRANSITION STRIP, MATCH BASE COLOR.

WALLS

PAINT

MINIMUM ONE (1) PRIMER COAT AND TWO (2) FINISH COATS AS RECOMMENDED BY MANUFACTURER.

P-1 BENJAMIN MOORE ECOSPEC INTERIOR LATEX EGGSHELL. COLOR: OC-96 GENTLE CREAM FIELD PAINT

P-2 BENJAMIN MOORE ECOSPEC UB INTERIOR LATEX SEMI-GLOSS. COLOR: TO MATCH SHERWIN WILLIAMS SW 6102 PORTABELLO. TRIM PAINT

P-3 BENJAMIN MOORE ECOSPEC INTERIOR LATEX EGGSHELL. COLOR: HC-110 WETHERSFIELD MOSS ACCENT PAINT

P-4 BENJAMIN MOORE ECOSPEC INTERIOR LATEX EGGSHELL. COLOR: HC-145 VAN COURTLAND BLUE ACCENT PAINT

P-5 BENJAMIN MOORE ECOSPEC INTERIOR LATEX EGGSHELL. COLOR: AC-5 SPRINGFIELD TAN ACCENT PAINT

P-6 BENJAMIN MOORE ECOSPEC INTERIOR LATEX FLAT. COLOR: HC-92 WHEELING NUETRAL SOFFIT PAINT.

WALLCOVERING

WC-1 EYKON TOWER WALLCOVERING WITH RECORE; STYLE: TRAPPING; COLOR: TARRAGON; TYPE II WITH 25% RECYCLED CONTENT.

AT ANY LOCATION WHERE WALLCOVERING ENDS AT AN OUTSIDE CORNER, APPLY SPECTRUM CORNER PROTECTORS, ST-200 AVAILABLE THROUGH SPECTRUM WALLCOVERINGS, T 770-454-8737.

MISCELLANEOUS FINISHES

PLASTIC LAMINATE

PL-1 WILSONART; AMBER CHERRY 7918-38 SHALL BE APPLIED TO ALL VERTICAL SURFACES UNLESS OTHERWISE NOTED. 20% POST-CONSUMER RECYCLED CONTENT.

PL-2 PIONITE; GRIDLOCK IN L.A. PFA81 SUEDE. SHALL BE APPLIED TO ALL HORIZONTAL SURFACES UNLESS OTHERWISE NOTED.

PL-3 NEVAMAR; PAINTED WOODLANDS PDG3027. SHALL BE APPLIED TO HORIZONTAL SURFACES AS NOTED.

SOLID SURFACE

SS-1 CORIAN; RICE PAPER. SEMI-POLISHED FINISH. BASED EDGE. SHALL BE APPLIED TO RECEPTION/NURSE STATION DESKS AS NOTED. 13% PRE CONSUMER RECYCLED CONTENT.

SS-2 ZODIAQ; MOSSY GREEN. BASED EDGE. SHALL BE APPLIED TO HORIZONTAL SURFACES IN CLC. 25% POST CONSUMER RECYCLED CONTENT.

MOULDINGS

CM-1 COVE-MOULD. SEE DETAIL 1, SHEET A5.14

CUBICLE CURTAINS

MESH (8%) INPRO CORPORATION; EZE-MESH. COLOR: TUSK. TRACK: INPRO CORPORATION; ULTRA CUBE CUBICLE TRACK WITH GES2208 CARRIER.

CC-1 MAHARAM; POSY BI4420. COLOR: 003 PLACID. 38% POST-CONSUMER RECYCLED CONTENT.

CORNER & END GUARD

CG CORNER GUARD, INPRO CORP. BIOPOLY PETG+ (G2 SERIES) ITEM # G2CSF - 3' X 3' X 90 DEGREE. COLOR: OATMEAL. PROVIDE FIRE RATED GUARD ON FIRE RATED WALLS. ITEM # G2BSFR1 - 3' X 3' X 90 DEGREE. REFER TO THE REFERENCE PLANS FOR WALL TYPES.

EG END GUARD, INPRO CORP. BIOPOLY PETG+ (G2 SERIES) ITEM # G2148D - 8', FLUSH-MOUNT END WALL PROTECTOR. COLOR: OATMEAL.

HANDRAIL; INPRO CORP. HR8 NORTHERN HARDWOODS HANDRAIL. COLOR TBD.



1 / A5.13 P-LAM BASE DETAIL

SCALE: 3/4" = 1'-0"

KEY NOTES

1. INSTALL TL-3 TO 4'-0" AFF. SEE DETAIL 3, SHEET A5.10
2. BASE & WALLS TO HAVE PLASTIC LAMINATE PANELING.
3. ROOMS TO COME PRE-FINISHED WITH FLOORING AND WALL FINISHES FROM MANUFACTURER.
4. SEE DETAIL 5, SHEET A5.10 FOR FLOOR TILE PATTERN.
5. ROOM TO RECEIVE COVE MOULDING, CM-1. SEE DETAIL 1, SHEET A5.14.
6. SEE DETAIL 2, SHEET A5.10 FOR FLOOR PATTERN.
7. INSTALL TL-3 TO 4'-0" AFF WITH 3" X 12" BULLNOSE TRIM PIECE AROUND SHOWER. INSTALL TL-3 TO CEILING. SEE ELEVATIONS 2-6 ON SHEET A5.11
8. INSTALL TL-4 ON ENTIRE WALL BEHIND STOVE FROM COUNTERTOP TO UNDERSIDE OF UPPER CABINETS.
9. USE BENJAMIN MOORE #532 AURA BATH & SPA MATTE FLAT FINISH PAINT IN THIS LOCATION.
10. USE BENJAMIN MOORE #538 AURA SEMI-GLOSS INTERIOR PAINT IN THIS LOCATION.
11. INSTALL WALL PROTECTION TO 4'-0" AFF IN THIS AREA. SEE FINISH PLAN FOR EXACT LOCATIONS.

PEACOCK ARCHITECTS
2000 RIVEREDGE PARKWAY
SUITE SEVEN HUNDRED
ATLANTA GEORGIA 30328
404-214-5200 PHONE
404-214-5208 FAX

TRINKA DAVIS VETERAN'S VILLAGE
CARROLLTON, GA 30117

STATE OF GEORGIA
H. DEAN PEACOCK
CERTIFICATE NO. 8000
REGISTERED ARCHITECT

DATE	REVISION
02/21/11	ISSUE FOR BID
03/18/11	ADDENDUM 3

PROJECT NO: 1228.01.00

DATE: 02/21/11

DRAWING TITLE: FINISH SCHEDULE & LEGEND - CBOC

A5.13

THIS DRAWING AND ANY REPRODUCTIONS ARE THE PROPERTY AND COPYRIGHT OF PEACOCK ARCHITECTS, INC. AND MAY NOT BE USED IN ANY MANNER WITHOUT THE EXPRESSED WRITTEN PERMISSION OF THE COPYRIGHT OWNER.

teamwork://designserver/TDVV DD SET