

ADDENDUM NO. 1:

Date: February 6, 2026
Project: Verbena Elementary School Classroom, Kitchen and Gym Additions
DCM# 2025552

Owner: Chilton County Board of Education
Architect: Ward Scott Morris Architecture, Inc.

BID DATE: February 10, 2026
BID TIME: 2:30 PM Local Time
BID LOCATION: Chilton County Board of Education, 1705 Lay Dam Road



This Addendum forms a part of the Contract Documents and modifies the original Bid Documents dated January 14, 2026, as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Proposal Form.

1.1 SPECIFICATIONS:

- A. Section 105300; Metal Walkway Covers; Para 2.5.d.1; change finish to 2-coat kynar finish.
- B. Section 105300; Metal Walkway Covers; Para 2.2.B.1.a; change roof panels to preformed "W" shape in lieu of roll-formed.
- C. Section 105300; Metal Walkway Covers; clarification canopy deck is to run perpendicular to sidewalk.


1.2 DRAWINGS:

- A. Sheet C301; clarification; Gravel Drive Patching for utility crossing existing gravel drive shall be per the following:
 - 1. Backfill around the utility piping shall be as required by the utility trench details.
 - 2. Backfill above utility piping can be approved soils removed as part of trench excavation. Soils must be placed in maximum 8" lifts compacted to 98% SPD.
 - 3. As part of the initial trench excavation, the contractor shall cast to the side of the trench and stockpile the top 12" of the existing gravel roadway build up. Upon completion of the utility installation and backfill of the trench as described above, the remaining +/- 12" of the trench shall be backfilled and compacted flush with the existing grade with the noted roadway stockpile material.
- B. Sheet A401; Roof Plan; Detail 2/A401; clarification Kitchen canopy (metal/alum) is as specified in section 105300.
- C. Sheet E300, General Auxiliary Notes; Delete reference to the \$15,000 allowance for the BDA system adjustment.
- D. Mechanical Sheets M001, M103; See attached addendum no. 1 on Smith, Stegall & Assoc. letterhead dated 2/5/26.

ATTACHED TO ADDENDUM

Addendum #1 – Smith Stegall & Assoc.
END OF ADDENDUM

ADDENDUM No.1



Smith, Stegall & associates p.c.

Consulting Engineers

2110 Eighth Street, Tuscaloosa, AL 35401

Phone/Fax 205 345 4402

PROJECT:

**Verbena Elementary School
DCM #202552**

ENG JOB #

2560

ARCH JOB #

25-060

DATE:

February 5, 2026

HVAC:

1. **Sheet M001 equipment schedule:** Delete control panel from schedule.
2. **Sheet M103 mezzanine:** Delete control panel from plan.
3. **Sheet M001 equipment schedule:** FCU #9 and HP #9 to be 6 tons same as FCU #10

END OF ADDENDUM



2-5-26